

APPENDIX A

Additional Photos of Flooding in Pembroke

Additional Flooding Photos



2017



2017



2017



2003 Doran Street and D'Arcy Street Intersection




2003 Doran Street and D'Arcy Street Intersection

APPENDIX B

Floodlines for the 100-year Ottawa River Flow Event




Scale 1: 5,000




Hoffman Lane Residences



Flood Elevation of 113.90


May 8, 2019




Scale 1: 1,000










Scale 1: 500






Scale 1: 2,000





Scale 1: 2,000





Scale 1: 1,000




Nelson Street Residences

Flood Elevation of 113.90

May 8, 2019




Scale 1: 500




Cedar Lane Residences

Water Elevation of 113.90

May 8, 2019



Scale 1: 1,000



APPENDIX C

Details of the Hydrological Model Inputs, Setup, Calibration, and Results

Table C.1: Summary of Channel Slope Variation

Chainage (US to DS)	Average Channel Slope (m/m)
Indian River	
0 m - 5,100 m	0.03140
5,100 m – 58,050 m	0.00199
58,050 m – 74,830 m	0.00058
Muskrat River (main branch)	
0 m – 6,350 m	0.01229
6,350 m - 30,590 m	0.00275
30,590 m - 39,430 m (Doré Lake and marshes)	0.00001
39,430 m - 56,040 m	0.00107
56,040 m - 92,090 m (Muskrat Lake and marshes)	0.00005
92,090 m - 97,990 m	0.00193
97,990 m - 99,060 m	0.00021




Figure C.1: IDF Curves for the Muskrat Watershed




Figure C.2: Hyetograph for the 2-yr, 12-hr AES 30% Design Storm for Southern Ontario




Figure C.3: Hyetograph for the 5-yr, 12-hr AES 30% Design Storm for Southern Ontario




Figure C.4: Hyetograph for the 10-yr, 12-hr AES 30% Design Storm for Southern Ontario




Figure C.5: Hyetograph for the 25-yr, 12-hr AES 30% Design Storm for Southern Ontario




Figure C.6: Hyetograph for the 50-yr, 12-hr AES 30% Design Storm for Southern Ontario




Figure C.7: Hyetograph for the 100-yr, 12-hr AES 30% Design Storm for Southern Ontario

Table C.2: Subbasin Properties and Inputs

Subbasin ID	Area (km ²)	Slope (m/m)	Initial Abstraction (mm)	Composite CN, Summer	Composite CN, Winter	Impervious Surface (%)	Lag Time (min)
Sub-1	1.27	0.06062	4.93	75.32	92.83	29.53	12.01
Sub-2	21.72	0.08698	9.77	50.87	76.96	5.36	412.00
Sub-3	40.65	0.05361	8.94	54.39	80.38	2.07	112.43
Sub-4	22.36	0.07521	9.25	50.01	76.69	7.09	1242.88
Sub-5	10.01	0.03300	10.12	58.20	83.10	0.39	699.02
Sub-6	17.97	0.08296	9.60	47.55	74.51	3.65	111.30
Sub-7	35.79	0.10260	9.65	52.90	79.27	4.10	197.22
Sub-8	32.74	0.04006	9.27	51.67	78.08	3.46	266.39
Sub-9	30.80	0.08219	8.85	51.79	77.99	13.11	2379.30
Sub-10	30.54	0.02353	8.59	54.08	80.03	1.08	146.18
Sub-11	88.93	0.06744	9.23	50.80	77.23	8.13	3989.40
Sub-12	77.23	0.02569	8.61	56.43	81.65	1.59	551.22
Sub-13	23.95	0.02535	8.38	56.93	82.52	1.43	589.11
Sub-14	24.89	0.06158	9.37	47.50	74.48	1.43	894.19
Sub-15	79.30	0.04183	7.13	50.77	77.37	21.49	6651.30
Sub-16	100.68	0.04928	8.10	45.04	72.06	13.73	7776.00
Sub-17	83.29	0.02981	8.22	54.46	80.05	7.45	4848.60
Sub-18	61.07	0.08993	9.04	53.30	79.93	10.16	5153.70
Sub-19	17.37	0.09233	9.58	52.43	79.08	4.54	908.25
Sub-20	34.80	0.02951	8.74	53.96	79.99	1.92	819.72
Sub-21	2.07	0.07256	9.46	47.13	74.76	1.00	134.64
Sub-22	4.00	0.06161	8.82	46.32	73.66	1.21	90.93
Sub-23	117.00	0.10881	9.61	53.16	79.85	4.64	1504.50
Sub-24	3.61	0.10505	9.79	50.09	77.13	0.85	139.59
Sub-25	24.37	0.06097	9.40	53.89	80.53	5.57	4533.90
Sub-26	31.66	0.03408	8.73	48.83	75.32	1.36	263.06
Sub-27	4.97	0.03193	5.84	63.21	85.86	15.44	215.97
Sub-28	35.88	0.02489	8.34	53.54	79.60	0.37	155.82
Sub-29	16.55	0.04056	9.79	57.65	82.82	1.85	706.48
Sub-30	23.76	0.05223	8.57	49.57	75.54	13.40	2538.90
Sub-31	18.07	0.02208	7.97	59.83	84.49	2.81	2312.40
Sub-32	2.62	0.03152	5.48	70.23	89.81	25.77	36.70
Sub-33	23.91	0.02760	7.59	58.62	83.38	0.97	363.48

Table C.3: Reach Properties

Reach ID	Length (m)	Slope (m/m)
Reach-1	1842.7	0.00045
Reach-2	4409.7	0.00046
Reach-3	11339.6	0.0002
Reach-4	11101.7	0.00046
Reach-5	2639.0	0.0008
Reach-6	1125.8	0.00061
Reach-7	6126.0	0.00042
Reach-8	3456.3	0.0005
Reach-9	4316.9	0.00185
Reach-9-1	1176.1	0.00016
Reach-9-2	3511.9	0.00302
Reach-10	1914.6	0.0011
Reach-11	7955.3	0.0001
Reach-12	8015.9	0.00001
Reach-12-1	4028.5	0.00001
Reach-13-1	2094.0	0.00001
Reach-13-2	2507.0	0.00001
Reach-14	6480.1	0.00002
Reach-15	8065.5	0.00048
Reach-15-1	8728.2	0.00006
Reach-16-1	11148.2	0.00125
Reach-17	6929.7	0.00033




Figure C.8: Doré Lake Elevation-Storage Curve




Figure C.9: Muskrat Lake Elevation-Storage Curve




Figure C.10: Doré Lake Outlet 8-Point Cross-Section




Figure C.11: Muskrat Lake Outlet 8-Point Cross-Section




Figure C.12: Comparison of the Measured and Calibrated Model Flows for the Cal-1 Event in Muskrat River




Figure C.13: Comparison of the Measured and Calibrated Model Flows for the Cal-1 Event in Indian River




Figure C.14: Comparison of the Measured and Calibrated Model Flows for the Cal-2 Event in Muskrat River




Figure C.15: Comparison of the Measured and Calibrated Model Flows for the Cal-2 Event in Indian River




Figure C.16: Comparison of the Measured and Calibrated Model Flows for the Cal-3 Event in Muskrat River




Figure C.17: Comparison of the Measured and Calibrated Model Flows for the Cal-3 Event in Indian River

**Table C.4: Variation in SCS Curve Number based on Antecedent Moisture Conditions
 (from CLOCA, 2017)**

Dry Conditions	Average Conditions	Wet Conditions
100	100	100
97	99	100
94	98	99
91	97	99
89	96	99
87	95	98
85	94	98
83	93	98
81	92	97
80	91	97
78	90	96
76	89	96
75	88	95
73	87	95
72	86	94
70	85	94
68	84	93
67	83	93
66	82	92
64	81	92
63	80	91
62	79	91
60	78	90
59	77	89
58	76	89
57	75	88
55	74	88
54	73	87
53	72	86
52	71	86
51	70	85
51	69	85
48	68	84
47	67	83
46	66	82
45	65	82
44	64	81
43	63	80
42	62	79
41	61	78

City-Wide Flood Risk Assessment and Storm Outlet Review
 City of Pembroke

Dry Conditions	Average Conditions	Wet Conditions
40	60	78
39	59	77
38	58	76
37	57	75
36	56	75
35	55	74
34	54	73
33	53	72
32	52	71
31	51	70
31	50	70
30	49	69
29	48	68
28	47	67
27	46	66
26	45	65
25	44	64
25	43	63
24	42	62
23	41	61
22	40	60
21	39	59
21	38	58
20	37	57
19	36	56
18	35	55
18	34	54
17	33	53
16	32	52
16	31	51
15	30	50
12	25	43
9	20	37
6	15	30
4	10	22
2	5	13
0	0	0

Table C.5: Calibrated CN Values for Average Antecedent Moisture Conditions (AMC I)

Land use	A	B	C	D
Woods*	21	44	58	64
Meadows	21	45	58	64
Cultivated*	31	39	46	51
Lawns	30	51	62	68
Dirt Lot	53	66	73	76
Gravel Lot	58	70	76	80
Bedrock	63	63	63	63
Bog	4	4	4	4
Fen	4	4	4	4
Marsh	31	31	31	31
Swamp	16	40	54	62

*Calibrated values

Table C.6: Calibrated CN Values for Average Antecedent Moisture Conditions (AMC II)

Land use	A	B	C	D
Woods*	39	64	76	81
Meadows	38	65	76	81
Cultivated*	50	59	66	69
Lawns	49	69	79	84
Dirt Lot	72	82	87	89
Gravel Lot	76	85	89	91
Bedrock	80	80	80	80
Bog	10	10	10	10
Fen	10	10	10	10
Marsh	50	50	50	50
Swamp	32	60	73	79

*Calibrated values

Table C.7: Calibrated CN Values for Average Antecedent Moisture Conditions (AMC III)

Land use	A	B	C	D
Woods*	59	81	89	92
Meadows	58	82	89	92
Cultivated*	70	77	82	85
Lawns	69	85	91	93
Dirt Lot	86	92	95	96
Gravel Lot	89	94	96	97
Bedrock	91	91	91	91
Bog	22	22	22	22
Fen	22	22	22	22
Marsh	70	70	70	70
Swamp	52	78	87	91

*Calibrated values

Table C.8: Calibrated CN Values for Moderately Dry Antecedent Moisture Conditions (Between AMC I and II)

Land use	A	B	C	D
Woods*	30	54	67	72.5
Meadows	29.5	55	67	72.5
Cultivated*	40.5	49	56	60
Lawns	39.5	60	70.5	76
Dirt Lot	62.5	74	80	82.5
Gravel Lot	67	77.5	82.5	85.5
Bedrock	71.5	71.5	71.5	71.5
Bog	7	7	7	7
Fen	7	7	7	7
Marsh	40.5	40.5	40.5	40.5
Swamp	24	50	63.5	70.5

*Calibrated values

Table C.9: Summer Peak Flows under the 2-yr, 5-yr, 10-yr, 25-yr, 50-yr, and 100-yr Events

Junction ID	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
Jun-1	24.9	45.8	63.6	89.7	111.2	132.3
Jun-2	25.1	46.2	64	90.2	111.7	132.9
Jun-3	16.9	30	40.3	54.5	67.8	85.1
Jun-4	10.7	19.2	26.4	36.6	45.5	55.1
Jun-5	10.7	19.2	26.4	36.6	45.4	54.8
Jun-6	10.1	18.4	25.4	35.4	44	53.1
Jun-7	9.8	17.2	23.1	31.2	37.9	44.9
Jun-8	9.4	16.5	22	29.7	36.1	42.6
Jun-9	3.5	6	8	10.7	13	15.3
Jun-9-1	3.5	6	8	10.7	12.9	15.3
Jun-9-2	3.3	5.6	7.5	10.1	12.2	14.5
Jun-10	13.7	21.3	27.3	35.6	42.5	49.7
Jun-11	10.6	17.9	24.6	35.1	44.4	54.4
Jun-12	10.8	17.7	23.6	31.9	39.1	46.6
Jun-13	15.6	25.3	33	43.7	52.6	61.7
Jun-14	6.3	8.4	10.1	12.3	14.2	16.1
Jun-15	7.1	10.2	13.3	18.9	24.3	30.6
Jun-16	8.4	15.1	20.4	27.8	34	40.4
Jun-17	12.4	25.8	38	57.4	72.3	87.5
Jun-18	13.2	20.1	25.6	33.3	39.7	46.3
Jun-19	3.5	3.5	3.5	3.9	4.2	4.6
Jun-20	9.1	13.5	17.6	23.7	29.2	35.1
Jun-21	8.9	13	16.9	22.8	28.1	33.9
Jun-22	6.3	8.4	10.1	12.3	14.2	16.1

Table C.10: Winter Peak Flows under the 2-yr, 5-yr, 10-yr, 25-yr, 50-yr, and 100-yr Events

Junction ID	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
Jun-1	57.2	105.4	139.1	183.7	219.9	256.1
Jun-2	57.7	105.9	139.8	184.9	221.5	258
Jun-3	38.6	65.2	92	130.7	162.9	194.1
Jun-4	23.8	43	58.1	80	97.1	113.7
Jun-5	23.8	42.6	57.6	78.9	95.5	112
Jun-6	23	41.1	55.8	76.2	92.3	108.4
Jun-7	21.5	36.7	48	62.7	74.9	86.5
Jun-8	20.6	34.9	45.6	59.4	70.4	81.4
Jun-9	7	11.9	15.6	20.5	24.4	28.3
Jun-9-1	7	11.9	15.6	20.5	24.4	28.3
Jun-9-2	6.5	11.3	14.8	19.5	23.2	27
Jun-10	25.2	40.9	52.6	67.7	79.8	91.8
Jun-11	21.8	41.5	57.6	79.3	97	115.1
Jun-12	21.2	36.8	48.8	64.7	77.5	90.3
Jun-13	30.9	50.8	65.5	84.4	99.5	114.5
Jun-14	8.3	12.1	15	18.8	21.8	24.8
Jun-15	9.5	19.8	29.7	44.3	57.1	70.7
Jun-16	20.3	34.3	44.6	57.9	68.6	79.1
Jun-17	34.5	69.6	94.3	127.4	153.6	179.8
Jun-18	22.8	36.8	47.3	61.1	72.1	83.2
Jun-19	2.7	3.5	4.1	4.9	5.5	6.2
Jun-20	15.4	26.9	36.4	49.7	60.9	72.6
Jun-21	14.7	25.8	35	48	59	70.5
Jun-22	8.2	12.1	15	18.8	21.8	24.8

APPENDIX D

Hydraulic Structure Inventory Sheets

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 9, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Indian River
UTM Co-ordinates	N: 5075651 m, E: 334600 m
Street Name	Boundary Road

Structure Information

Structure Type	Bridge
Number of Cells	1
Each Cell Shape	Flat
Each Cell Material	Concrete
Each Cell Dimension in Meters (Height x Width or Diameter)	4.88 m x 26.04 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	11.55 m

Additional Information where applicable

Pier Width in Meters	
Parapet Present (Y/N)	Y
Parapet Length in Meters	38.91 m
Parapet Height in Meters	0.83 m
Skew Angle in Degrees	

Photographs

Upstream Face



Downstream Face



Additional Comments

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 10, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Indian River
UTM Co-ordinates	N: 507602 m, E: 335053 m
Street Name	Christie Street

Structure Information

Structure Type	Bridge
Number of Cells	1
Each Cell Shape	Arched
Each Cell Material	Concrete
Each Cell Dimension in Meters (Height x Width or Diameter)	6.68 m x 16.72 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	13.5 m

Additional Information where applicable

Pier Width in Meters	
Parapet Present (Y/N)	N
Parapet Length in Meters	
Parapet Height in Meters	
Skew Angle in Degrees	

Photographs

Upstream Face

Downstream Face



Additional Comments

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 11, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Indian River
UTM Co-ordinates	N: 5076270 m, E: 335449 m
Street Name	N/A, near Miller Street @ Indian Lane

Structure Information

Structure Type	Pedestrian bridge
Number of Cells	1
Each Cell Shape	Flat
Each Cell Material	Concrete
Each Cell Dimension in Meters (Height x Width or Diameter)	3.27 m x 26.44 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	1.85 m

Additional Information where applicable

Pier Width in Meters	
Parapet Present (Y/N)	N
Parapet Length in Meters	
Parapet Height in Meters	
Skew Angle in Degrees	

Photographs

Upstream Face



Downstream Face



Additional Comments

Small wingwalls present on both U/S and D/S of bridge, and on both right and left sides

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 11, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Muskrat River
UTM Co-ordinates	N: 5075177 m, E: 335730 m
Street Name	Bennett Street

Structure Information

Structure Type	Bridge
Number of Cells	3
Each Cell Shape	Flat
Each Cell Material	Concrete
Each Cell Dimension in Meters (Height x Width or Diameter)	From left to right (looking D/S), without piers: 1. 7.97 m x 13.01 m 2. 8.05 m x 14.91 m 3. 5.82 m x 13.10 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	11.86 m

Additional Information where applicable

Pier Width in Meters	1.1 m
Parapet Present (Y/N)	Y
Parapet Length in Meters	52.14 m
Parapet Height in Meters	0.9 m
Skew Angle in Degrees	

Photographs

Upstream Face

Downstream Face



Additional Comments

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 10, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Muskrat River
UTM Co-ordinates	N: 5076619 m, E: 335980 m
Street Name	Mary Street

Structure Information

Structure Type	Bridge
Number of Cells	4
Each Cell Shape	Flat
Each Cell Material	Concrete
Each Cell Dimension in Meters (Height x Width or Diameter)	From left to right (looking D/S), without piers:: 1. 5.74 m x 11.88 m 2. 9.56 m x 28.14 m 3. 9.38 m x 25.68 m 4. 9.20 m x 29.52 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	14.2 m

Additional Information where applicable

Pier Width in Meters	1.5 m
Parapet Present (Y/N)	N
Parapet Length in Meters	
Parapet Height in Meters	
Skew Angle in Degrees	25

Photographs

Upstream Face

Downstream Face



Additional Comments

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 9, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Muskrat River
UTM Co-ordinates	N: 5076939 m, E: 335946 m
Street Name	Pembroke Street W

Structure Information

Structure Type	Bridge
Number of Cells	3
Each Cell Shape	Arched
Each Cell Material	Concrete
Each Cell Dimension in Meters (Height x Width or Diameter)	Without piers: 5.49 m x 14.53 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	15.59 m

Additional Information where applicable

Pier Width in Meters	4.68 m
Parapet Present (Y/N)	Y
Parapet Length in Meters	U/S: 58.33 m D/S: 68.87 m
Parapet Height in Meters	Small "lip": 0.19 m, Additional height: 0.7 m Width: 1.20 m, Gap width: 2.58 m
Skew Angle in Degrees	

Photographs

Upstream Face

Downstream Face



Additional Comments

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 9, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Muskrat River
UTM Co-ordinates	N: 5077095 m, E: 335902 m
Street Name	Lake Street

Structure Information

Structure Type	Bridge
Number of Cells	2
Each Cell Shape	Arched
Each Cell Material	Concrete
Each Cell Dimension in Meters (Height x Width or Diameter)	Without pier: 5.51 m x 26.42 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	14.96 m

Additional Information where applicable

Pier Width in Meters	0.75 m
Parapet Present (Y/N)	N
Parapet Length in Meters	
Parapet Height in Meters	
Skew Angle in Degrees	29

Photographs

Upstream Face



Downstream Face



Additional Comments

Hydraulic Structure Data Sheet

General Information

Date (Month DD, YYYY)	November 9, 2021
Field Crew Initial	D.M., G.D.
Municipality	City of Pembroke
Watershed Name	Muskrat
Creek or Tributary Name	Muskrat River
UTM Co-ordinates	N: 5077137 m, E: 335890 m
Street Name	N/A (Old Railway Bridge)

Structure Information

Structure Type	Old Railway Bridge Converted into Pedestrian Bridge
Number of Cells	2
Each Cell Shape	Flat
Each Cell Material	Steel
Each Cell Dimension in Meters (Height x Width or Diameter)	Without pier: 5.16 m x 23.44 m
Open Footing (Y/N)	Y
Structure Length in Meters (inlet to outlet)	4.46 m

Additional Information where applicable

Pier Width in Meters	2.51 m
Parapet Present (Y/N)	Y
Parapet Length in Meters	51.95 m
Parapet Height in Meters	2.66 m
Skew Angle in Degrees	

Photographs

Upstream Face

Downstream Face



Additional Comments

Pier width estimated from photographs to be approx. equal to parapet height

APPENDIX E

HEC-RAS Model Output Results

HEC-RAS Profile: Winter 100yr

River	Reach	River Sta	Profile	Plan	Q Total (m ³ /s)	Min Ch El (m)	W.S. Elev (m)	Crit W.S. (m)	E.G. Elev (m)	E.G. Slope (m/m)	Vel Chnl (m/s)	Flow Area (m ²)	Top Width (m)	Froude # Chl
Muskrat River	Main_2	2572	Winter 100yr	Winter - 113.621m	83.00	116.61	118.88		119.13	0.002746	2.24	40.07	24.81	0.52
Muskrat River	Main_2	2572	Summer 100yr	Summer - 113.621m	46.50	116.61	118.19		118.40	0.004198	2.03	23.67	22.53	0.60
Muskrat River	Main_2	2572	Summer 100yr	Summer - 112 m	46.50	116.61	118.19		118.40	0.004198	2.03	23.67	22.53	0.60
Muskrat River	Main_2	2572	Summer 100yr	Summer - 111.082m	46.50	116.61	118.19		118.40	0.004198	2.03	23.67	22.53	0.60
Muskrat River	Main_2	2532	Winter 100yr	Winter - 113.621m	83.00	116.17	118.78	117.97	119.03	0.002215	2.26	41.85	23.11	0.49
Muskrat River	Main_2	2532	Summer 100yr	Summer - 113.621m	46.50	116.17	118.09	117.53	118.26	0.002524	1.88	26.78	20.48	0.49
Muskrat River	Main_2	2532	Summer 100yr	Summer - 112 m	46.50	116.17	118.09	117.53	118.26	0.002524	1.88	26.78	20.48	0.49
Muskrat River	Main_2	2532	Summer 100yr	Summer - 111.082m	46.50	116.17	118.09	117.53	118.26	0.002524	1.88	26.78	20.48	0.49
Muskrat River	Main_2	2521												
Muskrat River	Main_2	2506	Winter 100yr	Winter - 113.621m	83.00	116.43	118.60	117.87	118.84	0.002373	2.17	40.37	24.35	0.49
Muskrat River	Main_2	2506	Summer 100yr	Summer - 113.621m	46.50	116.43	117.89	117.47	118.08	0.003307	1.90	24.74	20.70	0.54
Muskrat River	Main_2	2506	Summer 100yr	Summer - 112 m	46.50	116.43	117.89	117.47	118.08	0.003307	1.90	24.74	20.70	0.54
Muskrat River	Main_2	2506	Summer 100yr	Summer - 111.082m	46.50	116.43	117.89	117.47	118.08	0.003307	1.90	24.74	20.70	0.54
Muskrat River	Main_2	2494	Winter 100yr	Winter - 113.621m	83.00	116.59	118.63		118.76	0.001526	1.65	53.29	34.84	0.39
Muskrat River	Main_2	2494	Summer 100yr	Summer - 113.621m	46.50	116.59	117.88		118.01	0.002878	1.59	29.62	29.56	0.49
Muskrat River	Main_2	2494	Summer 100yr	Summer - 112 m	46.50	116.59	117.88		118.01	0.002878	1.59	29.62	29.56	0.49
Muskrat River	Main_2	2494	Summer 100yr	Summer - 111.082m	46.50	116.59	117.88		118.01	0.002878	1.59	29.62	29.56	0.49
Muskrat River	Main_2	2430	Winter 100yr	Winter - 113.621m	83.00	116.37	118.56		118.67	0.001081	1.49	58.06	34.21	0.33
Muskrat River	Main_2	2430	Summer 100yr	Summer - 113.621m	46.50	116.37	117.75		117.85	0.001885	1.40	33.37	28.64	0.41
Muskrat River	Main_2	2430	Summer 100yr	Summer - 112 m	46.50	116.37	117.75		117.85	0.001884	1.40	33.37	28.64	0.41
Muskrat River	Main_2	2430	Summer 100yr	Summer - 111.082m	46.50	116.37	117.75		117.85	0.001884	1.40	33.37	28.64	0.41
Muskrat River	Main_2	2351	Winter 100yr	Winter - 113.621m	83.00	115.97	118.49		118.59	0.000923	1.51	79.63	55.08	0.32
Muskrat River	Main_2	2351	Summer 100yr	Summer - 113.621m	46.50	115.97	117.58		117.71	0.001857	1.55	33.03	39.63	0.41
Muskrat River	Main_2	2351	Summer 100yr	Summer - 112 m	46.50	115.97	117.58		117.71	0.001857	1.55	33.03	39.63	0.41
Muskrat River	Main_2	2351	Summer 100yr	Summer - 111.082m	46.50	115.97	117.58		117.71	0.001857	1.55	33.03	39.63	0.41
Muskrat River	Main_2	2284	Winter 100yr	Winter - 113.621m	83.00	115.77	118.47		118.53	0.000575	1.23	105.94	56.96	0.25
Muskrat River	Main_2	2284	Summer 100yr	Summer - 113.621m	46.50	115.77	117.52		117.59	0.001172	1.27	52.95	54.33	0.33
Muskrat River	Main_2	2284	Summer 100yr	Summer - 112 m	46.50	115.77	117.52		117.59	0.001172	1.27	52.95	54.33	0.33
Muskrat River	Main_2	2284	Summer 100yr	Summer - 111.082m	46.50	115.77	117.52		117.59	0.001172	1.27	52.95	54.33	0.33
Muskrat River	Main_2	2201	Winter 100yr	Winter - 113.621m	83.00	115.16	118.45		118.50	0.000296	1.01	96.83	46.32	0.19
Muskrat River	Main_2	2201	Summer 100yr	Summer - 113.621m	46.50	115.16	117.50		117.53	0.000362	0.87	57.50	34.22	0.19
Muskrat River	Main_2	2201	Summer 100yr	Summer - 112 m	46.50	115.16	117.50		117.53	0.000362	0.87	57.51	34.22	0.19
Muskrat River	Main_2	2201	Summer 100yr	Summer - 111.082m	46.50	115.16	117.50		117.53	0.000362	0.87	57.51	34.22	0.19
Muskrat River	Main_2	2137	Winter 100yr	Winter - 113.621m	83.00	115.41	118.39	116.71	118.47	0.000529	1.30	76.69	39.11	0.25
Muskrat River	Main_2	2137	Summer 100yr	Summer - 113.621m	46.50	115.41	117.44	116.33	117.50	0.000678	1.12	45.83	30.31	0.26
Muskrat River	Main_2	2137	Summer 100yr	Summer - 112 m	46.50	115.41	117.44	116.33	117.50	0.000678	1.12	45.83	30.31	0.26
Muskrat River	Main_2	2137	Summer 100yr	Summer - 111.082m	46.50	115.41	117.44	116.33	117.50	0.000678	1.12	45.83	30.31	0.26
Muskrat River	Main_2	2030	Winter 100yr	Winter - 113.621m	83.00	114.96	118.41	115.98	118.43	0.000116	0.67	165.00	64.56	0.12
Muskrat River	Main_2	2030	Summer 100yr	Summer - 113.621m	46.50	114.96	117.44	115.69	117.46	0.000128	0.56	104.36	61.20	0.12
Muskrat River	Main_2	2030	Summer 100yr	Summer - 112 m	46.50	114.96	117.44	115.69	117.46	0.000128	0.56	104.36	61.20	0.12
Muskrat River	Main_2	2030	Summer 100yr	Summer - 111.082m	46.50	114.96	117.44	115.69	117.46	0.000128	0.56	104.36	61.20	0.12
Muskrat River	Main_1	1931	Winter 100yr	Winter - 113.621m	259.90	115.05	117.85		118.31	0.003042	3.02	92.44	40.87	0.59
Muskrat River	Main_1	1931	Summer 100yr	Summer - 113.621m	138.10	115.05	117.11		117.36	0.002570	2.24	63.49	36.57	0.51
Muskrat River	Main_1	1931	Summer 100yr	Summer - 112 m	138.10	115.05	117.11		117.36	0.002570	2.24	63.50	36.57	0.51
Muskrat River	Main_1	1931	Summer 100yr	Summer - 111.082m	138.10	115.05	117.11		117.36	0.002570	2.24	63.50	36.57	0.51
Muskrat River	Main_1	1764	Winter 100yr	Winter - 113.621m	259.90	114.67	117.38	116.68	117.79	0.002986	2.89	115.75	82.87	0.58
Muskrat River	Main_1	1764	Summer 100yr	Summer - 113.621m	138.10	114.67	116.65	116.04	116.91	0.002867	2.26	63.59	39.67	0.54
Muskrat River	Main_1	1764	Summer 100yr	Summer - 112 m	138.10	114.67	116.65	116.04	116.91	0.002865	2.26	63.61	39.68	0.54
Muskrat River	Main_1	1764	Summer 100yr	Summer - 111.082m	138.10	114.67	116.65	116.04	116.91	0.002865	2.26	63.61	39.68	0.54
Muskrat River	Main_1	1638	Winter 100yr	Winter - 113.621m	259.90	114.51	116.46	116.39	117.18	0.008074	3.79	75.72	50.82	0.90
Muskrat River	Main_1	1638	Summer 100yr	Summer - 113.621m	138.10	114.51	116.04	115.78	116.40	0.005712	2.67	54.58	49.25	0.72
Muskrat River	Main_1	1638	Summer 100yr	Summer - 112 m	138.10	114.51	116.04	115.78	116.40	0.005778	2.68	54.35	49.23	0.73
Muskrat River	Main_1	1638	Summer 100yr	Summer - 111.082m	138.10	114.51	116.04	115.78	116.40	0.005778	2.68	54.35	49.23	0.73
Muskrat River	Main_1	1562	Winter 100yr	Winter - 113.621m	259.90	114.25	115.92	115.85	116.49	0.009041	3.34	79.83	63.99	0.91
Muskrat River	Main_1	1562	Summer 100yr	Summer - 113.621m	138.10	114.25	115.45	115.40	115.83	0.010425	2.71	51.09	57.78	0.91
Muskrat River	Main_1	1562	Summer 100yr	Summer - 112 m	138.10	114.25	115.46	115.40	115.83	0.010159	2.69	51.49	57.83	0.90
Muskrat River	Main_1	1562	Summer 100yr	Summer - 111.082m	138.10	114.25	115.46	115.40	115.83	0.010159	2.69	51.49	57.83	0.90
Muskrat River	Main_1	1496	Winter 100yr	Winter - 113.621m	259.90	113.68	115.74	115.28	116.05	0.003566	2.55	120.57	85.99	0.60
Muskrat River	Main_1	1496	Summer 100yr	Summer - 113.621m	138.10	113.68	115.17	114.83	115.38	0.003855	2.06	72.42	69.90	0.59
Muskrat River	Main_1	1496	Summer 100yr	Summer - 112 m	138.10	113.68	115.24	114.83	115.42	0.003175	1.94	78.91	78.21	0.54
Muskrat River	Main_1	1496	Summer 100yr	Summer - 111.082m	138.10	113.68	115.24	114.83	115.42	0.003175	1.94	78.91	78.21	0.54
Muskrat River	Main_1	1365	Winter 100yr	Winter - 113.621m	259.90	112.78	115.44		115.67	0.002201	2.39	170.77	130.41	0.49
Muskrat River	Main_1	1365	Summer 100yr	Summer - 113.621m	138.10	112.78	114.51	114.18	114.82	0.004632	2.50	62.64	82.53	0.66
Muskrat River	Main_1	1365	Summer 100yr	Summer - 112 m	138.10	112.78	114.25	114.18	114.74	0.009145	3.10	45.91	44.32	0.90
Muskrat River	Main_1	1365	Summer 100yr	Summer - 111.082m	138.10	112.78	114.25	114.18	114.74	0.009145	3.10	45.91	44.32	0.90
Muskrat River	Main_1	1233	Winter 100yr	Winter - 113.621m	259.90	111.36	115.33		115.47	0.000781	1.89	234.65	166.66	0.32
Muskrat River	Main_1	1233	Summer 100yr	Summer - 113.621m	138.10	111.36	114.42		114.54	0.000808	1.59	108.04	71.45	0.31
Muskrat River	Main_1	1233	Summer 100yr	Summer - 112 m	138.10	111.36	114.13		114.29	0.001204	1.81	90.31	52.83	0.37
Muskrat River	Main_1	1233	Summer 100yr	Summer - 111.082m	138.10	111.36	114.13		114.29	0.001204	1.81	90.32	52.83	0.37
Muskrat River	Main_1	1170	Winter 100yr	Winter - 113.621m	259.90	110.91	115.30		115.44	0.000603	1.83	244.99	171.80	0.28
Muskrat River	Main_1	1170	Summer 100yr	Summer - 113.621m	138.10	110.91	114.40		114.50	0.000512	1.44	112.62	73.83	0.25
Muskrat River	Main_1	1170	Summer 100yr	Summer - 112 m	138.10	110.91	114.10		114.22	0.000719	1.60	97.24	45.01	0.29
Muskrat River	Main_1	1170	Summer 100yr	Summer - 111.082m	138.10	110.91	114.10		114.22	0.000719	1.60	97.24	45.01	0.29
Muskrat River	Main_1	1102	Winter 100yr	Winter - 113.621m	259.90	110.81	115.12		115.38	0.001148	2.46	191.11	154.57	0.39
Muskrat River	Main_1	1102	Summer 100yr	Summer - 113.621m	138.10	110.81	114.26		114.44	0.000957	1.92	87.20	52.50	0.34
Muskrat River	Main_1	1102	Summer 100yr	Summer - 112 m	138.10	110.81	113.91		114.15	0.001438	2.19	72.28	35.67	0.41
Muskrat River	Main_1	1102	Summer 100yr	Summer - 111.082m	138.10	110.81	113.91		114.15	0.001438	2.19	72.28	35.67	0.41
Muskrat River	Main_1	971	Winter 100yr	Winter - 113.621m	259.90	110.88	115.08		115.2					

HEC-RAS Profile: Winter 100yr (Continued)

River	Reach	River Sta	Profile	Plan	Q Total (m³/s)	Min Ch El (m)	W.S. Elev (m)	Crit W.S. (m)	E.G. Elev (m)	E.G. Slope (m/m)	Vel Chnl (m/s)	Flow Area (m²)	Top Width (m)	Froude # Cnl
Muskrat River	Main_1	871	Winter 100yr	Winter - 113.621m	259.90	110.79	114.87		115.13	0.001149	2.38	143.50	61.67	0.38
Muskrat River	Main_1	871	Summer 100yr	Summer - 113.621m	138.10	110.79	114.14		114.27	0.000702	1.62	100.69	55.23	0.29
Muskrat River	Main_1	871	Summer 100yr	Summer - 112 m	138.10	110.79	113.69		113.87	0.001200	1.91	79.42	36.63	0.37
Muskrat River	Main_1	871	Summer 100yr	Summer - 111.082m	138.10	110.79	113.69		113.87	0.001200	1.91	79.42	36.63	0.37
Muskrat River	Main_1	832	Winter 100yr	Winter - 113.621m	259.90	110.24	114.78		115.08	0.001240	2.58	136.21	55.55	0.40
Muskrat River	Main_1	832	Summer 100yr	Summer - 113.621m	138.10	110.24	114.12		114.24	0.000632	1.64	105.19	37.28	0.28
Muskrat River	Main_1	832	Summer 100yr	Summer - 112 m	138.10	110.24	113.65		113.82	0.001040	1.91	88.50	35.07	0.35
Muskrat River	Main_1	832	Summer 100yr	Summer - 111.082m	138.10	110.24	113.65		113.82	0.001040	1.91	88.50	35.07	0.35
Muskrat River	Main_1	812	Winter 100yr	Winter - 113.621m	259.90	110.27	114.57	113.22	115.03	0.002059	3.14	116.76	54.74	0.51
Muskrat River	Main_1	812	Summer 100yr	Summer - 113.621m	138.10	110.27	114.04	112.43	114.22	0.000949	1.93	93.96	37.99	0.34
Muskrat River	Main_1	812	Summer 100yr	Summer - 112 m	138.10	110.27	113.53	112.43	113.78	0.001741	2.33	74.54	35.44	0.45
Muskrat River	Main_1	812	Summer 100yr	Summer - 111.082m	138.10	110.27	113.53	112.43	113.78	0.001741	2.33	74.54	35.44	0.45
Muskrat River	Main_1	797												
Muskrat River	Main_1	785	Winter 100yr	Winter - 113.621m	259.90	110.89	114.18		114.85	0.003873	3.77	82.24	42.03	0.68
Muskrat River	Main_1	785	Summer 100yr	Summer - 113.621m	138.10	110.89	113.92		114.15	0.001503	2.22	72.00	35.05	0.42
Muskrat River	Main_1	785	Summer 100yr	Summer - 112 m	138.10	110.89	113.01		113.58	0.005823	3.39	43.73	27.39	0.77
Muskrat River	Main_1	785	Summer 100yr	Summer - 111.082m	138.10	110.89	113.01		113.58	0.005817	3.39	43.74	27.40	0.77
Muskrat River	Main_1	726	Winter 100yr	Winter - 113.621m	259.90	110.76	114.31		114.51	0.000977	2.01	139.90	45.55	0.35
Muskrat River	Main_1	726	Summer 100yr	Summer - 113.621m	138.10	110.76	113.96		114.03	0.000400	1.19	123.95	44.99	0.22
Muskrat River	Main_1	726	Summer 100yr	Summer - 112 m	138.10	110.76	113.08		113.23	0.001250	1.69	85.47	43.17	0.36
Muskrat River	Main_1	726	Summer 100yr	Summer - 111.082m	138.10	110.76	113.08		113.23	0.001249	1.69	85.49	43.17	0.36
Muskrat River	Main_1	581	Winter 100yr	Winter - 113.621m	259.90	110.67	114.11		114.38	0.001403	2.33	121.54	44.01	0.41
Muskrat River	Main_1	581	Summer 100yr	Summer - 113.621m	138.10	110.67	113.89		113.98	0.000504	1.33	112.00	42.63	0.24
Muskrat River	Main_1	581	Summer 100yr	Summer - 112 m	138.10	110.67	112.82		113.04	0.002220	2.09	66.62	38.88	0.48
Muskrat River	Main_1	581	Summer 100yr	Summer - 111.082m	138.10	110.67	112.83		113.04	0.002217	2.09	66.66	38.88	0.48
Muskrat River	Main_1	549	Winter 100yr	Winter - 113.621m	259.90	109.85	114.07		114.29	0.000830	1.98	135.52	42.08	0.33
Muskrat River	Main_1	549	Summer 100yr	Summer - 113.621m	138.10	109.85	113.88		113.95	0.000285	1.12	127.29	41.62	0.19
Muskrat River	Main_1	549	Summer 100yr	Summer - 112 m	138.10	109.85	112.76		112.92	0.001103	1.72	82.62	38.44	0.35
Muskrat River	Main_1	549	Summer 100yr	Summer - 111.082m	138.10	109.85	112.77		112.92	0.001102	1.72	82.66	38.45	0.35
Muskrat River	Main_1	470	Winter 100yr	Winter - 113.621m	259.90	110.11	114.08	112.04	114.21	0.000583	1.60	171.54	51.97	0.27
Muskrat River	Main_1	470	Summer 100yr	Summer - 113.621m	138.10	110.11	113.88	111.52	113.92	0.000201	0.91	161.11	51.86	0.16
Muskrat River	Main_1	470	Summer 100yr	Summer - 112 m	138.10	110.11	112.73	111.52	112.83	0.000847	1.41	102.25	51.15	0.30
Muskrat River	Main_1	470	Summer 100yr	Summer - 111.082m	138.10	110.11	112.73	111.52	112.83	0.000846	1.41	102.31	51.15	0.30
Muskrat River	Main_1	455												
Muskrat River	Main_1	436	Winter 100yr	Winter - 113.621m	259.90	110.32	113.92	112.29	114.08	0.000838	1.76	154.29	71.06	0.32
Muskrat River	Main_1	436	Summer 100yr	Summer - 113.621m	138.10	110.32	113.84	111.77	113.88	0.000260	0.96	149.67	70.90	0.18
Muskrat River	Main_1	436	Summer 100yr	Summer - 112 m	138.10	110.32	112.57	111.77	112.71	0.001628	1.68	84.38	50.36	0.40
Muskrat River	Main_1	436	Summer 100yr	Summer - 111.082m	138.10	110.32	112.57	111.77	112.71	0.001623	1.68	84.46	50.36	0.40
Muskrat River	Main_1	381	Winter 100yr	Winter - 113.621m	259.90	109.69	113.90	111.57	114.02	0.000489	1.59	179.22	60.52	0.25
Muskrat River	Main_1	381	Summer 100yr	Summer - 113.621m	138.10	109.69	113.83	110.99	113.86	0.000147	0.86	175.19	59.05	0.14
Muskrat River	Main_1	381	Summer 100yr	Summer - 112 m	138.10	109.69	112.53	110.99	112.62	0.000584	1.32	110.00	46.63	0.26
Muskrat River	Main_1	381	Summer 100yr	Summer - 111.082m	138.10	109.69	112.53	110.99	112.62	0.000583	1.32	110.07	46.64	0.26
Muskrat River	Main_1	319	Winter 100yr	Winter - 113.621m	259.90	109.63	113.82	111.81	113.97	0.000685	1.81	154.89	51.40	0.30
Muskrat River	Main_1	319	Summer 100yr	Summer - 113.621m	138.10	109.63	113.81	111.19	113.85	0.000195	0.96	154.39	51.14	0.16
Muskrat River	Main_1	319	Summer 100yr	Summer - 112 m	138.10	109.63	112.45	111.19	112.57	0.000928	1.56	92.62	44.18	0.32
Muskrat River	Main_1	319	Summer 100yr	Summer - 111.082m	138.10	109.63	112.45	111.19	112.57	0.000925	1.56	92.70	44.19	0.32
Muskrat River	Main_1	304												
Muskrat River	Main_1	291	Winter 100yr	Winter - 113.621m	259.90	109.77	113.78	111.81	113.95	0.000736	1.91	154.69	80.47	0.31
Muskrat River	Main_1	291	Summer 100yr	Summer - 113.621m	138.10	109.77	113.79	111.13	113.84	0.000205	1.01	155.47	81.69	0.16
Muskrat River	Main_1	291	Summer 100yr	Summer - 112 m	138.10	109.77	112.39	111.13	112.53	0.001039	1.69	87.91	47.02	0.34
Muskrat River	Main_1	291	Summer 100yr	Summer - 111.082m	138.10	109.77	112.39	111.13	112.53	0.001036	1.69	88.01	47.04	0.34
Muskrat River	Main_1	266	Winter 100yr	Winter - 113.621m	259.90	110.68	113.77	112.34	113.92	0.000945	1.80	156.85	184.86	0.33
Muskrat River	Main_1	266	Summer 100yr	Summer - 113.621m	138.10	110.68	113.79	111.80	113.83	0.000260	0.95	158.18	185.02	0.18
Muskrat River	Main_1	266	Summer 100yr	Summer - 112 m	138.10	110.68	112.25	111.80	112.47	0.003376	2.10	68.20	62.34	0.56
Muskrat River	Main_1	266	Summer 100yr	Summer - 111.082m	138.10	110.68	112.25	111.80	112.48	0.003350	2.10	68.37	62.39	0.56
Muskrat River	Main_1	256												
Muskrat River	Main_1	242	Winter 100yr	Winter - 113.621m	259.90	110.69	113.59	112.04	113.70	0.000697	1.48	176.39	118.96	0.28
Muskrat River	Main_1	242	Summer 100yr	Summer - 113.621m	138.10	110.69	113.61	111.63	113.64	0.000192	0.78	177.69	119.14	0.15
Muskrat River	Main_1	242	Summer 100yr	Summer - 112 m	138.10	110.69	112.06	111.63	112.22	0.003099	1.78	77.71	91.42	0.52
Muskrat River	Main_1	242	Summer 100yr	Summer - 111.082m	138.10	110.69	111.94	111.63	112.14	0.004255	1.98	70.01	88.59	0.60
Muskrat River	Main_1	213	Winter 100yr	Winter - 113.621m	259.90	109.78	113.62	111.32	113.66	0.000178	0.90	373.73	149.02	0.15
Muskrat River	Main_1	213	Summer 100yr	Summer - 113.621m	138.10	109.78	113.62	110.84	113.63	0.000050	0.48	373.52	149.00	0.08
Muskrat River	Main_1	213	Summer 100yr	Summer - 112 m	138.10	109.78	112.09	110.84	112.14	0.000487	1.03	157.70	129.65	0.23
Muskrat River	Main_1	213	Summer 100yr	Summer - 111.082m	138.10	109.78	111.97	110.84	112.03	0.000625	1.12	135.59	95.84	0.25
Muskrat River	Main_1	146	Winter 100yr	Winter - 113.621m	259.90	110.64	113.62	111.74	113.64	0.000177	0.75	523.88	300.00	0.14
Muskrat River	Main_1	146	Summer 100yr	Summer - 113.621m	138.10	110.64	113.62	111.40	113.63	0.000050	0.40	524.64	300.00	0.08
Muskrat River	Main_1	146	Summer 100yr	Summer - 112 m	138.10	110.64	112.01	111.40	112.08	0.001431	1.20	117.72	111.39	0.35
Muskrat River	Main_1	146	Summer 100yr	Summer - 111.082m	138.10	110.64	111.86	111.40	111.96	0.002283	1.38	101.25	107.79	0.44
Muskrat River	Main_1	1	Winter 100yr	Winter - 113.621m	259.90	110.62	113.62	111.27	113.63	0.000031	0.32	808.99	300.00	0.06
Muskrat River	Main_1	1	Summer 100yr	Summer - 113.621m	138.10	110.62	113.62	111.13	113.62	0.000009	0.17	808.99	300.00	0.03
Muskrat River	Main_1	1	Summer 100yr	Summer - 112 m	138.10	110.62	112.00	111.13	112.01	0.000169	0.41	329.75	286.77	0.12
Muskrat River	Main_1	1	Summer 100yr	Summer - 111.082m	138.10	110.62	111.13	111.13	111.27	0.014154	1.66	84.79	272.51	0.91
Indian River	Main_1	3247	Winter 100yr	Winter - 113.621m	181.90	116.94	121.18		121.38	0.000857	2.11	117.57	46.81	0.33
Indian River	Main_1	3247	Summer 100yr	Summer - 113.621m	92.90	116.94	119.93		120.07	0.000852	1.65	64.30	37.70	0.31
Indian River	Main_1	3247	Summer 100yr	Summer - 112 m	92.90	116.94	119.93		120.07	0.000852	1.65	64.30	37.70	0.31
Indian River	Main_1	3247	Summer 100yr	Summer - 111.082m	92.90	116.94	119.93		120.07	0.000852	1.65	64.30	37.70	0.31
Indian River	Main_1	3075	Winter 100yr	Winter - 113.621m	181.90	116.95	121.01		121.23	0.000922	2.12	105.94	39.28	0.34
Indian River	Main_1	3075	Summer 100yr	Summer - 113.621m	92.90	116.95	119.78		119.92	0.000893	1.63	61.17	28.70	0.31

HEC-RAS Profile: Winter 100yr (Continued)

River	Reach	River Sta	Profile	Plan	Q Total (m ³ /s)	Min Ch El (m)	W.S. Elev (m)	Crit W.S. (m)	E.G. Elev (m)	E.G. Slope (m/m)	Vel Chnl (m/s)	Flow Area (m ²)	Top Width (m)	Froude # Chl
Indian River	Main_1	3075	Summer 100yr	Summer - 112 m	92.90	116.95	119.78		119.92	0.000893	1.63	61.17	28.70	0.31
Indian River	Main_1	3075	Summer 100yr	Summer - 111.082m	92.90	116.95	119.78		119.92	0.000893	1.63	61.17	28.70	0.31
Indian River	Main_1	2884	Winter 100yr	Winter - 113.621m	181.90	115.87	120.82		121.06	0.000812	2.23	103.03	31.75	0.33
Indian River	Main_1	2884	Summer 100yr	Summer - 113.621m	92.90	115.87	119.65		119.77	0.000597	1.57	68.70	26.73	0.27
Indian River	Main_1	2884	Summer 100yr	Summer - 112 m	92.90	115.87	119.65		119.77	0.000597	1.57	68.70	26.73	0.27
Indian River	Main_1	2884	Summer 100yr	Summer - 111.082m	92.90	115.87	119.65		119.77	0.000597	1.57	68.70	26.73	0.27
Indian River	Main_1	2861	Winter 100yr	Winter - 113.621m	181.90	116.61	120.68	119.20	121.02	0.001544	2.68	81.92	30.81	0.44
Indian River	Main_1	2861	Summer 100yr	Summer - 113.621m	92.90	116.61	119.55	118.40	119.74	0.001396	2.01	53.37	26.59	0.40
Indian River	Main_1	2861	Summer 100yr	Summer - 112 m	92.90	116.61	119.55	118.40	119.74	0.001396	2.01	53.37	26.59	0.40
Indian River	Main_1	2861	Summer 100yr	Summer - 111.082m	92.90	116.61	119.55	118.40	119.74	0.001396	2.01	53.37	26.59	0.40
Indian River	Main_1	2845		Bridge										
Indian River	Main_1	2832	Winter 100yr	Winter - 113.621m	181.90	116.56	120.52	119.25	120.96	0.002033	3.04	74.18	27.42	0.50
Indian River	Main_1	2832	Summer 100yr	Summer - 113.621m	92.90	116.56	119.45	118.36	119.70	0.001732	2.25	47.15	23.03	0.44
Indian River	Main_1	2832	Summer 100yr	Summer - 112 m	92.90	116.56	119.45	118.36	119.70	0.001732	2.25	47.15	23.03	0.44
Indian River	Main_1	2832	Summer 100yr	Summer - 111.082m	92.90	116.56	119.45	118.36	119.70	0.001732	2.25	47.15	23.03	0.44
Indian River	Main_1	2798	Winter 100yr	Winter - 113.621m	181.90	116.76	120.55		120.81	0.001238	2.35	98.74	41.86	0.39
Indian River	Main_1	2798	Summer 100yr	Summer - 113.621m	92.90	116.76	119.43		119.60	0.001229	1.84	56.30	30.57	0.37
Indian River	Main_1	2798	Summer 100yr	Summer - 112 m	92.90	116.76	119.43		119.60	0.001229	1.84	56.30	30.57	0.37
Indian River	Main_1	2798	Summer 100yr	Summer - 111.082m	92.90	116.76	119.43		119.60	0.001229	1.84	56.30	30.57	0.37
Indian River	Main_1	2746	Winter 100yr	Winter - 113.621m	181.90	116.46	120.56		120.73	0.000733	1.90	126.86	56.99	0.30
Indian River	Main_1	2746	Summer 100yr	Summer - 113.621m	92.90	116.46	119.43		119.54	0.000685	1.47	72.16	38.13	0.28
Indian River	Main_1	2746	Summer 100yr	Summer - 112 m	92.90	116.46	119.43		119.54	0.000685	1.47	72.16	38.13	0.28
Indian River	Main_1	2746	Summer 100yr	Summer - 111.082m	92.90	116.46	119.43		119.54	0.000685	1.47	72.16	38.13	0.28
Indian River	Main_1	2646	Winter 100yr	Winter - 113.621m	181.90	116.37	120.57		120.66	0.000373	1.39	163.89	52.47	0.22
Indian River	Main_1	2646	Summer 100yr	Summer - 113.621m	92.90	116.37	119.42		119.48	0.000312	1.02	107.97	46.87	0.19
Indian River	Main_1	2646	Summer 100yr	Summer - 112 m	92.90	116.37	119.42		119.48	0.000312	1.02	107.97	46.87	0.19
Indian River	Main_1	2646	Summer 100yr	Summer - 111.082m	92.90	116.37	119.42		119.48	0.000312	1.02	107.97	46.87	0.19
Indian River	Main_1	2613	Winter 100yr	Winter - 113.621m	181.90	116.39	120.55		120.64	0.000419	1.46	175.42	70.04	0.23
Indian River	Main_1	2613	Summer 100yr	Summer - 113.621m	92.90	116.39	119.41		119.46	0.000369	1.10	104.87	53.44	0.21
Indian River	Main_1	2613	Summer 100yr	Summer - 112 m	92.90	116.39	119.41		119.46	0.000369	1.10	104.87	53.44	0.21
Indian River	Main_1	2613	Summer 100yr	Summer - 111.082m	92.90	116.39	119.41		119.46	0.000369	1.10	104.87	53.44	0.21
Indian River	Main_1	2576	Winter 100yr	Winter - 113.621m	181.90	116.41	120.54	118.23	120.62	0.000371	1.37	227.50	116.76	0.22
Indian River	Main_1	2576	Summer 100yr	Summer - 113.621m	92.90	116.41	119.39	117.60	119.45	0.000382	1.11	109.55	67.32	0.21
Indian River	Main_1	2576	Summer 100yr	Summer - 112 m	92.90	116.41	119.39	117.60	119.45	0.000382	1.11	109.55	67.32	0.21
Indian River	Main_1	2576	Summer 100yr	Summer - 111.082m	92.90	116.41	119.39	117.60	119.45	0.000382	1.11	109.55	67.32	0.21
Indian River	Main_1	2492	Winter 100yr	Winter - 113.621m	181.90	116.46	120.48	118.74	120.58	0.000612	1.72	249.08	157.47	0.28
Indian River	Main_1	2492	Summer 100yr	Summer - 113.621m	92.90	116.46	119.24	117.96	119.39	0.001077	1.77	64.11	35.82	0.35
Indian River	Main_1	2492	Summer 100yr	Summer - 112 m	92.90	116.46	119.24	117.96	119.39	0.001077	1.77	64.11	35.82	0.35
Indian River	Main_1	2492	Summer 100yr	Summer - 111.082m	92.90	116.46	119.24	117.96	119.39	0.001077	1.77	64.11	35.82	0.35
Indian River	Main_1	2443	Winter 100yr	Winter - 113.621m	181.90	116.42	120.47	118.55	120.55	0.000475	1.53	269.59	159.08	0.25
Indian River	Main_1	2443	Summer 100yr	Summer - 113.621m	92.90	116.42	119.21	117.80	119.33	0.000842	1.57	70.13	36.56	0.31
Indian River	Main_1	2443	Summer 100yr	Summer - 112 m	92.90	116.42	119.21	117.80	119.33	0.000842	1.57	70.13	36.56	0.31
Indian River	Main_1	2443	Summer 100yr	Summer - 111.082m	92.90	116.42	119.21	117.80	119.33	0.000842	1.57	70.13	36.56	0.31
Indian River	Main_1	2341	Winter 100yr	Winter - 113.621m	181.90	116.43	120.39	118.41	120.50	0.000557	1.64	203.61	108.20	0.27
Indian River	Main_1	2341	Summer 100yr	Summer - 113.621m	92.90	116.43	119.13	117.72	119.25	0.000805	1.51	68.48	34.28	0.30
Indian River	Main_1	2341	Summer 100yr	Summer - 112 m	92.90	116.43	119.13	117.72	119.25	0.000805	1.51	68.48	34.28	0.30
Indian River	Main_1	2341	Summer 100yr	Summer - 111.082m	92.90	116.43	119.13	117.72	119.25	0.000805	1.51	68.48	34.28	0.30
Indian River	Main_1	2308	Winter 100yr	Winter - 113.621m	181.90	116.44	120.33	118.58	120.48	0.000772	1.89	168.75	83.18	0.31
Indian River	Main_1	2308	Summer 100yr	Summer - 113.621m	92.90	116.44	119.07	117.83	119.21	0.001122	1.74	70.10	71.67	0.35
Indian River	Main_1	2308	Summer 100yr	Summer - 112 m	92.90	116.44	119.07	117.83	119.21	0.001122	1.74	70.10	71.67	0.35
Indian River	Main_1	2308	Summer 100yr	Summer - 111.082m	92.90	116.44	119.07	117.83	119.21	0.001122	1.74	70.10	71.67	0.35
Indian River	Main_1	2283	Winter 100yr	Winter - 113.621m	181.90	115.74	120.31	117.93	120.46	0.000569	1.79	149.29	57.73	0.27
Indian River	Main_1	2283	Summer 100yr	Summer - 113.621m	92.90	115.74	119.09	117.20	119.18	0.000523	1.38	83.29	47.63	0.25
Indian River	Main_1	2283	Summer 100yr	Summer - 112 m	92.90	115.74	119.09	117.20	119.18	0.000523	1.38	83.29	47.63	0.25
Indian River	Main_1	2283	Summer 100yr	Summer - 111.082m	92.90	115.74	119.09	117.20	119.18	0.000523	1.38	83.29	47.63	0.25
Indian River	Main_1	2187	Winter 100yr	Winter - 113.621m	181.90	115.64	120.25	117.97	120.40	0.000636	1.90	164.05	76.23	0.29
Indian River	Main_1	2187	Summer 100yr	Summer - 113.621m	92.90	115.64	119.00	117.22	119.12	0.000650	1.55	77.12	57.84	0.28
Indian River	Main_1	2187	Summer 100yr	Summer - 112 m	92.90	115.64	119.00	117.22	119.12	0.000650	1.55	77.12	57.84	0.28
Indian River	Main_1	2187	Summer 100yr	Summer - 111.082m	92.90	115.64	119.00	117.22	119.12	0.000650	1.55	77.12	57.84	0.28
Indian River	Main_1	2108	Winter 100yr	Winter - 113.621m	181.90	115.66	120.20	117.95	120.35	0.000629	1.89	163.50	68.85	0.29
Indian River	Main_1	2108	Summer 100yr	Summer - 113.621m	92.90	115.66	118.96	117.16	119.07	0.000628	1.52	84.76	56.69	0.27
Indian River	Main_1	2108	Summer 100yr	Summer - 112 m	92.90	115.66	118.96	117.16	119.07	0.000628	1.52	84.76	56.69	0.27
Indian River	Main_1	2108	Summer 100yr	Summer - 111.082m	92.90	115.66	118.96	117.16	119.07	0.000628	1.52	84.76	56.69	0.27
Indian River	Main_1	2068	Winter 100yr	Winter - 113.621m	181.90	115.70	120.20	117.89	120.32	0.000526	1.72	168.75	73.59	0.26
Indian River	Main_1	2068	Summer 100yr	Summer - 113.621m	92.90	115.70	118.94	117.14	119.04	0.000586	1.45	84.14	60.70	0.26
Indian River	Main_1	2068	Summer 100yr	Summer - 112 m	92.90	115.70	118.94	117.14	119.04	0.000586	1.45	84.14	60.70	0.26
Indian River	Main_1	2068	Summer 100yr	Summer - 111.082m	92.90	115.70	118.94	117.14	119.04	0.000586	1.45	84.14	60.70	0.26
Indian River	Main_1	2040	Winter 100yr	Winter - 113.621m	181.90	115.65	120.15	117.78	120.30	0.000589	1.81	144.03	64.49	0.28
Indian River	Main_1	2040	Summer 100yr	Summer - 113.621m	92.90	115.65	118.93	117.05	119.02	0.000542	1.39	80.49	43.43	0.25
Indian River	Main_1	2040	Summer 100yr	Summer - 112 m	92.90	115.65	118.93	117.05	119.02	0.000542	1.39	80.49	43.43	0.25
Indian River	Main_1	2040	Summer 100yr	Summer - 111.082m	92.90	115.65	118.93	117.05	119.02	0.000542	1.39	80.49	43.43	0.25
Indian River	Main_1	1966	Winter 100yr	Winter - 113.621m	181.90	115.66	120.03	118.15	120.24	0.000892	2.18	122.58	50.42	0.34
Indian River	Main_1	1966	Summer 100yr	Summer - 113.621m	92.90	115.66	118.84	117.28	118.97	0.000830	1.68	70.41	33.09	0.31
Indian River	Main_1	1966	Summer 100yr	Summer - 112 m	92.90	115.66	118.84	117.28	118.97	0.000830	1.68	70.41	33.09	0.31
Indian River	Main_1	1966	Summer 100yr	Summer - 111.082m	92.90	115.66	118.84	117.28	118.97	0.000830	1.68	70.41	33.09	0.31
Indian River	Main_1	1921	Winter 100yr	Winter - 113.621m	181.90	115.65	120.09	117.80	120.18	0.000389	1.47	183.61	80.76	0.22
Indian River	Main_1	1921	Summer 100yr	Summer - 113.621m	92.90	115.65	118.83	117.05	118.93	0.000571	1.41	85.43	64.84	0.26
Indian River	Main_1	1921	Summer 100yr	Summer -										

HEC-RAS Profile: Winter 100yr (Continued)

River	Reach	River Sta	Profile	Plan	Q Total (m ³ /s)	Min Ch El (m)	W.S. Elev (m)	Crit W.S. (m)	E.G. Elev (m)	E.G. Slope (m/m)	Vel Chnl (m/s)	Flow Area (m ²)	Top Width (m)	Froude # Chl
Indian River	Main_1	1888	Summer 100yr	Summer - 113.621m	92.90	115.59	118.82	116.99	118.91	0.000490	1.31	88.05	44.02	0.24
Indian River	Main_1	1888	Summer 100yr	Summer - 112 m	92.90	115.59	118.82	116.99	118.91	0.000490	1.31	88.05	44.02	0.24
Indian River	Main_1	1888	Summer 100yr	Summer - 111.082m	92.90	115.59	118.82	116.99	118.91	0.000490	1.31	88.05	44.02	0.24
Indian River	Main_1	1868	Winter 100yr	Winter - 113.621m	181.90	114.90	119.87	117.52	120.13	0.000856	2.32	85.64	25.39	0.34
Indian River	Main_1	1868	Summer 100yr	Summer - 113.621m	92.90	114.90	118.77	116.68	118.89	0.000547	1.56	64.78	23.73	0.26
Indian River	Main_1	1868	Summer 100yr	Summer - 112 m	92.90	114.90	118.77	116.68	118.89	0.000547	1.56	64.78	23.73	0.26
Indian River	Main_1	1868	Summer 100yr	Summer - 111.082m	92.90	114.90	118.77	116.68	118.89	0.000547	1.56	64.78	23.73	0.26
Indian River	Main_1	1859												
Indian River	Main_1	1849	Winter 100yr	Winter - 113.621m	181.90	115.16	119.77	117.70	120.05	0.001013	2.39	81.18	26.41	0.37
Indian River	Main_1	1849	Summer 100yr	Summer - 113.621m	92.90	115.16	118.73	116.89	118.86	0.000670	1.62	60.98	23.96	0.29
Indian River	Main_1	1849	Summer 100yr	Summer - 112 m	92.90	115.16	118.73	116.89	118.86	0.000670	1.62	60.98	23.96	0.29
Indian River	Main_1	1849	Summer 100yr	Summer - 111.082m	92.90	115.16	118.73	116.89	118.86	0.000670	1.62	60.98	23.96	0.29
Indian River	Main_1	1829	Winter 100yr	Winter - 113.621m	181.90	114.48	119.85	117.08	119.94	0.000377	1.47	188.25	73.89	0.22
Indian River	Main_1	1829	Summer 100yr	Summer - 113.621m	92.90	114.48	118.75	116.38	118.81	0.000305	1.11	114.01	61.82	0.19
Indian River	Main_1	1829	Summer 100yr	Summer - 112 m	92.90	114.48	118.75	116.38	118.81	0.000305	1.11	114.01	61.82	0.19
Indian River	Main_1	1829	Summer 100yr	Summer - 111.082m	92.90	114.48	118.75	116.38	118.81	0.000305	1.11	114.01	61.82	0.19
Indian River	Main_1	1799	Winter 100yr	Winter - 113.621m	181.90	114.29	119.79	117.70	119.93	0.000464	1.82	168.88	90.14	0.26
Indian River	Main_1	1799	Summer 100yr	Summer - 113.621m	92.90	114.29	118.72	116.80	118.80	0.000337	1.32	96.80	54.32	0.21
Indian River	Main_1	1799	Summer 100yr	Summer - 112 m	92.90	114.29	118.72	116.80	118.80	0.000337	1.32	96.80	54.32	0.21
Indian River	Main_1	1799	Summer 100yr	Summer - 111.082m	92.90	114.29	118.72	116.80	118.80	0.000337	1.32	96.80	54.32	0.21
Indian River	Main_1	1748	Winter 100yr	Winter - 113.621m	181.90	114.63	119.84	117.70	119.88	0.000165	1.04	206.75	110.42	0.15
Indian River	Main_1	1748	Summer 100yr	Summer - 113.621m	92.90	114.63	118.72	116.80	118.78	0.000243	1.06	103.75	64.09	0.18
Indian River	Main_1	1748	Summer 100yr	Summer - 112 m	92.90	114.63	118.72	116.80	118.78	0.000243	1.06	103.75	64.09	0.18
Indian River	Main_1	1748	Summer 100yr	Summer - 111.082m	92.90	114.63	118.72	116.80	118.78	0.000243	1.06	103.75	64.09	0.18
Indian River	Main_1	1608	Winter 100yr	Winter - 113.621m	181.90	114.02	119.78	117.21	119.85	0.000333	1.48	205.20	116.40	0.21
Indian River	Main_1	1608	Summer 100yr	Summer - 113.621m	92.90	114.02	118.61	116.34	118.72	0.000488	1.50	79.79	84.34	0.25
Indian River	Main_1	1608	Summer 100yr	Summer - 112 m	92.90	114.02	118.61	116.34	118.72	0.000488	1.50	79.79	84.34	0.25
Indian River	Main_1	1608	Summer 100yr	Summer - 111.082m	92.90	114.02	118.61	116.34	118.72	0.000488	1.50	79.79	84.34	0.25
Indian River	Main_1	1516	Winter 100yr	Winter - 113.621m	181.90	115.21	119.76	117.43	119.82	0.000311	1.33	206.18	104.46	0.20
Indian River	Main_1	1516	Summer 100yr	Summer - 113.621m	92.90	115.21	118.58	116.65	118.67	0.000497	1.37	87.41	90.83	0.24
Indian River	Main_1	1516	Summer 100yr	Summer - 112 m	92.90	115.21	118.58	116.65	118.67	0.000497	1.37	87.41	90.83	0.24
Indian River	Main_1	1516	Summer 100yr	Summer - 111.082m	92.90	115.21	118.58	116.65	118.67	0.000497	1.37	87.41	90.83	0.24
Indian River	Main_1	1429	Winter 100yr	Winter - 113.621m	181.90	115.22	119.73	117.33	119.79	0.000291	1.29	270.79	143.39	0.20
Indian River	Main_1	1429	Summer 100yr	Summer - 113.621m	92.90	115.22	118.54	116.60	118.63	0.000476	1.34	83.23	47.64	0.24
Indian River	Main_1	1429	Summer 100yr	Summer - 112 m	92.90	115.22	118.54	116.60	118.63	0.000476	1.34	83.23	47.64	0.24
Indian River	Main_1	1429	Summer 100yr	Summer - 111.082m	92.90	115.22	118.54	116.60	118.63	0.000476	1.34	83.23	47.64	0.24
Indian River	Main_1	1313	Winter 100yr	Winter - 113.621m	181.90	114.10	119.72	116.77	119.75	0.000241	1.00	283.14	134.47	0.14
Indian River	Main_1	1313	Summer 100yr	Summer - 113.621m	92.90	114.10	118.51	115.91	118.57	0.000439	1.14	120.48	112.70	0.18
Indian River	Main_1	1313	Summer 100yr	Summer - 112 m	92.90	114.10	118.51	115.91	118.57	0.000439	1.14	120.48	112.70	0.18
Indian River	Main_1	1313	Summer 100yr	Summer - 111.082m	92.90	114.10	118.51	115.91	118.57	0.000439	1.14	120.48	112.70	0.18
Indian River	Main_1	1308												
Indian River	Main_1	1301	Winter 100yr	Winter - 113.621m	181.90	114.66	119.70	117.46	119.74	0.000161	0.92	284.36	140.99	0.13
Indian River	Main_1	1301	Summer 100yr	Summer - 113.621m	92.90	114.66	118.49	116.58	118.55	0.000395	1.19	115.21	116.61	0.20
Indian River	Main_1	1301	Summer 100yr	Summer - 112 m	92.90	114.66	118.49	116.58	118.55	0.000395	1.19	115.22	116.61	0.20
Indian River	Main_1	1301	Summer 100yr	Summer - 111.082m	92.90	114.66	118.49	116.58	118.55	0.000395	1.19	115.22	116.61	0.20
Indian River	Main_1	1220	Winter 100yr	Winter - 113.621m	181.90	115.04	119.63	117.08	119.70	0.000333	1.37	232.04	121.01	0.21
Indian River	Main_1	1220	Summer 100yr	Summer - 113.621m	92.90	115.04	118.44	116.43	118.51	0.000370	1.17	101.16	59.79	0.21
Indian River	Main_1	1220	Summer 100yr	Summer - 112 m	92.90	115.04	118.44	116.43	118.51	0.000370	1.17	101.16	59.79	0.21
Indian River	Main_1	1220	Summer 100yr	Summer - 111.082m	92.90	115.04	118.44	116.43	118.51	0.000370	1.17	101.16	59.79	0.21
Indian River	Main_1	1125	Winter 100yr	Winter - 113.621m	181.90	115.08	119.59	117.23	119.67	0.000381	1.47	208.71	92.02	0.22
Indian River	Main_1	1125	Summer 100yr	Summer - 113.621m	92.90	115.08	118.40	116.51	118.47	0.000439	1.27	106.15	79.16	0.23
Indian River	Main_1	1125	Summer 100yr	Summer - 112 m	92.90	115.08	118.40	116.51	118.47	0.000439	1.27	106.15	79.16	0.23
Indian River	Main_1	1125	Summer 100yr	Summer - 111.082m	92.90	115.08	118.40	116.51	118.47	0.000439	1.27	106.15	79.16	0.23
Indian River	Main_1	974	Winter 100yr	Winter - 113.621m	181.90	115.02	119.49	117.04	119.61	0.000472	1.62	144.15	50.96	0.25
Indian River	Main_1	974	Summer 100yr	Summer - 113.621m	92.90	115.02	118.34	116.36	118.41	0.000401	1.22	89.54	43.42	0.22
Indian River	Main_1	974	Summer 100yr	Summer - 112 m	92.90	115.02	118.34	116.36	118.41	0.000401	1.22	89.54	43.42	0.22
Indian River	Main_1	974	Summer 100yr	Summer - 111.082m	92.90	115.02	118.34	116.36	118.41	0.000401	1.22	89.54	43.42	0.22
Indian River	Main_1	888	Winter 100yr	Winter - 113.621m	181.90	113.98	119.39	117.00	119.56	0.000566	1.87	126.07	40.10	0.27
Indian River	Main_1	888	Summer 100yr	Summer - 113.621m	92.90	113.98	118.29	116.38	118.38	0.000375	1.28	84.63	35.15	0.21
Indian River	Main_1	888	Summer 100yr	Summer - 112 m	92.90	113.98	118.29	116.38	118.38	0.000375	1.28	84.63	35.15	0.21
Indian River	Main_1	888	Summer 100yr	Summer - 111.082m	92.90	113.98	118.29	116.38	118.38	0.000375	1.28	84.63	35.15	0.21
Indian River	Main_1	829	Winter 100yr	Winter - 113.621m	181.90	115.08	119.33	117.19	119.52	0.000750	1.98	118.70	43.77	0.31
Indian River	Main_1	829	Summer 100yr	Summer - 113.621m	92.90	115.08	118.24	116.47	118.35	0.000593	1.44	73.65	37.69	0.26
Indian River	Main_1	829	Summer 100yr	Summer - 112 m	92.90	115.08	118.24	116.47	118.35	0.000593	1.44	73.65	37.69	0.26
Indian River	Main_1	829	Summer 100yr	Summer - 111.082m	92.90	115.08	118.24	116.47	118.35	0.000593	1.44	73.65	37.69	0.26
Indian River	Main_1	671	Winter 100yr	Winter - 113.621m	181.90	115.01	119.24	117.10	119.40	0.000674	1.86	142.24	60.54	0.29
Indian River	Main_1	671	Summer 100yr	Summer - 113.621m	92.90	115.01	118.16	116.40	118.25	0.000565	1.39	83.11	50.05	0.26
Indian River	Main_1	671	Summer 100yr	Summer - 112 m	92.90	115.01	118.16	116.40	118.25	0.000565	1.39	83.11	50.05	0.26
Indian River	Main_1	671	Summer 100yr	Summer - 111.082m	92.90	115.01	118.16	116.40	118.25	0.000565	1.39	83.11	50.05	0.26
Indian River	Main_1	532	Winter 100yr	Winter - 113.621m	181.90	115.05	119.09	117.00	119.29	0.000837	2.02	111.40	41.36	0.32
Indian River	Main_1	532	Summer 100yr	Summer - 113.621m	92.90	115.05	118.07	116.38	118.17	0.000634	1.44	72.91	34.50	0.27
Indian River	Main_1	532	Summer 100yr	Summer - 112 m	92.90	115.05	118.07	116.38	118.17	0.000634	1.44	72.91	34.50	0.27
Indian River	Main_1	532	Summer 100yr	Summer - 111.082m	92.90	115.05	118.07	116.38	118.17	0.000634	1.44	72.91	34.50	0.27
Indian River	Main_1	368	Winter 100yr	Winter - 113.621m	181.90	115.08	118.94	117.07	119.15	0.000917	2.06	106.24	38.55	0.34
Indian River	Main_1	368	Summer 100yr	Summer - 113.621m	92.90	115.08	117.95	116.38	118.06	0.000700	1.47	70.05	34.33	0.28
Indian River	Main_1	368	Summer 100yr	Summer - 112 m	92.90	115.08	117.95	116.38	118.06	0.000700	1.47	70.05	34.33	0.28
Indian River	Main_1	368	Summer 100yr	Summer - 111.082m	92.90	115.08	117.95	116.38	118.06	0.000700	1.47	70.05		

HEC-RAS Profile: Winter 100yr (Continued)

River	Reach	River Sta	Profile	Plan	Q Total (m ³ /s)	Min Ch El (m)	W.S. Elev (m)	Crit W.S. (m)	E.G. Elev (m)	E.G. Slope (m/m)	Vel Chnl (m/s)	Flow Area (m ²)	Top Width (m)	Froude # Chl
Indian River	Main_1	274	Summer 100yr	Summer - 111.082m	92.90	115.08	117.84		117.98	0.000978	1.67	65.55	42.79	0.33
Indian River	Main_1	217	Winter 100yr	Winter - 113.621m	181.90	115.07	118.79		118.98	0.000949	2.04	142.15	75.64	0.34
Indian River	Main_1	217	Summer 100yr	Summer - 113.621m	92.90	115.07	117.79		117.92	0.000909	1.61	70.53	54.75	0.32
Indian River	Main_1	217	Summer 100yr	Summer - 112 m	92.90	115.07	117.79		117.92	0.000909	1.61	70.54	54.75	0.32
Indian River	Main_1	217	Summer 100yr	Summer - 111.082m	92.90	115.07	117.79		117.92	0.000909	1.61	70.54	54.75	0.32
Indian River	Main_1	157	Winter 100yr	Winter - 113.621m	181.90	115.06	118.74		118.92	0.001002	2.07	150.64	84.77	0.35
Indian River	Main_1	157	Summer 100yr	Summer - 113.621m	92.90	115.06	117.71		117.86	0.001097	1.73	69.24	71.18	0.35
Indian River	Main_1	157	Summer 100yr	Summer - 112 m	92.90	115.06	117.71		117.86	0.001097	1.73	69.24	71.18	0.35
Indian River	Main_1	157	Summer 100yr	Summer - 111.082m	92.90	115.06	117.71		117.86	0.001097	1.73	69.24	71.18	0.35
Indian River	Main_1	64	Winter 100yr	Winter - 113.621m	181.90	115.05	118.61		118.82	0.001136	2.17	122.92	58.65	0.37
Indian River	Main_1	64	Summer 100yr	Summer - 113.621m	92.90	115.05	117.61		117.76	0.001108	1.71	66.39	53.34	0.35
Indian River	Main_1	64	Summer 100yr	Summer - 112 m	92.90	115.05	117.61		117.76	0.001108	1.71	66.39	53.34	0.35
Indian River	Main_1	64	Summer 100yr	Summer - 111.082m	92.90	115.05	117.61		117.76	0.001108	1.71	66.39	53.34	0.35
Indian River	Main_1	2	Winter 100yr	Winter - 113.621m	181.90	114.32	118.42		118.73	0.001447	2.61	94.41	38.44	0.43
Indian River	Main_1	2	Summer 100yr	Summer - 113.621m	92.90	114.32	117.53		117.69	0.001012	1.82	61.65	34.57	0.34
Indian River	Main_1	2	Summer 100yr	Summer - 112 m	92.90	114.32	117.53		117.69	0.001012	1.82	61.65	34.58	0.34
Indian River	Main_1	2	Summer 100yr	Summer - 111.082m	92.90	114.32	117.53		117.69	0.001012	1.82	61.65	34.58	0.34

APPENDIX F

PCSWMM Model Parameters and Design Storm Parameters

Table F.1: Subcatchment Information of Amalgamated Model

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
A_001	0.8099	90	89.989	4.403	69.212	127	120
A_002	0.3734	40	93.35	4.699	75.815	127	120
A_003	0.1224	40	30.6	6.028	75.143	127	120
A_004	0.4767	70	68.1	7.661	68.476	127	119.75
A_005	0.2591	35	74.029	4.945	68.768	125	97.31
A_006	0.2803	40	70.075	3.975	69.114	122	72.52
A_007	0.1821	30	60.7	4.383	71.451	120	55.55
A_008	3.5933	140	256.664	5.094	43.536	126	117.07
A_011	0.9121	60	152.017	4.617	73.92	124	90.77
A_012	0.0558	8	69.75	6.209	71.11	120	55
A_013	0.5451	40	136.275	4.478	74.644	120	55
A_014	0.3111	30	103.7	4.728	73.441	120	55
A_015	0.9438	70	134.829	5.576	71.409	131	37.38
A_016	0.3602	50	72.04	6.657	73.115	150	7.5
A_017	0.0096	5	19.2	3.292	80.444	150	7.5
A_018	0.3674	40	91.85	5.772	67.51	130	36.87
A_019	0.0092	5	18.4	2.543	85.169	120	55
A_020	0.6947	70	99.243	3.895	3.73	127	120
A_021	0.0104	5	20.8	4.658	80.863	127	120
A_022	0.3707	80	46.337	3.38	30.555	127	120
A_023	0.0214	8	26.75	2.109	81.682	127	120
A_024	0.4184	60	69.733	4.203	76.082	127	120
A_025	0.0294	8	36.75	3.804	80.128	127	120
A_026	0.1536	20	76.8	5.545	73.442	127	120
A_027	0.5417	60	90.283	4.888	70.767	127	116.43
A_028	0.2942	30	98.067	5.711	72.944	121	63.79
A_029	0.2398	30	79.933	5.397	70.922	120	55.05
A_030	0.0109	5	21.8	3.797	78.312	120	55
A_031	0.0094	7	13.429	1.749	90.143	120	55
A_032	0.7203	55	130.964	5.481	73.187	121	65.53
A_033	0.2086	20	104.3	6.06	68.788	126	105.54
A_034	0.5554	80	69.425	5.219	67.628	127	120
A_035	0.3082	25	123.28	3.883	70.744	127	119.16
A_036	0.1371	20	68.55	3.791	73.415	121	66.98
A_037	0.7359	60	122.65	4.037	70.892	120	55.36

City-Wide Flood Risk Assessment and Storm Outlet Review
 City of Pembroke

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
A_038	0.9934	80	124.175	4.197	58.824	120	56.94
A_039	1.8753	90	208.367	5.512	71.019	124	89.06
A_040	0.0095	8	11.875	3.19	90.493	120	55
A_041	0.3145	40	78.625	4.665	72.334	120	55
A_042	1.7183	200	85.915	5.906	71.863	120	55
A_043	1.7626	60	293.767	4.705	32.745	123	82.14
A_044	0.6551	70	93.586	7.412	69.827	120	55
A_045	1.1887	60	198.117	6.594	54.18	122	69.84
A_046	0.948	60	158	7.099	71.708	124	89.92
A_047	0.2275	20	113.75	5.105	70.499	120	55.37
A_048	0.905	60	150.833	7.504	64.08	124	91.95
A_049	0.5998	40	149.95	7.248	62.367	125	104.33
A_050	0.1462	20	73.1	9.155	68.39	123	84.71
A_051	0.0076	8	9.5	5.509	80.457	120	61.28
A_052	1.2377	50	247.54	5.573	70.344	125	101.47
A_053	0.4944	50	98.88	3.533	81.432	120	55
A_054	0.424	50	84.8	3.839	79.7	120	55
A_055	1.7536	180	97.422	6.867	68.24	127	116.88
A_056	0.0287	8	35.875	4.303	75.821	120	55
A_057	0.3099	30	103.3	5.061	79.742	121	59.56
A_058	0.3662	30	122.067	3.983	79.983	122	73.73
A_059	0.2457	25	98.28	5.664	81.545	123	81
A_060	0.4817	50	96.34	5.242	78.038	127	119.84
A_061	0.3775	50	75.5	6.283	71.825	127	120
A_062	0.4576	50	91.52	6.405	72.01	127	120
A_063	0.4936	60	82.267	7.711	73.593	126	114.87
A_064	0.3522	40	88.05	8.392	78.199	120	55
A_065	2.1559	90	239.544	7	63.168	120	55
A_066	0.053	10	53	7.854	69.543	120	55
A_067	0.8771	110	79.736	7.565	81.719	127	114.84
A_068	0.5429	70	77.557	6.714	80.249	127	120
A_069	0.2622	35	74.914	5.906	81.082	127	120
A_070	0.1052	20	52.6	6.718	82.025	127	120
A_071	1.9256	90	213.956	8.203	72.076	126	107.26
A_072	1.5051	80	188.138	9.349	72.259	129	53.93
A_073	0.3587	40	89.675	5.344	79.558	136	29.43
A_074	0.0458	10	45.8	4.054	79.376	123	48.51
A_075	0.4291	90	47.678	5.993	73.339	145	13.76
A_076	0.27	60	45	3.991	74.633	150	7.5
A_077	3.8693	120	322.442	4.068	66.339	145	5.75
A_078	0.0502	10	50.2	3.243	73.728	150	7.5
A_079	0.0201	5	40.2	2.198	81.7	150	7.5

City-Wide Flood Risk Assessment and Storm Outlet Review
 City of Pembroke

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
A_080	0.0354	8	44.25	2.397	83.114	150	7.5
A_081	0.243	40	60.75	5.863	80.68	150	7.5
A_082	1.2666	100	126.66	5.88	41.924	150	7.5
A_083	0.2407	30	80.233	3.957	66.155	150	7.5
A_084	0.0264	7	37.714	4.371	72.68	150	7.5
A_085	3.4079	120	283.992	4.884	40.907	150	7.5
A_086	0.2642	30	88.067	6.851	64.904	150	7.5
A_087	1.3673	80	170.912	6.012	52.643	150	7.5
A_088	0.0655	20	32.75	5.778	78.803	150	7.5
A_089	0.6369	60	106.15	5.059	71.936	150	7.5
A_090	0.4573	70	65.329	5.735	68.372	146	10.91
A_091	0.6787	60	113.117	6	72.995	133	33.68
A_092	1.743	110	158.455	5.396	74.26	149	6.28
A_093	0.4918	60	81.967	4.721	70.367	150	7.5
A_094	0.9006	100	90.06	7.991	69.161	140	21.95
A_095	0.2148	40	53.7	6.587	70.867	150	7.5
A_096	0.4094	40	102.35	7.33	70.967	150	7.5
A_097	0.4322	50	86.44	6.776	70.098	150	7.5
A_098	0.266	50	53.2	5.008	73.217	150	7.5
A_099	0.8825	100	88.25	6.898	48.131	150	7.5
A_100	0.5359	60	89.317	4.4	67.686	150	7.5
A_101	0.0978	15	65.2	3.893	64.33	150	7.5
A_102	0.3095	30	103.167	6.853	67.846	150	7.5
A_103	0.059	15	39.333	3.738	67.739	150	7.5
A_104	0.2502	40	62.55	3.58	70.182	150	7.5
A_105	0.5688	120	47.4	3.946	74.698	150	7.5
A_106	0.2588	30	86.267	3.779	78.85	150	7.5
A_107	1.438	120	119.833	3.377	74.473	150	7.5
A_108	1.5897	120	132.475	3.784	70.396	150	7.5
A_109	0.9205	65	141.615	4.48	70.156	150	7.5
A_110	0.2907	25	116.28	9.168	81.104	150	7.5
A_111	0.2985	30	99.5	6.17	76.428	150	7.5
A_112	0.081	8	101.25	5.783	78.705	150	7.5
A_113	0.0128	7	18.286	2.161	85.332	150	7.5
A_114	0.0469	12	39.083	3.95	78.308	150	7.5
A_115	0.2115	40	52.875	8.609	77.733	150	7.5
A_116	0.0838	20	41.9	9.192	72.323	150	7.5
A_117	0.0445	20	22.25	15	59.973	150	7.5
A_118	0.2517	60	41.95	13.286	60.519	150	7.5
A_119	0.183	45	40.667	11.637	59.984	150	7.5

Table F.2: Subcatchment Information for the Darcy Model

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
D_01	0.7208	90	80.089	5	69.809	150	5
D_02	0.0015	2	7.5	3.536	94.287	150	5
D_03	0.5365	60	89.417	5	69.971	150	5
D_04	0.9031	70	129.014	5	68.181	123	3.76
D_05	0.0041	5	8.2	4.018	86.194	150	5
D_06	0.004	4	10	1.709	92.95	150	5
D_07	0.3142	50	62.84	5	65.967	135	4.31
D_08	0.293	50	58.6	4.056	73.434	77	1.7
D_09	0.0094	4	23.5	5.331	75.804	50	0.51
D_10	0.1013	30	33.767	5.015	63.86	50	0.51

Table F.3: Subcatchment Information for the Lake Street Area Model

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
L_01	1.9858	120	165.483	3.353	71.044	50	0.51
L_02	0.3315	30	110.5	3.614	72.398	50	0.51
L_03	0.00005	0.5	0.98	2.771	81.686	50	0.51
L_04	0.1958	20	97.9	3.322	66.219	50	0.51
L_05	0.0845	10	84.5	3.411	68.503	50	0.51
L_06	0.0205	5	41	2.54	81.397	50	0.51
L_07	0.3804	50	76.08	5.417	73.082	50	0.51
L_08	0.3577	40	89.425	4.357	74.302	50	0.51
L_09	0.4464	50	89.28	2.652	73.715	50	0.51
L_10	0.0005	2	2.5	1.534	93.074	50	0.51
L_11	0.0675	15	45	5.083	62.233	50	0.51
L_12	0.0858	30	28.6	3.118	75.306	50	0.51
L_13	0.0697	15	46.467	3.563	68.19	50	0.51
L_14	0.0317	8	39.625	4.519	68.237	50	0.51
L_15	0.0621	18	34.5	4.835	69.855	50	0.51
L_16	0.0217	8	27.125	2.59	76.431	50	0.51
L_17	0.6703	80	83.788	3.162	78.271	50	0.51
L_18	0.0108	7	15.429	1.475	94.774	50	0.51
L_19	0.2848	60	47.467	3.065	76.243	50	0.51
L_20	0.598	50	119.6	3.434	81.283	50	0.51
L_21	0.3804	50	76.08	4.193	88.33	50	0.51
L_22	0.0076	5	15.2	2.033	92.295	50	0.51
L_23	2.3039	90	255.989	8	69.861	50	0.51
L_24	4.2446	150	282.973	3.685	42.354	50	0.51
L_25	0.2984	40	74.6	2.961	78.897	50	0.51
L_26	0.4818	40	120.45	3.907	77.793	50	0.51

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
L_27	0.1233	30	41.1	3.982	80.087	50	0.51
L_28	0.1687	25	67.48	5.4	70.649	50	0.51
L_29	0.2879	40	71.975	8	69.646	50	0.51
L_30	0.2474	40	61.85	5.074	66.003	50	0.51
L_31	0.5998	60	99.967	2.006	59.992	50	0.51
L_32	0.2566	40	64.15	5.442	67.983	50	0.51
L_33	0.5735	50	114.7	5.593	77.479	50	0.51
L_34	0.465	60	77.5	5.722	81.67	50	0.51
L_35	0.3176	35	90.743	6	76.016	50	0.51

Table F.4: Subcatchment Information for the Trafalgar Model

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
T_01	1.5233	120	126.942	4.929	70.986	150	5
T_02	0.2192	40	54.8	4.949	74.549	150	5
T_03	0.0166	8	20.75	5.654	80.33	150	5
T_04	0.5603	80	70.038	7.19	70.503	150	5
T_05	0.0231	8	28.875	4.38	80.476	150	5
T_06	0.8884	60	148.067	4.952	69.818	96	2.57
T_07	0.9211	60	153.517	5.971	69.896	95	2.56
T_08	0.0104	4	26	3.83	79.372	50	0.51
T_09	0.0189	8	23.625	2.928	90.193	50	0.51
T_10	1.2501	70	178.586	7.107	68.44	143	16.01
T_11	0.0173	5	34.6	6	80.624	150	5
T_12	0.4351	70	62.157	5.452	72.603	113	3.34
T_13	0.691	70	98.714	4.347	69.079	55	0.73
T_14	1.22	80	152.5	3.873	71.681	150	5
T_15	0.4719	45	104.867	6.204	69.244	150	5
T_16	0.5204	60	86.733	7.135	70.686	150	5
T_17	0.562	60	93.667	8.289	70.257	148	4.91
T_18	0.6727	60	112.117	3.402	69.146	50	0.51
T_19	1.0056	100	100.56	3.311	72.022	50	0.51
T_20	0.9058	90	100.644	4.289	67.116	50	0.51
T_21	0.0678	30	22.6	4.263	82.624	50	0.51
T_22	0.244	35	69.714	4.293	68.691	50	0.51
T_23	0.0348	10	34.8	6.588	69.308	50	0.51
T_24	0.4243	60	70.717	4.009	70.641	50	0.51
T_25	0.2928	35	83.657	3.304	69.181	50	0.51
T_26	0.2236	25	89.44	2.202	71.862	50	0.51
T_27	0.3748	50	74.96	2.984	72.165	50	0.51
T_28	0.2026	20	101.3	6.741	75.032	50	0.51

City-Wide Flood Risk Assessment and Storm Outlet Review
 City of Pembroke

Name	Area (ha)	Width (m)	Flow Length (m)	Slope (%)	Imperv. (%)	Max. Infil. Rate (mm/hr)	Min. Infil. Rate (mm/hr)
T_29	0.1821	15	121.4	3.517	75.426	50	0.51
T_30	0.2933	45	65.178	4.149	75.421	50	0.51
T_31	0.046	7	65.714	5.136	75.235	50	0.51
T_32	0.3931	50	78.62	5.001	73.346	50	0.51
T_33	0.1996	40	49.9	4.698	75.551	50	0.51
T_34	0.3327	20	166.35	5.6	74.845	50	0.51
T_35	0.5374	40	134.35	5.721	67.351	50	0.51
T_36	0.2044	40	51.1	5.503	83.446	50	0.51
T_37	0.1927	35	55.057	4.813	77.088	50	0.51
T_38	0.1353	20	67.65	4.973	78.645	50	0.51
T_39	1.7895	80	223.688	4.699	72.784	50	0.51
T_40	0.0808	15	53.867	6.074	76.452	50	0.51
T_41	0.0224	10	22.4	6.856	70.721	50	0.51
T_42	0.105	50	21	8	75.657	50	0.51
T_43	3.8802	80	485.025	7.827	74.717	50	0.51
T_44	0.0239	10	23.9	6.233	74.614	50	0.51
T_45	0.0559	40	13.975	5	86.347	50	0.51
T_46	1.1491	60	191.517	2.219	75.237	53	0.63
T_47	0.0081	5	16.2	2.52	84.324	50	0.51
T_48	2.6441	120	220.342	2.972	85.647	50	0.51
T_49	0.0499	40	12.475	4.834	87.974	50	0.51
T_50	0.0422	30	14.067	4.611	88.82	50	0.51
T_51	0.0331	20	16.55	5	82.386	50	0.51
T_52	0.5291	50	105.82	4.369	64.313	50	0.51
T_53	0.5212	70	74.457	2.987	72.009	50	0.51
T_54	0.0685	10	68.5	2.475	77.835	50	0.51
T_55	0.6208	60	103.467	8.18	77.797	50	0.51
T_56	1.9492	120	162.433	4.929	73.691	50	0.51
T_57	0.2537	25	101.48	3.547	70.838	50	0.51
T_58	0.5225	100	52.25	4.242	73.572	50	0.51
T_59	0.4609	120	38.408	8	76.255	50	0.51
T_60	0.0871	30	29.033	7.327	79.535	50	0.51
T_61	1.145	60	190.833	5.619	76.232	50	0.51
T_62	0.211	65	32.462	10	74.994	50	0.51
T_63	0.1659	55	30.164	10	74.978	50	0.51
T_64	0.2954	20	147.7	3.41	86.103	50	0.51
T_65	0.1419	80	17.738	3.11	75.014	50	0.51
T_66	1.145	150	76.333	4.732	79.392	50	0.51
T_67	0.0531	30	17.7	8.496	74.921	50	0.51
T_68	0.0001	0.5	2	3.417	84.329	61	1

Table F.5: Sewer Pipe Information for the Amalgamated Model

Name	Length (m)	Roughness	Inlet Elev. (m)	Outlet Elev. (m)	Diameter (m)
18_0001	45.887	0.013	111.033	110.494	0.9
18_0002	63.155	0.013	111.557	111.033	0.9
18_0003	23.29	0.013	112.807	111.557	0.9
18_0004	20.248	0.013	114.074	112.807	0.9
18_005	64.174	0.013	117.454	114.074	0.9
18_008	68.906	0.013	118.355	117.966	1.5
18_012	13.264	0.013	119.679	117.671	0.525
18_014	8.35	0.013	119.907	119.818	0.525
18_016	32.723	0.013	120.09	119.907	0.525
18_017	23.227	0.013	120.309	120.066	0.525
18_019	66.234	0.013	120.574	120.309	0.525
18_045	37.134	0.013	120.692	117.454	0.9
18_051	43.153	0.013	121.321	120.726	0.9
18_054	108.915	0.013	123.664	121.321	0.9
18_058	38.852	0.013	124.606	123.684	0.9
18_059	9.222	0.013	124.636	124.606	0.9
18_060	3.523	0.013	124.7	124.636	0.9
18_063	13.236	0.013	124.89	124.7	1
18_078	24.992	0.013	126.377	126.233	1
18_079	60.11	0.013	127.034	126.377	0.9
18_1	36.772	0.013	120.706	120.578	0.8
18_129a	6.991	0.013	147.556	147.503	0.75
18_129b	14.898	0.013	147.503	147.454	0.75
18_170	9.144	0.013	150.495	150.362	0.3
18_171	35.139	0.013	150.693	150.495	0.3
18_174	44.099	0.013	149.872	149.647	0.3
18_176	13.831	0.013	149.366	148.758	0.3
18_178	89.425	0.013	148.758	146.297	0.3
18_179	38.283	0.013	146.287	145.812	0.5
18_180	41.3	0.013	145.812	145.87	0.5
18_2	33.722	0.013	120.578	120.522	0.8
18_201	21.184	0.013	144.876	143.695	0.45
18_202	41.402	0.013	145.202	144.876	0.45
18_203	22.696	0.013	128.011	127.897	0.625
18_204	49.743	0.013	128.38	128.011	0.675
18_3	24.985	0.013	117.782	117.671	1.5
18_4	19.243	0.013	117.671	117.454	1.5
18_5	42.502	0.013	139.09	137.52	0.6
18_6	34.127	0.013	137.52	136.26	0.6
C1_1	81.155	0.013	126.048	124.832	0.675
C1_2	8.568	0.013	124.832	124.734	0.675
C20	22.753	0.013	118.765	118.355	1.2

City-Wide Flood Risk Assessment and Storm Outlet Review
 City of Pembroke

Name	Length (m)	Roughness	Inlet Elev. (m)	Outlet Elev. (m)	Diameter (m)
C24	56.269	0.013	124.734	123.115	0.9
C35	18.551	0.013	122.838	122.556	0.31
C8_1	31.878	0.013	119.482	119.042	1.5
C8_2	17.397	0.013	119.042	118.765	1.5
C2	73.139	0.01	145.628	145.202	1
18_086	9.451	0.013	136.21	136.21	0.75
18_091	62.629	0.013	139.52	139.09	0.75
18_093	32.193	0.013	139.75	139.52	0.75
18_095	22.772	0.013	139.91	139.75	0.75
18_097	52.934	0.013	142.2	140.06	0.6
18_099	71.053	0.013	144.7	142.2	0.6
18_101	61.596	0.013	145.34	145.03	0.75
18_103	86.793	0.013	145.77	145.34	0.75
18_106	77.424	0.013	146.15	145.77	0.75
18_117	86.515	0.013	146.9	146.496	0.75
18_119A	10.341	0.013	147.05	147.018	0.75
18_119B	31.86	0.013	147.018	146.92	0.75
18_121	30.198	0.013	148.408	147.749	0.3
18_159	65.147	0.013	147.895	147.57	0.75
18_160	4.997	0.013	147.919	147.9	0.75
18_216	71.782	0.013	138.1	135.73	0.3
18_125	56.547	0.013	147.45	147.166	0.75
18_214	67.338	0.013	135.73	131.942	0.3
18_109	13.176	0.013	146.22	146.15	0.75
18_123	23.081	0.013	147.166	147.05	0.75
18_163	20.597	0.013	148.364	147.932	0.75
18_165	37.927	0.013	149.349	148.63	0.5
18_207	97.1	0.013	128.708	128.46	0.675
18_0114	85.588	0.013	146.45	145.979	0.75
18_026	99.747	0.013	120.99	120.573	0.45
18_037	118.081	0.013	121.66	121.052	0.375
18_038	20.47	0.013	122.032	121.845	0.375
18_046	101.437	0.013	120.158	120.021	0.9
18_048	14.909	0.013	120.246	120.226	0.9
18_081	85.164	0.013	127.798	126.958	0.7
18_082	19.504	0.013	128.16	127.938	0.6
18_084	63.431	0.013	132.534	128.344	0.6
18_085	59.119	0.013	136.153	133.116	0.6
18_110	33.481	0.013	146.366	146.28	0.45
18_130	6.972	0.013	147.751	147.659	0.36
18_132	40.054	0.013	148.207	147.75	0.46
18_137	44.504	0.013	148.612	148.21	0.45
18_140	15.028	0.013	148.73	148.597	0.43

City-Wide Flood Risk Assessment and Storm Outlet Review
 City of Pembroke

Name	Length (m)	Roughness	Inlet Elev. (m)	Outlet Elev. (m)	Diameter (m)
18_142	32.003	0.013	148.966	148.835	0.29
18_143	9.4	0.013	149.118	149.062	0.28
18_144	67.138	0.013	149.73	149.106	0.28
18_147	15.388	0.013	149.047	148.966	0.36
18_149	66.449	0.013	149.445	149.134	0.28
18_151	9.961	0.013	149.43	149.45	0.28
18_154	69.84	0.013	149.86	149.499	0.27
18_167	42.537	0.013	150.117	149.715	0.3
18_169	15.415	0.013	150.277	150.202	0.3
18_175	51.168	0.013	149.634	149.213	0.3
18_181	47.57	0.013	145.863	145.719	0.5
18_183	69.607	0.013	140.25	136.617	0.6
18_184	50.304	0.013	141.345	140.218	0.6
18_187	47.379	0.013	141.521	141.328	0.6
18_188	46.516	0.013	141.714	141.56	0.675
18_189	22.453	0.013	141.822	141.758	0.675
18_190	46.093	0.013	142.026	141.81	0.675
18_193	47.953	0.013	142.282	142.109	0.675
18_195	16.559	0.013	142.591	142.54	0.35
18_196	55.931	0.013	144.122	142.662	0.3
18_199	55.814	0.013	143.583	143.018	0.45
18_208	123.498	0.013	130.746	128.818	0.525
18_210	12.565	0.013	130.911	130.847	0.525
18_212	42.348	0.013	131.959	130.902	0.6
C108	90.078	0.013	121.602	120.903	0.675
C28	61.123	0.013	121.791	120.685	0.9
C31	92.118	0.013	121.956	121.625	0.675
C36	67.783	0.013	120.338	119.599	1.2
C37	61.862	0.013	125.341	123.271	0.45
C38	71.103	0.013	123.18	120.698	0.45
C41	64.165	0.013	122.507	122.357	0.5
C6	56.689	0.013	122.21	122.012	0.675

Table F.6: Sewer Pipe Information for the Darcy Model

Name	Length (m)	Roughness	Inlet Elev. (m)	Outlet Elev. (m)	Diameter (m)
44_0001	67.375	0.013	115.897	113.277	0.3
44_0004	8.752	0.013	116.013	115.897	0.3
44_0005	3.845	0.013	116.925	116.827	0.2
44_0007	12.983	0.013	117.09	116.925	0.2
44_0013	48.3	0.013	118.814	116.075	0.2
C41_2	7.67	0.013	116.91	116.741	0.2
C43	40.6	0.013	116.693	115.839	0.2
44_0008	42.9	0.013	116.525	116.339	0.2
C42	5.7	0.013	116.336	116.033	0.2
C40	53.9	0.013	116.913	116.66	0.2

Table F.7: Sewer Pipe Information for the Lake Street Area Model

Name	Length (m)	Roughness	Inlet Elev. (m)	Outlet Elev. (m)	Diameter (m)
09_0004	9.203	0.013	110.841	110.704	0.9
09_0005	18.426	0.013	110.983	110.841	0.9
09_0007	7.917	0.013	111.036	110.983	0.9
09_0008	15.13	0.013	111.208	111.036	0.9
09_0009	40.722	0.013	111.69	111.208	0.9
09_0014	4.164	0.013	111.964	111.92	0.75
09_0015	6.728	0.013	112.123	111.964	0.75
09_0019	17.605	0.013	112.234	112.123	0.75
09_0021	0.65	0.013	112.238	112.234	0.75
09_0022	35.062	0.013	112.501	112.238	0.75
09_0023	17	0.013	112.86	112.501	0.45
09_0042	89	0.013	112.65	111.729	0.6
09_0043	10.829	0.013	111.237	111.199	0.3
09_0044	78.466	0.013	111.568	111.237	0.6
09_0048	14.622	0.013	112.081	111.84	0.3
09_0049	28.403	0.013	112.491	112.081	0.3
10_0001	67.4	0.013	110.655	109.936	0.375
10_0002	54	0.013	111.182	110.655	0.375
21_0001	34.7	0.013	111.725	109.686	0.675
10_0010	4	0.013	112.895	112.879	0.25
09_0012	39.407	0.013	111.92	111.758	0.75
10_0008	40.3	0.013	112.874	112.32	0.25
C50	34	0.013	113.28	113.11	0.3
C52	42.5	0.013	113.11	112.9	0.3
C53	3.5	0.013	112.9	112.623	0.3
09_0001	127.2	0.013	110.932	109.279	0.75
09_0002	95.6	0.013	111.1	110.969	0.75
09_0036	13.043	0.013	112.651	112.42	0.3

Name	Length (m)	Roughness	Inlet Elev. (m)	Outlet Elev. (m)	Diameter (m)
09_0040	14.7	0.013	111.792	111.593	0.6
10_0004	52.7	0.013	111.343	111.182	0.375
10_0006	26.3	0.013	111.833	111.362	0.375
10_0007	40.7	0.013	112.32	111.874	0.375
21_0003	70	0.013	111.893	111.725	0.675
21_0006	40	0.013	112.217	112.04	0.43
21_0008	55.2	0.013	112.522	112.207	0.525

Table F.8: Sewer Pipe Information for the Trafalgar Model

Name	Length (m)	Roughness	Inlet Elev. (m)	Outlet Elev. (m)	Diameter (m)
06_0001	32.9	0.013	111.766	109.705	0.6
06_0019	18	0.013	118.016	116.297	0.6
06_0048	105.979	0.013	127.282	125.617	0.375
06_0050	38.224	0.013	127.822	127.416	0.3
06_0082	11.283	0.013	120.34	119.995	0.6
06_0083	50.2	0.013	122.022	120.34	0.6
06_0085	17.512	0.013	122.545	122.492	0.75
06_0086	23.017	0.013	122.657	122.545	0.75
06_0087	28.123	0.013	122.807	122.715	0.75
06_0089	36.553	0.013	122.916	122.807	0.75
06_0091	40.373	0.013	123.201	122.916	0.75
06_0092	12.584	0.013	123.278	123.201	0.525
06_0093	8.122	0.013	123.328	123.278	0.525
06_0098	46.319	0.013	125.361	124.836	0.675
06_0100	10.088	0.013	125.447	125.361	0.675
06_0101	6.224	0.013	125.523	125.447	0.675
06_0103	53.52	0.013	125.838	125.575	0.675
06_0104	27.563	0.013	126.013	125.838	0.375
06_0105	35.455	0.013	126.297	126.013	0.375
06_0129	68.714	0.013	126.699	126.55	0.45
06_0131	0.729	0.013	126.714	126.699	0.375
06_0132	10.314	0.013	126.782	126.714	0.375
06_0134	70.342	0.013	130.196	126.86	0.375
06_0135	46.244	0.013	131.838	130.196	0.375
08_0051	8.505	0.013	126.702	126.5	0.25
08_0052	6.825	0.013	127.24	126.702	0.25
08_0062	8.291	0.013	132.762	132.564	0.2
08_0063	9.302	0.013	132.939	132.762	0.2
08_0072	22.3	0.013	132.306	131.759	0.2
ABL-P1	4.409	0.013	127.416	127.362	0.3
ABL-P2	8.757	0.013	127.362	127.282	0.3
06_0020	40.5	0.013	119.31	119.18	0.31

Table F.10: IDF Curves

Duration	5-min	10-min	15-min	30-min	1-hr	2-hr	6-hr	12-hr	24-hr
	Intensity (mm/h)								
2-yr	114.2	70.3	53	32.6	20.1	12.4	5.7	3.5	2.2
5-yr	151.7	93.4	70.4	43.3	26.7	16.4	7.6	4.7	2.9
10-yr	176.6	108.8	82	50.5	31.1	19.2	8.9	5.5	3.4
25-yr	207.3	127.7	96.2	59.3	36.5	22.5	10.4	6.4	4
50-yr	230.6	142.1	107	65.9	40.6	25	11.6	7.1	4.4
100-yr	253.3	156	117.5	72.4	44.6	27.5	12.7	7.9	4.8

Table F.11: Design Storms

Time (Hr)	5-yr Storm	100-yr Storm
	Depth (m)	Depth (m)
0	0	0
0.25	1.480246	2.47262
0.5	1.480246	2.47262
0.75	6.249926	10.43995
1	17.10506	28.5725
1.5	4.276265	7.143125
2	2.302604	3.846298
2.5	0	0

APPENDIX G

Outfall Assessment Field Notes

Watercourse and Crossing Location

Little River Muskkrat

ID Number

27

Date

*Nov 8, 2021
11:39*

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	<i>12"</i> Span
Pipe-Arch <input type="checkbox"/>	CMP <input checked="" type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	cm
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: <i>CSP</i> <i>+ Cast iron</i>	Other: _____	Other: _____	Other: _____	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical
- Exposed Footing (Open Bottom Culvert Only)

Location

Overall Rating

<i>No</i>		
<i>No</i>	Good	<input type="checkbox"/>
<i>No</i>		
<i>No</i>	Fair	<input type="checkbox"/>
<i>Critical</i>		
<i>Critical</i>	Poor	<input type="checkbox"/>
<i>No</i>		
<i>Poor Critical</i>	Critical	<input checked="" type="checkbox"/>
<i>No</i>		
<i>Critical</i>	Unknown	<input type="checkbox"/>
<i>No</i>		
<i>No</i>	Performance Problems	<input type="checkbox"/>
<i>No</i>		
<i>No</i>		
<i>No</i>		

Category

Rating

Invert Deterioration	<i>Critical</i>
Joint and Seams	<i>Crit</i>
Corrosion / Chemical	<i>N/A</i>
Cross-Section Deformation	
Cracking	<i>crit</i>
Headwall / Wingwall	<i>Crit</i>
Apron	<i>N/A</i>
Flared End Section	<i>N/A</i>
Scour Protection	<i>Crit</i>

Notes

- ~ 50 m of CSP missing between upstream cast iron pipe and headwall*
- Large concrete blocks at outfall of cast iron pipe*
- Manhole ~~cap~~ appears to have fallen, possibly due to bank erosion, causing failure of pipe*

Watercourse and Crossing Location

Indiana River, Christie St

ID Number

41

Date

Nov 8

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input checked="" type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	Span 24' 5 3/4 cm
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Headwall <input type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: <u>outflanked</u>	Other: _____	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical
- Exposed Footing (Open Bottom Culvert Only)

Location

Overall Rating

- No
- No
- No
- N/A
- Yes
- Yes
- No
- ~ Yes (exposed foundation)
- No
- No
- No
- No
- N/A
- No
- No
- No

Category

Rating

- Invert Deterioration Good
- Joint and Seams Critical
- Corrosion / Chemical Good
- ~~Cross-Section Deformation~~ No
- Cracking Critical
- Headwall / Wingwall Good
- Apron N/A
- Flared End Section N/A
- Scour Protection None/Poor

Notes: • 1" crack from settling, cracked all through wall, 3/4 of circumference
 • leakage from crack
 • outflanked
 • Another crack at seam, 1"

Watercourse and Crossing Location

Muskrat

ID Number

35

Date

Nov 10, 2021

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter 102 cm
Box <input checked="" type="checkbox"/>	Concrete <input checked="" type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	Span 123 cm Rise 125 cm
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	
Other: _____	Other: _____	Other: _____	Other: _____	Other: <u>Armed stone headwall</u>	

Circular

Box

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical Exposed Footing (Open Bottom Culvert Only)

Location

Overall Rating

- No
- No
- No
- No
- No
- Yes
- No
- No
- No
- No
- No
- No
- No
- No
- No

- Good
- Fair
- Poor
- Critical
- Unknown
- Performance Problems

Category

Rating

- Invert Deterioration: Good
- Joint and Seams: Critical
- Corrosion / Chemical: Good
- Cross-Section Deformation: Good
- Cracking: Critical
- Headwall / Wingwall: Good
- Apron: N/A
- Flared End Section: N/A
- Scour Protection: None/ Critical

Notes:

- 17 m of box culvert failed, embankment, fair condition
- Box culvert appears to have fed into circular concrete pipe
- Failure of box culvert created channel next to failed portion
- Several circular pipe sections disconnected from each other
- US end is now outlet under old road

Watercourse and Crossing Location

Muskroot

ID Number

N/A

Date

Nov 10, 2021

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input checked="" type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	<i>12"</i>
Pipe-Arch <input type="checkbox"/>	CMP <input checked="" type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical Exposed Footing (Open Bottom Culvert Only)

Location

- No*
- No*
- No*
- No*
- No*
- Yes*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- Yes*
- N/A*

Overall Rating

- Good
- Fair
- Poor
- Critical
- Unknown
- Performance Problems

Category

Rating

- Invert Deterioration *From Poor*
- Joint and Seams *Good*
- Corrosion / Chemical *Poor*
- Cross-Section Deformation *No*
- Cracking *No*
- Headwall / Wingwall *N/A*
- Apron *N/A*
- Flared End Section *N/A*
- Scour Protection *From Poor*

** Roundstone used as scour protection but slope is very steep esp. at out fall. washed out. Bottom of culvert is rusted through at outlet*

Watercourse and Crossing Location

ID Number

Date

Indian

31

Nov 8, 2021
13:00

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	Span 11.75 ^m
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input checked="" type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical Exposed Footing (Open Bottom Culvert Only)

Location

Overall Rating

No	Good	<input checked="" type="checkbox"/>
No	Fair	<input type="checkbox"/>
No (Yes for CSP)	Poor	<input type="checkbox"/>
No	Critical	<input type="checkbox"/>
No/Yes (at CSP)	Unknown	<input type="checkbox"/>
No	Performance Problems	<input type="checkbox"/>
No		
No/Yes (CSP)		
NO		

Category

Rating

Invert Deterioration	Good
Joint and Seams	N/A
Corrosion / Chemical	Good/Fair (CSP)
Cross-Section Deformation	
Cracking	Good
Headwall / Wingwall	Fair
Apron	N/A
Flared End Section	N/A
Scour Protection	Fair (CSP)

Notes:

- CSP half-pipe converges water from outfall to channel
- Has very small headwall
- CSP is fair condition but: 1 section downstream is undermined, 1 fell fallen. Some rust corrosion.

Watercourse and Crossing Location

Indian River

ID Number

45

Date

Nov 8, 2021
10:12

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input checked="" type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input checked="" type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	7.75"
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: <u>None</u>	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical Exposed Footing (Open Bottom Culvert Only)

Location

- No
- No
- No
- No
- Yes
- Yes
- No
- No
- No
- No
- No
- N/A
- Yes
- No
- N/A

Overall Rating

- Good
- Fair
- Poor
- Critical
- Unknown
- Performance Problems

Category	Rating
Invert Deterioration	Good
Joint and Seams	Critical
Corrosion / Chemical	Good
Cross-Section Deformation-	
Cracking	Critical
Headwall / Wingwall	N/A
Apron	N/A
Flared End Section	N/A
Scour Protection	None/Poor

Notes

- 30" broken / detached pipe section, 1 ft between sections
- At seam, pipe is in good condition but is recessed into the bank

Watercourse and Crossing Location

Indian

ID Number

42

Date

Nov 8, 2021
16:03

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input checked="" type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	24" Span
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	cm
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input checked="" type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical
- Exposed Footing (Open Bottom Culvert Only)

Location

- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No

Overall Rating

- Good
- Fair
- Poor
- Critical
- Unknown
- Performance Problems

Category	Rating
Invert Deterioration	Good
Joint and Seams	No Good
Corrosion / Chemical	No Good
Cross-Section Deformation	No Good
Cracking	Fair
Headwall / Wingwall	Fair / Critical
Apron	N/A
Flared End Section	N/A
Scour Protection	Fair

Notes

- ~20m recessed from channel
- Wingwalls failing
- Erosion along downstream outfall channel portion

Watercourse and Crossing Location

Indian

ID Number

56

Date

Nov 8, 2021
15:46

Barrel Shape	Material		No. of Barrels	End Treatments		Dimension
				Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter	
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	cm	
Pipe-Arch <input type="checkbox"/>	CMP <input checked="" type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Span 12"	
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	cm	
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	Rise	
					cm	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical
- Exposed Footing (Open Bottom Culvert Only)

Location

- No Yes
- Yes
- No Over Basin
- No
- No
- Yes
- No
- No
- No
- No
- No
- Yes
- Yes No
- No
- No

Overall Rating

- Good
- Fair
- Poor
- Critical
- Unknown
- Performance Problems

Category Rating

- Invert Deterioration Good
- Joint and Seams Good
- Corrosion / Chemical Fair
- Cross-Section Deformation Fair
- Cracking Good
- Headwall / Wingwall Critical
- Apron N/A
- Flared End Section N/A
- Scour Protection None/Fair

Notes:

- Headwall destroyed
- End partially buried and concrete slightly crushed
- ~ 3-4 m above channel

NOT LOCATED - Likely buried
 under dumped veg/grass clippings
 ID Number 43
 Date Nov 8, 2021
 11:06

Watercourse and Crossing Location

Indian River

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input type="checkbox"/>	Timber <input type="checkbox"/>	One <input type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	

Performance Problems

Location

Overall Rating

Debris/Veg. Blockage > 1/3 of Rise		Good	<input type="checkbox"/>
Sediment Blockage 1/3 to 3/4 of Rise			
Buoyancy or Crushing-Related Failure		Fair	<input type="checkbox"/>
Poor Channel Alignment			
Previous and/or Frequent Overtopping		Poor	<input type="checkbox"/>
Local Scour			
Embankment Piping		Critical	<input type="checkbox"/>
Channel Degradation			
Headcut		Unknown	<input type="checkbox"/>
Embankment Slope Instability			
Sediment Blockage > 3/4 Rise			
Sediment Blockage > 1/3 Rise Throughout Barrel		Performance Problems	<input type="checkbox"/>
Submerged / Ends Totally Buried			
Aggressive Abrasion / Corrosion / Chemical			
Exposed Footing (Open Bottom Culvert Only)			

Category	Rating
Invert Deterioration	
Joint and Seams	
Corrosion / Chemical	
Cross-Section Deformation	
Cracking	
Headwall / Wingwall	
Apron	
Flared End Section	
Scour Protection	

Notes: found remnants of broken concrete pipe

Watercourse and Crossing Location
 Indian River, Christie

ID Number
 1564 1565
 55

Date
 Nov 8
 9:50

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input checked="" type="checkbox"/>	Span 7.75m
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input checked="" type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input checked="" type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	

Performance Problems	Location	Overall Rating
Debris/Veg. Blockage > 1/3 of Rise	No	Good <input checked="" type="checkbox"/>
Sediment Blockage 1/3 to 3/4 of Rise	No	
Buoyancy or Crushing-Related Failure	No	
Poor Channel Alignment	No	Fair <input type="checkbox"/>
Previous and/or Frequent Overtopping	Yes	
Local Scour	No	Poor <input type="checkbox"/>
Embankment Piping	No	
Channel Degradation	No	Critical <input type="checkbox"/>
Headcut	No	
Embankment Slope Instability	No	Unknown <input type="checkbox"/>
Sediment Blockage > 3/4 Rise	No	
Sediment Blockage > 1/3 Rise Throughout	No	
Barrel	N/A	Performance Problems <input type="checkbox"/>
Submerged / Ends Totally Buried	No	
Aggressive Abrasion / Corrosion / Chemical	No	
Exposed Footing (Open Bottom Culvert Only)	No	

Category	Rating
Invert Deterioration	Good
Joint and Seams	N/A
Corrosion / Chemical	No Good
Cross-Section Deformation	No
Cracking	No Good
Headwall / Wingwall	N/A
Apron	N/A
Flared End Section	N/A
Scour Protection	None/Good

Notes:
 - slight drop but no scour protection
 - pipe is mitered, concrete surrounding is critical condition

Watercourse and Crossing Location

Indran River, D'Arcy

ID Number

44

Date

Nov 8
10:30

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	11.75"
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input type="checkbox"/>	Span
Elliptical <input type="checkbox"/>	PVC <input checked="" type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	cm
Other: _____	Other: _____	Other: _____	Other: <u>h</u>	Other: <u>N/A</u>	Rise cm

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical Exposed Footing (Open Bottom Culvert Only)

Location

Overall Rating

No	Good	<input type="checkbox"/>
No	Fair	<input checked="" type="checkbox"/>
No	Poor	<input type="checkbox"/>
No	Critical	<input type="checkbox"/>
No	Unknown	<input type="checkbox"/>
No	Performance Problems	<input type="checkbox"/>
N/A		
Partially submerged		
Yes		
N/A		

Category

Rating

Invert Deterioration	N/A Good
Joint and Seams	Good
Corrosion / Chemical	Good
Cross-Section Deformation	
Cracking	Poor
Headwall / Wingwall	N/A
Apron	N/A
Flared End Section	N/A
Scour Protection	None / Good

Watercourse and Crossing Location
 Indian River, Christie St

ID Number
 47

Date
 Nov 8, 2021

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	20-20.5"
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input checked="" type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: _____	Other: _____	Other: <u>N/A</u>	Other: _____	

Performance Problems	Location	Overall Rating
Debris/Veg. Blockage > 1/3 of Rise	No N/A	Good <input checked="" type="checkbox"/>
Sediment Blockage 1/3 to 3/4 of Rise	No	
Buoyancy or Crushing-Related Failure	No	
Poor Channel Alignment	N/A	Fair <input type="checkbox"/>
Previous and/or Frequent Overtopping	Yes, Previous	
Local Scour	No	
Embankment Piping	Yes (side of headwall)	Poor <input type="checkbox"/>
Channel Degradation	No	
Headcut	No	Critical <input type="checkbox"/>
Embankment Slope Instability	No	
Sediment Blockage > 3/4 Rise	No	Unknown <input type="checkbox"/>
Sediment Blockage > 1/3 Rise Throughout Barrel	No	
Submerged / Ends Totally Buried	N/A	Performance Problems <input type="checkbox"/>
Aggressive Abrasion / Corrosion / Chemical Exposed Footing (Open Bottom Culvert Only)	No	
	No	
	No	

Category	Rating
Invert Deterioration	Good
Joint and Seams	Good
Corrosion / Chemical	Fair (nuts)
Cross-Section Deformation	Good
Cracking	Good
Headwall / Wingwall	Good
Apron	N/A
Flared End Section	N/A
Scour Protection	Good

Watercourse and Crossing Location

ID Number

Date

Muskraut

28

Nov 8
14-48

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input checked="" type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	35-36"
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input checked="" type="checkbox"/>	Span
Elliptical <input type="checkbox"/>	PVC <input type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	Rise cm

Performance Problems

Location

Overall Rating

Debris/Veg. Blockage > 1/3 of Rise	No	Good	<input checked="" type="checkbox"/>
Sediment Blockage 1/3 to 3/4 of Rise	No		
Buoyancy or Crushing-Related Failure	No		
Poor Channel Alignment	No	Fair	<input type="checkbox"/>
Previous and/or Frequent Overtopping	Yes		
Local Scour	No	Poor	<input type="checkbox"/>
Embankment Piping	No		
Channel Degradation	No	Critical	<input type="checkbox"/>
Headcut	No		
Embankment Slope Instability	No	Unknown	<input type="checkbox"/>
Sediment Blockage > 3/4 Rise	No		
Sediment Blockage > 1/3 Rise Throughout Barrel	No	Performance Problems	<input type="checkbox"/>
Submerged / Ends Totally Buried	No		
Aggressive Abrasion / Corrosion / Chemical Exposed Footing (Open Bottom Culvert Only)	Both No		
	No		
	N/A		

Category

Rating

Invert Deterioration	Good
Joint and Seams	Good
Corrosion / Chemical	Yes (grate)
Cross-Section Deformation	
Cracking	Good
Headwall / Wingwall	Good
Apron	N/A
Flared End Section	N/A
Scour Protection	None/Good

Grate: minor pest
 - partially submerged
 - overland flow erosion

Watercourse and Crossing Location

Muskraat

ID Number

30

Date

*Nov 8
12:37*

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input checked="" type="checkbox"/>	<i>10^m</i>
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input type="checkbox"/>	Span
Elliptical <input type="checkbox"/>	PVC <input checked="" type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	cm
Other: _____	Other: _____	Other: _____	Other: _____	Other: _____	Rise cm

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical
- Exposed Footing (Open Bottom Culvert Only)

Location

- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*
- No*

Overall Rating

- Good
- Fair
- Poor
- Critical
- Unknown
- Performance Problems

Category	Rating
Invert Deterioration	<i>Good</i>
Joint and Seams	<i>Good</i>
Corrosion / Chemical	<i>Good</i>
Cross-Section Deformation	<i>No</i>
Cracking	<i>Good</i>
Headwall / Wingwall	<i>N/A</i>
Apron	<i>N/A</i>
Flared End Section	<i>N/A</i>
Scour Protection	<i>Good</i>

Notes:

- Cable - crete scour protection*
- is recessed ~ 70 m*

Watercourse and Crossing Location

Indian River

ID Number

62

Date

Nov 8, 2021
10:53

Barrel Shape	Material	No. of Barrels	End Treatments		Dimension
			Upstream	Downstream	
Circular <input checked="" type="checkbox"/>	Timber <input type="checkbox"/>	One <input checked="" type="checkbox"/>	Projecting <input type="checkbox"/>	Projecting <input type="checkbox"/>	Diameter cm
Box <input type="checkbox"/>	Concrete <input type="checkbox"/>	Two <input type="checkbox"/>	Mitered <input type="checkbox"/>	Mitered <input type="checkbox"/>	11.75" Span
Pipe-Arch <input type="checkbox"/>	CMP <input type="checkbox"/>	Three <input type="checkbox"/>	Headwall <input type="checkbox"/>	Headwall <input type="checkbox"/>	Span cm
Elliptical <input type="checkbox"/>	PVC <input checked="" type="checkbox"/>	Four <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Wingwalls <input type="checkbox"/>	Rise cm
Other: _____	Other: <u>Corrugated</u>	Other: _____	Other: _____	Other: <u>N/A</u>	

Performance Problems

- Debris/Veg. Blockage > 1/3 of Rise
- Sediment Blockage 1/3 to 3/4 of Rise
- Buoyancy or Crushing-Related Failure
- Poor Channel Alignment
- Previous and/or Frequent Overtopping
- Local Scour
- Embankment Piping
- Channel Degradation
- Headcut
- Embankment Slope Instability
- Sediment Blockage > 3/4 Rise
- Sediment Blockage > 1/3 Rise Throughout Barrel
- Submerged / Ends Totally Buried
- Aggressive Abrasion / Corrosion / Chemical
- Exposed Footing (Open Bottom Culvert Only)

Location

- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No
- No

Overall Rating

- Good
- Fair
- Poor
- Critical
- Unknown
- Performance Problems

Category

Rating

- Invert Deterioration Good
- Joint and Seams Good
- Corrosion / Chemical Good
- ~~Cross-Section Deformation~~
- Cracking Good
- Headwall / Wingwall N/A
- Apron N/A
- Flared End Section N/A
- Scour Protection Good

Notes:

Recessed from river ~ 50m

APPENDIX H

Design Briefs for Storm Outfall Reconstruction

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 27

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 27 as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall 27 are shown in **Figure 1-1**. The storm sewer has a diameter of 300 mm and extends off of the corner joining Margaret Street to Moffat Street, outletting into the Muskrat River. Outfall 27 was identified to be in need of rehabilitation and was ranked as the highest priority site, of the total 17 sites that were assessed.




Figure 1-1: Location of Study Area for Storm Sewer Outfall 27

2 EXISTING CONDITIONS

2.1 Overview

Outfall 27 has completely failed, with disconnected pipe segments and a concrete headwall strewn throughout the study area (**Figure 2-1** and **Figure 2-2**). Under current conditions, stormwater discharges from a failed 300 mm cast iron pipe protruding from the valley slope (**Figure 2-3**) approximately 27 m from the edge of the Muskrat River. Water exiting the pipe appears to have created a large scarp that has a maximum width of ~13 m and is characterized by steep slopes exceeding 1.4H:1V in some places. Large amounts of debris, including concrete rubble, sewer pipe segments, and woody debris are found within the scarp. Some of the concrete rubble found within the site appears to have belonged to a manhole and/or drop structure that may have helped stormwater overcome the steep vertical gradient before discharging into the Muskrat River (**Figure 2-4**).



Figure 2-1: Debris within the Study Area



Figure 2-2: Failed Concrete Headwall and Pipe Segment



Figure 2-3: Remaining Pipe Protruding from the Slope



Figure 2-4: Possible Rubble from a Failed Manhole

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface above and surrounding the storm sewer pipe, extending into the Muskrat River to capture streambed tie-in elevations;
- Any visible storm sewer infrastructure near the outlet (invert and obvert, exposed pipe, headwall, etc.);
- Upstream maintenance hole lid and pipe invert;
- Top and bottom of bank elevations approximately 5-10 m upstream and downstream of the storm sewer outfall; and
- Ground shots at the edge of erosion scars and within the eroded areas.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on March 16th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-09 was advanced to a depth of 18.9 m below grade using a truck-mounted drill.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. In situ vane shear testing was carried out in the borehole to measure the undrained shear strength of the silty clay deposits. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

Fill material was encountered at the surface of the borehole, extending to 1.8 m below surface grade. The fill was variable but was described as brown sand and gravel to silty sand with trace asphaltic concrete. The fill material was underlain by native deposits of sandy silt (11 m thick), silty clay (5.8 m thick), and glacial till composed of grey sand and silt with gravel (extending to the termination depth of the borehole). Based on soil sample appearance, the groundwater level was estimated to be at approximately 12.2 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 27 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 9 trees were

inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 6 in the detailed design drawings shows the locations of the surveyed trees within the Outfall 27 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
831	White Ash	<i>Fraxinus americana</i>	Fair
832	White Spruce	<i>Picea glauca</i>	Fair-Good
NT1	Basswood	<i>Tilia americana</i>	Good
Bn1	Butternut	<i>Juglans cinerea</i>	Good
NT2	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
833	Sugar Maple	<i>Acer saccharum</i>	Good, Fair(12)
NT3	White Spruce	<i>Picea glauca</i>	Good
NT4	Manitoba Maple	<i>Acer negundo</i>	Fair
NT5	Manitoba Maple	<i>Acer negundo</i>	Fair

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 27 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction should be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees should be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Slope Stabilization – Slope erosion and failure should be restored by regrading to attain a natural long-term stable slope, followed by application of erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel bank are not compromised.

Outlet Protection – The design should consider appropriate protection to prevent erosion and scouring damage to the pipe, structures and associated channel works.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 27 are provided under a separate cover. Due to the presence of an over-steepened slope (exceeding 1.4H:1V) between the upstream storm sewer and the Muskrat River, the design proposes to overcome most of the vertical gradient by installing three 1500 mm maintenance holes, each incorporating an internal 250 mm diam. PVC drop structure. The most upstream drop structure is specified to have a depth of ~5 m, while the two downstream drop structures are to be ~4 m deep.

PVC pipes having a diameter of 300 mm are to be used for connecting the maintenance holes and conveying stormwater to the river. The storm sewer outlet is to be located above water surface elevations that occur during frequent flow events within the Muskrat River. A short runoff channel consisting of 750 mm deep angular stone is to be constructed at the pipe outlet to prevent scouring near the confluence with the river. A concrete headwall is specified to mitigate erosion near the outlet pipe and prevent scouring of the slope, and to allow for a stable confluence of the outfall channel with the Muskrat River.

Specific elements of the design and construction include removing existing debris within the scarp and the failed 300 mm cast iron pipe protruding from the slope. The existing guard rail is to be removed prior to construction and relocated. The proposed maintenance holes and sewer pipes are to be backfilled and vegetated with native riparian seed mix, shrubs, and trees, which are intended to provide additional slope stability and resist erosion from overland flow during extreme storm events.

The reconstruction of Outfall 27 is to be co-ordinated with downstream slope restoration works (design and tender to be completed by others). Co-ordination between these projects will ensure a smooth transition between reconstructed slopes, and has the potential to increase construction efficiency (e.g., by undertaking construction works during the same timeframe).

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Muskrat River provides habitat to both spring and fall spawning species. As a major watercourse, the Muskrat River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 7 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site's location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphotrichum novae-angliae</i>	New England Aster	1%
<i>Symphotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Acer rubrum</i>	Red Maple	3	5 gal. potted
<i>Acer saccharum</i>	Sugar Maple	3	5 gal. potted
<i>Picea glauca</i>	White Spruce	2	5 gal. potted
<i>Thuja occidentalis</i>	Eastern White Cedar	2	5 gal. potted
<i>Tilia americana</i>	Basswood	2	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
<i>Amelanchier arborea</i>	Downy Juneberry	8	2 gal. potted
<i>Cornus alternifolia</i>	Alternate-leaved Dogwood	8	2 gal. potted
<i>Cornus racemosa</i>	Grey dogwood	8	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	8	2 gal. potted
<i>Ribes hirtellum</i>	Smooth Gooseberry	7	2 gal. potted
<i>Rubus odoratus</i>	Flowering Raspberry	7	2 gal. potted
<i>Salix petiolaris</i>	Slender Willow	7	2 gal. potted
<i>Sambucus racemosa</i>	Red-berried Elder	7	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 9 live trees identified during the assessment (detailed previously in **Table 2-1**), 4 have been identified for removal. Trees identified for removal are listed in **Table 4-4** below and are shown on Sheet 6 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of page wire hoarding specified on Sheet 5 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Trees Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition
831	White Ash	<i>Fraxinus americana</i>	Fair
NT1	Basswood	<i>Tilia americana</i>	Good
NT4	Manitoba Maple	<i>Acer negundo</i>	Fair
NT5	Manitoba Maple	<i>Acer negundo</i>	Fair

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. As shown on Sheet 6 of the detailed design drawings, access routes and the staging and storage area are proposed within private property at 393 Moffat Street, for which an easement would be required. The reconstruction of Outfall 27 should be coordinated with downstream slope restoration works during the easement procurement process, as it may be possible to use the same easement on 393 Maffat Street for both projects. In all cases, an OLS should be retained to confirm property parcels and associated limits.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing

the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Muskrat River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access routes and the staging and storage area are shown on Sheet 6 of the drawing set. Access for construction is proposed from Moffat Street, passing through private property at 393 Moffat Street. The staging and storage area is also proposed to be located on 393 Moffat Street. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$647,520 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 27

PEMBROKE OUTLETS - OUTLET # 27					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS	\$25,000	\$25,000
2	Field Office	1	LS	\$3,000	\$3,000
3	Construction Layout, Utility & Locates	1	LS	\$10,000	\$10,000
4	Mobilization & Demobilization	1	LS	\$35,000	\$35,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$120,000	\$120,000
6	Clearing, Grubbing, and Vegetation Removal	1	LS	\$25,000	\$25,000
8	Supply, Install & Remove Temporary Construction Fence	50	m	\$15	\$750
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$35,000	\$35,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
11	Removal & Disposal of Concrete Headwall and Excess Pipe	1	LS	\$10,000	\$10,000
Subtotal Section A (Excl of HST)					\$268,750
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$60,000	\$60,000
13	Supply & Placement of Angular Channel Substrate	25	tonne	\$200	\$5,000
14	Supply & Placement of Concrete Headwall	1	ea	\$15,000	\$15,000
14	Supply & Placement of 300mm dia. PVC pipe including joint restraints	30	m	\$2,500	\$75,000
15	Supply & Placement of 1500mm dia. Maintenance Hole including 300mm dia. Drop pipe and Watertight Frame Cover	3	ea	\$25,000	\$75,000
16	Supply & Placement of Erosion Control Blanket - Coir Mat	800	m ²	\$8	\$6,400
17	Supply & Placement of Topsoil for Restoration (300mm for terraseed area & 150mm for Sod)	240	m ³	\$50	\$12,000
18	Supply & Application of Terraseed Mixture	800	m ²	\$8	\$6,400
19	Supply & Application of Sod	35	m ²	\$10	\$350
20	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	ii) Red Maple	3	ea	\$250	\$750
	ii) Sugar Maple	3	ea	\$250	\$750
	iii) White Spruce	2	ea	\$250	\$500
	iv) Eastern White Cedar	2	ea	\$250	\$500
	v) Basswood	2	ea	\$250	\$500
21	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Grey Dogwood	8	ea	\$45	\$360
	ii) Chokecherry	8	ea	\$45	\$360
	iii) Alternate Leaved Dogwood	8	ea	\$45	\$360
	iv) Downy juneberry	8	ea	\$45	\$360
	v) Smooth Gooseberry	7	ea	\$45	\$315
	vi) Flowering Raspberry	7	ea	\$45	\$315
	vii) Slender Willow	7	ea	\$45	\$315
	viii) Red-berried Elder	7	ea	\$45	\$315
Subtotal Section B (Excl of HST)					\$260,850

Section "C" – Provisional					
23	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
24	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$10,000
Section "D" – Contingency					
25	Contingency (20%)	1	LS	\$107,920	\$107,920
Subtotal Section D (Excl of HST)					\$107,920
Section "A" – Site Preparation & Removals					
Section "B" – Sewer Works, Channel Works and Restoration					
Section "C" – Provisional					
Section "D" – Contingency					
Sub Total (Exc of taxes)					
HST @ 13%					
Total Bid Price (Incl of taxes)					
Outlet # 27 Engineering Estimate (Inc. Contingency, Exc. HST)					\$647,520

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

- Dave Maunder – Project Manager
- Robert Amos – Water Resources Lead
- Golmar Golmohammadi – Water Resources Engineer
- Gabriel Dubé – Water Resources Specialist
- Yun Xia – Water Resources Specialist
- Palka Sharma – CAD Technician
- Julie Scott – Terrestrial Ecologist
- Jakub Ripley – GIS Specialist
- Darcy LaFramboise – Certified Arborist
- Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.



MEMORANDUM

April 1st, 2022

Dave Maunder

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 31

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 31 as well as the Detailed Design of the proposed outfall reconstruction.

Outfall 31 extends off of Moffat Street, outletting into the Indian River (**Figure 1-1**). The storm sewer pipe has a diameter of 300 mm and is located approximately 140 m upstream of the confluence of Indian River with Muskrat River. Outfall 31 was identified to be in need of rehabilitation and was ranked as the 5th highest priority site, of the total 17 sites that were assessed.




Figure 1-1: Location of Study Area for Storm Sewer Outfall 31

2 EXISTING CONDITIONS

2.1 Overview

As can be seen in **Figure 2-1** and **Figure 2-2**, the existing outfall is composed of a 300 mm PVC pipe that discharges into a 525 mm CSP half-pipe extending past the bottom of bank and into the Indian River. The CSP is in poor condition, as one section downstream has been undermined, and another has become entirely detached (**Figure 2-3** and **Figure 2-4**). The CSP also displays evidence of rust corrosion, and bank erosion was noted beneath the pipe.



Figure 2-1: PVC Pipe Outlet into the CSV Half-Pipe



Figure 2-2: CSV Half-Pipe



Figure 2-3: CSV Half-Pipe at the Edge of the Indian River (Looking Downstream)



Figure 2-4: CSV Half-Pipe at the Edge of the Indian River (Looking Upstream)

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface along the PVC storm sewer pipe and CSP half-pipe, extending into the Indian River to capture streambed tie-in elevations;
- Any visible storm sewer infrastructure near the outlet (invert and obvert, CSP half-pipe, headwall, etc.);
- Upstream maintenance hole lid and pipe invert;
- Top and bottom of bank elevations approximately 5-10 m upstream and downstream of the storm sewer outfall; and
- Ground shots at the edge of erosion scars and within the eroded areas.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on March 15th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-08 was advanced to a depth of 9.8 m below grade using a truck-mounted drill.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. In situ vane shear testing was carried out in the borehole to measure the undrained shear strength of the silty clay deposits. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

A 40 mm layer of asphaltic concrete was encountered at the surface, followed by a 200 mm layer of road base consisting of a brown crushed sand with gravel and some silt. Beneath the road base, a 1.9 m thick layer of fill was encountered, consisting of brown silty sand with trace clay. The fill material was underlain by native deposits of sand with some silt (2.8 m thick) and silty clay (extending to the termination depth of the borehole). Based on soil sample appearance, the groundwater level was estimated to be at approximately 4.3 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 31 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 12 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 5 in the

detailed design drawings shows the locations of the surveyed trees within the Outfall 31 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
NT1	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT2	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT3	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT4	Siberian Elm	<i>Ulmus pumila</i>	Good
NT5	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT6	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT7	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT8	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT9	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT10	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT11	Eastern White Cedar	<i>Thuja occidentalis</i>	Fair-Good
NT12	White Ash	<i>Fraxinus americana</i>	Dead

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 31 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Slope Stabilization – Slope erosion should be restored by regrading to attain a natural long-term stable slope, followed by application of erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel bank are not compromised.

Outlet Protection – The design should consider appropriate protection to prevent erosion and scouring damage to the pipe, structures and associated channel works.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 31 are provided under a separate cover. Due to the presence of an existing steep slope (exceeding 2.2H:1V) between the PVC pipe outlet and the Indian River, the design proposes to overcome much of the vertical gradient by installing a 1500 mm maintenance hole incorporating an internal 2.5 m deep (250 mm diam.) PVC drop-structure that connects to a 300 mm PVC sewer pipe. Downstream of the proposed maintenance hole, the pipe outlet is to be located above water surface elevations that occur during frequent flow events within the Indian River. Flows exiting the sewer pipe are to be conveyed to the Indian River via a 12 m long outfall channel constructed with 750 mm deep angular stone. A concrete headwall is specified to mitigate erosion near the outlet pipe and prevent scouring of the slope, and to allow for a stable confluence of the outfall channel with the Indian River.

Other elements of the design and reconstruction include removing the existing CSP half pipe and 4 m of the existing PVC pipe. The proposed maintenance hole and sewer pipe are to be backfilled and vegetated with native upland seed mix and shrubs, which are intended to provide additional slope stability and resist erosion from overland flow during extreme storm events. A vegetated buttress having a total length of ~6 m is proposed in order to provide bank protection near the confluence of the outfall channel with the Indian River.

As an additional measure to deter failure of the storm sewer under potential bank erosion, it is proposed to install the 300 mm storm sewer with Class 150 PVC (DR-18) pipe, complete with mechanical joint restraints.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

No tree removals are anticipated for the restoration of Outfall 31. However, if any tree removals become necessary, they should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period. We note that for this site in particular, no tree removals are required and in turn this window restriction will not apply.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Indian River provides habitat to both spring and fall spawning species. As a major watercourse, the Indian River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 6 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native shrubs within Pembroke and the site's location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1** and **Table 4-2**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Upland Mix (Application Rate: 25 kg/ha)		
<i>Asclepias syriaca</i>	Common Milkweed	5%
<i>Clematis virginiana</i>	Virgin's Bower	2%
<i>Fragaria virginiana</i>	Wild Strawberry	3%
<i>Monarda fistulosa</i>	Wild Bergamot	5%
<i>Panicum acuminatum</i> (<i>P. implicatum</i> ; <i>P. lanuginosum</i>)	Hairy Panic Grass	30%
<i>Rudbeckia hirta</i>	Black-eye Susan	15%
<i>Solidago canadensis</i>	Canada Goldenrod	8%
<i>Sporobolus cryptandrus</i>	Sand Dropseed	30%
<i>Symphotrichum cordifolium</i>	Heart-leaved Aster	1%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphotrichum novae-angliae</i>	New England Aster	1%
<i>Symphotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
Restoration Plantings			
<i>Cornus rugosa</i>	Round-leaved Dogwood	10	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	10	2 gal. potted
<i>Ribes hirtellum</i>	Smooth Gooseberry	10	2 gal. potted
<i>Rubus ideaus</i>	Wild Red Raspberry	10	2 gal. potted
<i>Spirea alba</i>	Narrow-leaved Meadowsweet	10	2 gal. potted
Vegetated Buttress Plantings			
<i>Cornus sericea</i>	Red-osier Dogwood	5	2 gal. potted
<i>Cornus rugosa</i>	Round-leaved Dogwood	5	2 gal. potted
<i>Salix petiolaris</i>	Slender Willow	5	2 gal. potted
<i>Spirea alba</i>	Narrow-leaved Meadowsweet	5	2 gal. potted
<i>Viburnum lentago</i>	Nannyberry	4	2 gal. potted

No tree removals are planned during construction. However, shrub plantings at 1 m spacing are proposed to restore and stabilize portions of the slope that will be disturbed. A denser planting of shrubs at 0.5 m spacing is proposed overtop the vegetated buttress along the river bank, providing additional erosion protection to the bank.

4.3.1 Removal Timing Window and Protection Measures

No tree removals are planned during construction, and in turn no timing window restrictions will apply.

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of page wire hoarding specified on Sheet 4 of the detailed design drawings, should be followed in order to mitigate against potential damages.

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. In all cases, an OLS should be retained to confirm property parcels and associated limits. In some cases, it may be necessary to require temporary or permanent easements.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Indian River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. Any tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access for construction is proposed from Moffat Street. The access routes are shown on Sheet 5 of the drawing set. A staging and storage area has also been shown. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$226,148 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 31

PEMBROKE OUTLETS - OUTLET # 31					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS		\$0
2	Field Office	1	LS		\$0
3	Construction Layout, Utility & Locates	1	LS	\$8,000	\$8,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$12,000	\$10,000
6	Clearing, Grubbing, and Vegetation Removal	1	LS	\$15,000	\$15,000
7	Supply, Install & Remove Temporary Hoarding / Sediment Control Fence	65	m	\$20	\$1,300
8	Supply, Install & Remove Temporary Construction Fence	30	m	\$15	\$450
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$20,000	\$20,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
11	Removal & Disposal of CSP Half Pipe, Excess Pipe	1	LS	\$8,000	\$8,000
Subtotal Section A (Excl of HST)					\$77,750
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$10,000	\$10,000
13	Supply & Placement of 300mm dia. PVC pipe	10.6	m	\$1,800	\$19,080
14	Supply & Placement of 250mm dia. PVC drop pipe	6	m	\$1,650	\$9,900
15	Supply & Placement of 1200mm dia. Maintenance Hole including Watertight Frame Cover	1	ea	\$15,000	\$15,000
16	Supply & Placement of Concrete Headwall	1	ea	\$10,000	\$10,000
17	Supply & Placement of Angular Channel Substrate	55	tonne	\$200	\$11,000
18	Supply & Placement of Vegetated Buttress				
	Roundstone as specified	45	tonne	\$200	\$9,000
	Topsoil to enhance vegetation	10	m ³	\$50	\$500
	Stock Plantings (2 gal potted @ 0.5 spacing)				
	i) Red-osier Dogwood	5	ea	\$45	\$225
	ii) Round Leaved Dogwood	5	ea	\$45	\$225
	iii) Slender Willow	5	ea	\$45	\$225
	iv) Nannyberry	4	ea	\$45	\$180
	v) Narrow-Leaved Meadowsweet	5	ea	\$45	\$225
19	Supply & Placement of Erosion Control Blanket - Coir Mat	155	m ²	\$8	\$1,240
20	Supply & Placement of Topsoil for Restoration (300mm)	50	m ³	\$50	\$2,500
21	Supply & Application of Terraseed Mixture (Upland)	100	m ²	\$8	\$800
22	Supply & Application of Terraseed Mixture (Riparian)	55	m ²	\$8	\$440
23	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Round Leaved Dogwood	10	ea	\$45	\$450
	ii) Chokecherry	10	ea	\$45	\$450
	iii) Smooth Gooseberry	10	ea	\$45	\$450
	iv) Wild Red Raspberry	10	ea	\$45	\$450
	v) Narrow-Leaved Meadowsweet	10	ea	\$45	\$450
Subtotal Section B (Excl of HST)					\$92,790

Section "C" – Provisional					
24	Full Road Repair (Removal, Granular Placement, New Asphalt, Buffer Restoration)	65	m ²	\$250	\$16,250
25	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
26	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$26,250
Section "D" – Contingency					
27	Contingency (20%)	1	LS	\$39,358	\$39,358
Subtotal Section D (Excl of HST)					\$39,358
Section "A" – Site Preparation & Removals					\$77,750
Section "B" – Sewer Works, Channel Works and Restoration					\$92,790
Section "C" – Provisional					\$26,250
Section "D" – Contingency					\$39,358
Sub Total (Exc of taxes)					\$236,148
HST @ 13%					\$30,699
Total Bid Price (Incl of taxes)					\$266,847
Outlet # 31 Engineering Estimate (Inc. Contingency, Exc. HST)					\$236,148

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

- Dave Maunder – Project Manager
- Robert Amos – Water Resources Lead
- Golmar Golmohammadi – Water Resources Engineer
- Gabriel Dubé – Water Resources Specialist
- Yun Xia – Water Resources Specialist
- Palka Sharma – CAD Technician
- Julie Scott – Terrestrial Ecologist
- Jakub Ripley – GIS Specialist
- Darcy LaFramboise – Certified Arborist
- Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.



MEMORANDUM

April 1st, 2022

Dave Maunder

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 35

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 35 as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall 35 are shown in **Figure 1-1**. The outfall consists of a series of disconnected box culverts and concrete pipe segments that convey water from ditches upstream of a decommissioned road to a scour pool, which is connected to a 20 m long outfall channel that discharges into Muskrat River, approximately 35 m upstream of Boundary Road. The decommissioned road runs parallel to Upper Valley Drive and connects Boundary Road East to the backlot of O’Kenny Craft Spirits off of International Drive. Outfall 35 was identified to be in need of rehabilitation and was ranked as the 3rd highest priority site, of the total 17 sites that were assessed.



Figure 1-1: Location of Study Area for Storm Sewer Outfall 35

2 EXISTING CONDITIONS

2.1 Overview

The assessment of Outfall 35 revealed that water is collected from upstream ditches by a concrete box culvert (Box Culvert #1, **Figure 2-1**) that is in fair condition and passes under a decommissioned asphalt road. On the downstream side of the road, it appears that both the box culvert and a ditch were intended to feed into a second concrete box culvert (Box Culvert #2, **Figure 2-2**), which is now severely deteriorated and segmented, causing water to flow around it. Water then passes into a series of disconnected 1050 mm concrete pipe segments (**Figure 2-3**), before discharging into a scour pool (**Figure 2-4**) that connects to the Muskrat River via a 20 m long outfall channel. Based on the observed existing conditions, it is unclear whether Box Culvert #2 and the concrete pipe were initially connected or simply joined by an open-air channel. Channel gradient is high throughout the study area, having an average of 10% between the outlet of Box Culvert 1 and the scour pool.



Figure 2-1: Box Culvert under the Asphalt Road (Box Culvert #1)



Figure 2-2: Failed Box Culvert (Box Culvert #2)



Figure 2-3: Concrete Pipe Segments



Figure 2-4: Scour Pool

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface above and surrounding the culverts and pipe segments, extending ~5 m past the outlet of the scour pool;
- Thalweg of the channel between disconnected culvert and pipe segments;
- Any visible storm sewer infrastructure near the outlet (inverts and obverts, top of culvert and pipe segments, etc.);
- Cross sections and thalweg shots of ditches that feed into the culverts; and
- Ground shots at the edge of erosion scars and within the eroded areas.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on February 14th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, as well as make recommendations regarding channel bank stabilization measures. One (1) borehole designated as 22-02 was advanced to a depth of 4.9 m below grade using portable drilling equipment.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

Fill material was encountered at the surface of the borehole, extending to 1.4 m below surface grade. The fill consisted of 200 mm of gravelly sand over brown silty clay fill with trace sand. The fill material was underlain by native deposits of silty clay, extending to the termination depth of the borehole. Based on soil sample appearance, the groundwater level was estimated to be at approximately 3.0 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 35 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 8 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 6 in the detailed design drawings shows the locations of the surveyed trees within the Outfall 35 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
860	White Spruce	<i>Picea glauca</i>	Good
861	White Pine	<i>Pinus strobus</i>	Good
862	White Ash	<i>Fraxinus americana</i>	Fair
863	Black Ash	<i>Fraxinus nigra</i>	Fair-Good
864	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
865	White Pine	<i>Pinus strobus</i>	Good
NT1	Common Apple	<i>Malus spp.</i>	Fair
NT2	Willow sp.	<i>Salix spp.</i>	Good

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 35 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Channel Bank Stabilization – Toe erosion and slope failures along the outfall channel should be restored by regrading to attain a long-term stable slope, followed by the application of channel bank and toe erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel banks are not compromised.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 35 are provided under a separate cover. The proposed design consists of restoring the outfall channel using a series of cascades and pools, allowing for a more gradual bed level change

than that achieved across the existing channel bed and deteriorated conveyance structures. This approach was selected over riffle-pool morphology because the gradient between the upstream and downstream tie-in points is 10%, whereas engineered riffle slopes do not usually exceed 3%.

Specific elements of the design and construction include removing the existing deteriorated and segmented concrete box culvert (Box Culvert 2) and sewer pipe. The proposed works will include substantial amounts of cutting in order to provide a more uniform channel gradient. Bank slopes are to be regraded and vegetated with native riparian seed mix, shrubs, and trees, which are intended to provide additional slope stability and resist erosion from overland flow during extreme storm events.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Muskrat River provides habitat to both spring and fall spawning species. As a major watercourse, the Muskrat River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 7 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site's location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphotrichum novae-angliae</i>	New England Aster	1%
<i>Symphotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Acer saccharum</i>	Sugar Maple	3	5 gal. potted
<i>Picea glauca</i>	White Spruce	3	5 gal. potted
<i>Pinus strobus</i>	White Pine	2	5 gal. potted
<i>Thuja occidentalis</i>	Eastern White Cedar	2	5 gal. potted
<i>Tilia americana</i>	Basswood	2	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
<i>Amelanchier arborea</i>	Downy Juneberry	10	2 gal. potted
<i>Cornus alternifolia</i>	Alternate-leaved Dogwood	10	2 gal. potted
<i>Cornus rugosa</i>	Round-leaved Dogwood	10	2 gal. potted
<i>Lonicera canadensis</i>	Northern Fly Honeysuckle	10	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	10	2 gal. potted
<i>Ribes hirtellum</i>	Smooth Gooseberry	10	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 8 live trees identified during the assessment (detailed previously in **Table 2-1**), 4 have been identified for removal. Trees identified for removal are listed in **Table 4-4** below and are shown on Sheet 6 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of page wire hoarding specified on Sheet 5 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Trees Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition
860	White Spruce	<i>Picea glauca</i>	Good
862	White Ash	<i>Fraxinus americana</i>	Fair
NT1	Common Apple	<i>Malus spp.</i>	Fair
NT2	Willow sp.	<i>Salix spp.</i>	Good

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. In all cases, an OLS should be retained to confirm property parcels and associated limits. In some cases, it may be necessary to require temporary or permanent easements.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on

requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Muskrat River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access for construction is proposed from Boundary Road East through the decommissioned asphalt road. The access routes are shown on Sheet 6 of the drawing set. A staging and storage area has also been shown. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$263,100 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 35

PEMBROKE OUTLETS - OUTLET # 35					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS		\$0
2	Field Office	1	LS		\$0
3	Construction Layout, Utility & Locates	1	LS	\$8,000	\$8,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$15,000	\$10,000
6	Clearing, Grubbing, and Vegetation Removal	1	LS	\$25,000	\$25,000
7	Supply, Install & Remove Temporary Erosion & Sediment Control Fence	100	m	\$20	\$2,000
8	Supply, Install & Remove Temporary Construction Fence	32	m	\$15	\$480
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$20,000	\$20,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
11	Removal & Disposal of Concrete Headwalls and Concrete Sewer Pipe	1	LS	\$20,000	\$20,000
Subtotal Section A (Excl of HST)					\$100,480
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$15,000	\$15,000
17	Supply & Placement of Angular Channel Substrate	120	tonne	\$200	\$24,000
17	Supply & Placement of Boulder Ribs (Boulder size 1mX1mX1m)	90	tonne	\$235	\$21,150
19	Supply & Placement of Erosion Control Blanket - Coir Mat	370	m ²	\$8	\$2,960
20	Supply & Placement of Topsoil for Restoration (300mm)	110	m ³	\$50	\$5,500
21	Supply & Application of Terraseed Mixture	370	m ²	\$8	\$2,960
23	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	i) Sugar Maple	3	ea	\$250	\$750
	ii) White Spruce	3	ea	\$250	\$750
	iii) White Pine	2	ea	\$250	\$500
	iv) Eastern White Cedar	2	ea	\$250	\$500
	v) Basswood	2	ea	\$250	\$500
23	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Round Leaved Dogwood	10	ea	\$45	\$450
	ii) Chokecherry	10	ea	\$45	\$450
	iii) Smooth Gooseberry	10	ea	\$45	\$450
	iv) Alternate-Leaved Dogwood	10	ea	\$45	\$450
	v) Downy juneberry	10	ea	\$45	\$450
	vi) Northern Fly Honeysuckle	10	ea	\$45	\$450
Subtotal Section B (Excl of HST)					\$77,270

Section "C" – Provisional					
24	Asphalt Road Repair (Removal, Granular Placement, New Asphalt, Buffer Restoration)	126	m ²	\$250	\$31,500
25	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
26	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$41,500
Section "D" – Contingency					
27	Contingency (20%)	1	LS	\$43,850	\$43,850
Subtotal Section D (Excl of HST)					\$43,850
Section "A" – Site Preparation & Removals					\$100,480
Section "B" – Sewer Works, Channel Works and Restoration					\$77,270
Section "C" – Provisional					\$41,500
Section "D" – Contingency					\$43,850
Sub Total (Exc of taxes)					\$263,100
HST @ 13%					\$34,203
Total Bid Price (Incl of taxes)					\$297,303
Outlet # 35 Engineering Estimate (Inc. Contingency, Exc. HST)					\$263,100

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

Dave Maunder – Project Manager
 Robert Amos – Water Resources Lead
 Golmar Golmohammadi – Water Resources Engineer
 Gabriel Dubé – Water Resources Specialist
 Yun Xia – Water Resources Specialist
 Palka Sharma – CAD Technician
 Julie Scott – Terrestrial Ecologist
 Jakub Ripley – GIS Specialist
 Darcy LaFramboise – Certified Arborist
 Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.



MEMORANDUM

April 1st, 2022

Dave Maunder

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 41

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 41 as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall 41 are shown in **Figure 1-1**. The outfall pipe has a diameter of 600 mm and extends off of Eganville Road, outletting into the Indian River, immediately downstream of the Eganville Road bridge crossing. Outfall 41 was identified to be in need of rehabilitation and was ranked as the 2nd highest priority site, of the total 17 sites that were assessed.



Figure 1-1: Location of Study Area for Storm Sewer Outfall 41

2 EXISTING CONDITIONS

2.1 Overview

The assessment of Outfall 41 revealed that it has been outflanked and is in critical condition (**Figure 2-1** and **Figure 2-2**). The concrete headwall and 600 mm sewer pipe have been undermined, which appears to have caused settling of the outfall structure, thereby placing stress on the concrete pipe. Two points of failure were noted along the concrete pipes: a 1" wide crack along the exposed outlet pipe that was leaking water (**Figure 2-3**), and a 1" wide gap between two pipe segments (**Figure 2-4**).



Figure 2-1: Outflanked Outlet Pipe



Figure 2-2: View of Outfall 41 Looking Downstream



Figure 2-3: Cracked Concrete Pipe



Figure 2-4: Disconnected Pipe Segments

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface above the storm sewer pipe, extending into the Indian River to capture streambed tie-in elevations;
- Any visible storm sewer infrastructure near the outlet (invert and obvert, exposed pipe, headwall, etc.);
- Upstream maintenance hole lid and pipe inverts;
- Top and bottom of bank elevations approximately 5-10 m upstream and downstream of the storm sewer outfall; and
- Ground shots beside the exposed pipe, i.e., within eroded areas.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on February 11th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-01 was advanced to a depth of 4.3 m below grade using portable drilling equipment.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

A 75 mm thick topsoil layer was encountered at the ground surface, followed by a 1 m layer of fill material composed of brown sand and silt with trace gravel. The fill material was underlain by native deposits of sand with silt (2.1 m thick) and silty clay (extending to the termination depth of the borehole). Based on soil sample appearance, the groundwater level was estimated to be at approximately 2.1 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 41 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 15 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 5 in the detailed design drawings shows the locations of the surveyed trees within the Outfall 41 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
846	Manitoba Maple	<i>Acer negundo</i>	Good
847	Manitoba Maple	<i>Acer negundo</i>	Fair
848	Manitoba Maple	<i>Acer negundo</i>	Fair-Poor
849	Manitoba Maple	<i>Acer negundo</i>	Fair
850	Manitoba Maple	<i>Acer negundo</i>	Good, Fair(23), Fair-Poor(26)
851	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
852	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
853	White Ash	<i>Fraxinus americana</i>	Good
854	White Ash	<i>Fraxinus americana</i>	Good
855	Manitoba Maple	<i>Acer negundo</i>	Fair-Poor
856	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
857	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
858	Manitoba Maple	<i>Acer negundo</i>	Fair-Poor
859	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
NT1	Manitoba Maple	<i>Acer negundo</i>	Fair

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 41 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Channel Bank Stabilization – Toe erosion and slope failures should be restored by regrading to attain a natural long-term stable slope, followed by the application of channel bank and toe erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel banks are not compromised.

Outlet Protection – The design should consider appropriate protection to prevent erosion and scouring damage to the pipe, structures and associated channel works.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 41 are provided under a separate cover. The proposed design consists of removing the 5 m portion of exposed concrete pipe and the existing headwall, such that the outlet is recessed from the Indian River. A new concrete headwall is proposed to mitigate erosion near the outlet pipe and prevent scouring of the slope, and to allow for a stable confluence of the outfall channel with the Indian River.

Additional erosion protection works include a 5 m long rip-rap lined scour pool between the outlet and the Indian River. Furthermore, a vegetated buttress having a total length of ~13 m is proposed to provide bank protection near the outfall and to prevent exposure of the remaining sewer pipe.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Indian River provides habitat to both spring and fall spawning species. As a major watercourse, the Indian River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 6 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site’s location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil’s Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin’s Bower	4%

<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphyotrichum novae-angliae</i>	New England Aster	1%
<i>Symphyotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Picea glauca</i>	White Spruce	5	5 gal. potted
<i>Thuja occidentalis</i>	Eastern White Cedar	5	5 gal. potted
<i>Tilia americana</i>	Basswood	5	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
Restoration Plantings			
<i>Amelanchier arborea</i>	Downy Juneberry	15	2 gal. potted
<i>Cornus rugosa</i>	Round-leaved Dogwood	15	2 gal. potted
<i>Lonicera canadensis</i>	Northern Fly Honeysuckle	15	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	15	2 gal. potted
<i>Spirea alba</i>	Narrow-leaved Meadowsweet	15	2 gal. potted
Vegetated Buttress Plantings			
<i>Cornus sericea</i>	Red-osier Dogwood	8	2 gal. potted
<i>Salix petiolaris</i>	Slender Willow	8	2 gal. potted
<i>Spirea alba</i>	Narrow-leaved Meadowsweet	8	2 gal. potted
<i>Viburnum lentago</i>	Nannyberry	8	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 15 live trees identified during the assessment (detailed previously in **Table 2-1**), 10 have been identified for removal. Trees identified for removal are listed in **Table 4-4** below and are shown on Sheet 5 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protection measures, consisting of page wire hoarding specified on Sheet 4 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Trees Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition
846	Manitoba Maple	<i>Acer negundo</i>	Good
847	Manitoba Maple	<i>Acer negundo</i>	Fair
848	Manitoba Maple	<i>Acer negundo</i>	Fair-Poor
852	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
853	White Ash	<i>Fraxinus americana</i>	Good
854	White Ash	<i>Fraxinus americana</i>	Good
855	Manitoba Maple	<i>Acer negundo</i>	Fair-Poor
856	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
857	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
NT1	Manitoba Maple	<i>Acer negundo</i>	Fair

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. In all cases, an OLS should be retained to confirm property parcels and associated limits. In some cases, it may be necessary to require temporary or permanent easements.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species

or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Indian River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water

around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access for construction is proposed from Eganville Road. The access routes are shown on Sheet 5 of the drawing set. A staging and storage area has also been shown. A section of the guard rail along Eganville Road is to be removed prior construction to facilitate site access, and is to be replaced upon completion of construction. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$220,386 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 41

PEMBROKE OUTLETS - OUTLET # 41					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS		\$0
2	Field Office	1	LS		\$0
3	Construction Layout, Utility & Locates	1	LS	\$10,000	\$10,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$20,000	\$10,000
6	Clearing, Grubbing, and Vegetation Removal	1	LS	\$25,000	\$25,000
7	Supply, Install & Remove Temporary Erosion & Sediment Control Fence	65	m	\$20	\$1,300
8	Supply, Install & Remove Temporary Construction Fence	60	m	\$15	\$900
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$15,000	\$15,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
11	Removal & Disposal of Concrete Headwall and Excess Pipe	1	LS	\$20,000	\$20,000
Subtotal Section A (Excl of HST)					\$97,200
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$10,000	\$10,000
13	Supply & Placement of Angular Channel Substrate	35	tonne	\$200	\$7,000
14	Supply & Placement of Concrete Headwall	1	ea	\$12,000	\$12,000
15	Supply & Placement of Vegetated Buttress				
	Roundstone as specified	75	tonne	\$200	\$15,000
	Topsoil to enhance vegetation	15	m ³	\$50	\$750
	Stock Plantings (2 gal potted @ 0.5 spacing)				
	i) Red-osier Dogwood	8	ea	\$45	\$360
	ii) Slender Willow	8	ea	\$45	\$360
	iii) Nannyberry	8	ea	\$45	\$360
	iv) Narrow-Leaved Meadowsweet	8	ea	\$45	\$360
16	Supply & Placement of Erosion Control Blanket - Coir Mat	90	m ²	\$8	\$720
17	Supply & Placement of Topsoil for Restoration (300mm for terraseed area & 150mm for Sod)	75	m ³	\$50	\$3,750
18	Supply & Application of Terraseed Mixture	90	m ²	\$8	\$720
19	Supply & Application of Sod	295	m ²	\$10	\$2,950
20	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	ii) White Spruce	5	ea	\$250	\$1,250
	ii) Eastern White Cedar	5	ea	\$250	\$1,250
	iii) Basswood	5	ea	\$250	\$1,250
21	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Round Leaved Dogwood	15	ea	\$45	\$675
	ii) Chokecherry	15	ea	\$45	\$675
	iii) Narrow-Leaved Meadowsweet	15	ea	\$45	\$675
	iv) Downy juneberry	15	ea	\$45	\$675
	v) Northern Fly Honeysuckle	15	ea	\$45	\$675
Subtotal Section B (Excl of HST)					\$61,455

Section "C" – Provisional					
22	Replace/ Repair Concrete Sidewalk, Curb & Sod	1	LS	\$15,000	\$15,000
23	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
24	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$25,000
Section "D" – Contingency					
25	Contingency (20%)	1	LS	\$36,731	\$36,731
Subtotal Section D (Excl of HST)					\$36,731
Section "A" – Site Preparation & Removals					\$97,200
Section "B" – Sewer Works, Channel Works and Restoration					\$61,455
Section "C" – Provisional					\$25,000
Section "D" – Contingency					\$36,731
Sub Total (Exc of taxes)					\$220,386
HST @ 13%					\$28,650
Total Bid Price (Incl of taxes)					\$249,036
Outlet # 41 Engineering Estimate (Inc. Contingency, Exc. HST)					\$220,386

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

- Dave Maunder – Project Manager
- Robert Amos – Water Resources Lead
- Golmar Golmohammadi – Water Resources Engineer
- Gabriel Dubé – Water Resources Specialist
- Yun Xia – Water Resources Specialist
- Palka Sharma – CAD Technician
- Julie Scott – Terrestrial Ecologist
- Jakub Ripley – GIS Specialist
- Darcy LaFramboise – Certified Arborist
- Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.



MEMORANDUM

April 1st, 2022

Dave Maunder

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

Head Office:

2600 Skymark Ave, Building 6, Suite 202, L4W 5B2
Tel: 905-629-0099 Fax: 905-629-0089

Branch Office:

55 Regal Road, Unit 3, Guelph, Ontario, N1K 1B6
Tel: 519-224-3740 • Fax: 519-224-3750

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 42

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 42 as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall 42 are shown in **Figure 1-1**. The storm sewer has a diameter of 600 mm that extends off of Everett Street, outletting into a 30 m long outfall channel that discharges into an outside bend of the Indian River, approximately 410 m upstream of the confluence with the Muskrat River. Outfall 42 was identified to be in need of rehabilitation and was ranked as the 7th highest priority site, of the total 17 sites that were assessed.




Figure 1-1: Location of Study Area for Storm Sewer Outfall 42

2 EXISTING CONDITIONS

2.1 Overview

The existing outfall structure consists of a 600 mm concrete sewer pipe, a concrete headwall, and failed concrete wingwalls (**Figure 2-1**). The sewer pipe outlets into a 30 m long outfall channel (**Figure 2-2**), with substantial bank erosion and downcutting noted at the downstream extents of the channel (**Figure 2-3** and **Figure 2-4**). Channel gradient is very high throughout the study area, having an average of 19% between the outlet and the Indian River.



Figure 2-1: Concrete Pipe Outlet with Headwall and Failed Wingwalls



Figure 2-2: Outlet and Upstream Extents of the Outfall Channel



Figure 2-3: Erosion at the Downstream Extents of the Outfall Channel (Looking Downstream)



Figure 2-4: Erosion at the Downstream Extents of the Outfall Channel (Looking Upstream)

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface above the storm sewer pipe;
- Survey points to characterize the outfall channel (cross-sections, thalweg, top-of-bank, etc.), extending into the Indian River to capture streambed tie-in elevations;
- Any visible storm sewer infrastructure near the outlet (invert and obvert, headwall, etc.);
- Top and bottom of bank elevations along the Indian River, extending approximately 5-10 m upstream and downstream of the confluence with the outfall channel; and
- Additional ground shots within the outfall channel to capture erosion.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on February 16th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-04 was advanced to a depth of 10.2 m below grade portable drilling equipment.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. In situ vane shear testing was carried out in the borehole to measure the undrained shear strength of the silty clay deposits. Dynamic cone penetration testing (DCPT) was also carried out in this borehole. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

Fill material was encountered at the surface of the borehole, extending to 1.2 m below surface grade. The fill consisted of dark brown sand and silt with some gravel. The fill material was underlain by native deposits of clayey sand (1.8 m thick), clayey silt (1.8 m thick), silty clay (1.5 m thick), and glacial till primarily composed of clayey sand and silt with some gravel (extending to the sampling termination depth at 7.0 m below surface grade). The borehole was further advanced by means of a DCPT and terminated at a depth of about 10.2 m due to refusal within the inferred glacial till on cobbles or boulders. Blow counts recorded during the DCPT test ranged from 14 to 58 blows per 300 mm. Based on soil sample appearance, the groundwater level was estimated to be at approximately 4.9 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 42 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 11 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 6 in the detailed design drawings shows the locations of the surveyed trees within the Outfall 42 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
835	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
836	Manitoba Maple	<i>Acer negundo</i>	Good
837	Manitoba Maple	<i>Acer negundo</i>	Good
838	Manitoba Maple	<i>Acer negundo</i>	Good
839	Manitoba Maple	<i>Acer negundo</i>	Fair
840	Manitoba Maple	<i>Acer negundo</i>	Good
841	Manitoba Maple	<i>Acer negundo</i>	Good
842	Manitoba Maple	<i>Acer negundo</i>	Good
843	White Ash	<i>Fraxinus americana</i>	Fair
844	White Elm	<i>Ulmus americana</i>	Good
845	White Ash	<i>Fraxinus americana</i>	Fair-Good(26), Fair(20)

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 42 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Channel Bank Stabilization – Toe erosion and slope failures should be restored by regrading to attain a natural long-term stable slope, followed by the application of channel bank and toe erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel banks are not compromised.

Outlet Protection – The design should consider appropriate protection to prevent erosion and scouring damage to the pipe, structures and associated channel works.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 42 are provided under a separate cover. Due to the presence of a very high gradient (19%) between the existing outlet and the Indian River, the design proposes to reduce stormwater velocity by extending the storm sewer with 600 mm PVC pipes and incorporating a 1500 mm maintenance hole with an internal 8.5 m deep (300 mm diam.) PVC drop structure. A second maintenance hole having a diameter of 1200 mm is also proposed 7 m downstream of the first maintenance hole. A 3 m wide swale lined with rip-rap is to be constructed overtop the proposed pipe extension, with the intent of directing accumulated overland flow into the Indian River and protecting the sewer infrastructure from erosion.

The pipe outlet is to be located above water surface elevations that occur during frequent flow events within the Indian River. A 12 m long runoff channel consisting of 750 mm deep angular stone is to be constructed at the pipe outlet to prevent scouring near the confluence with the river. In addition, a concrete headwall is specified to mitigate erosion near the outlet pipe and prevent scouring of the slope, and to allow for a stable confluence of the outfall channel with the Indian River.

Specific elements of the design and construction include removing the existing concrete headwall and 4.6 m of the storm pipe to enable. Slopes along the existing outfall channel are to be regraded and vegetated with native riparian seed mix, trees, and shrubs, which are intended to provide additional slope stability and resist erosion from overland flow during extreme storm events. A vegetated buttress having a total length of ~8 m is proposed in order to provide bank protection near the confluence of the runoff channel with the Indian River.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Indian River provides habitat to both spring and fall spawning species. As a major watercourse, the Indian River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 7 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site's location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphotrichum novae-angliae</i>	New England Aster	1%
<i>Symphotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Acer rubrum</i>	Red Maple	6	5 gal. potted
<i>Quercus macrocarpa</i>	Bur Oak	6	5 gal. potted
<i>Thuja occidentalis</i>	Eastern White Cedar	6	5 gal. potted
<i>Tilia americana</i>	Basswood	6	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
Restoration Plantings			
<i>Amelanchier arborea</i>	Downy Juneberry	18	2 gal. potted
<i>Cornus alternifolia</i>	Alternate-leaved Dogwood	18	2 gal. potted
<i>Cornus rugosa</i>	Round-leaved Dogwood	18	2 gal. potted
<i>Lonicera canadensis</i>	Northern Fly Honeysuckle	18	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	16	2 gal. potted
<i>Rubus ideaus</i>	Wild Red Raspberry	16	2 gal. potted
<i>Sambucus racemosa</i>	Red-berried Elder	16	2 gal. potted
Vegetated Buttress Plantings			
<i>Cornus sericea</i>	Red-osier Dogwood	5	2 gal. potted
<i>Salix petiolaris</i>	Slender Willow	5	2 gal. potted
<i>Spiraea alba</i>	Narrow-leaved Meadowsweet	5	2 gal. potted
<i>Viburnum lentago</i>	Nannyberry	5	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 11 live trees identified during the assessment (detailed previously in **Table 2-1**), 8 have been identified for removal. Trees identified for removal are listed in **Table 4-4** below and are shown on Sheet 6 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of page wire hoarding specified on Sheet 5 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Trees Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition
835	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
836	Manitoba Maple	<i>Acer negundo</i>	Good
837	Manitoba Maple	<i>Acer negundo</i>	Good
839	Manitoba Maple	<i>Acer negundo</i>	Fair
842	Manitoba Maple	<i>Acer negundo</i>	Good
843	White Ash	<i>Fraxinus americana</i>	Fair
844	White Elm	<i>Ulmus americana</i>	Good
845	White Ash	<i>Fraxinus americana</i>	Fair-Good(26), Fair(20)

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. In all cases, an OLS should be retained to confirm property parcels and associated limits. In some cases, it may be necessary to require temporary or permanent easements.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Indian River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access routes are shown on Sheet 6 of the drawing set, along with a staging and storage area. Access for construction is proposed from Everett Street, which will require temporary lane closure. A cedar hedge is to be removed prior construction to facilitate site access. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting.



April 1st, 2022

If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$460,230 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 42

PEMBROKE OUTLETS - OUTLET # 42					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS	\$12,000	\$12,000
2	Field Office	1	LS	\$3,000	\$3,000
3	Construction Layout, Utility & Locates	1	LS	\$10,000	\$10,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$20,000	\$10,000
6	Clearing, Grubbing, and Vegetation Removal	1	LS	\$25,000	\$25,000
7	Supply, Install & Remove Temporary Erosion & Sediment Control Fence	90	m	\$20	\$1,800
8	Supply, Install & Remove Temporary Construction Fence	25	m	\$15	\$375
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$15,000	\$15,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
11	Removal & Disposal of Concrete Headwall and Excess Pipe	1	LS	\$15,000	\$15,000
Subtotal Section A (Excl of HST)					\$107,175
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$40,000	\$40,000
13	Supply & Placement of Angular Channel Substrate	320	tonne	\$200	\$64,000
14	Supply & Placement of Concrete Headwall	1	ea	\$15,000	\$15,000
14	Supply & Placement of 600mm dia. PVC pipe including joint restraints	25.7	m	\$2,500	\$64,250
15	Supply & Placement of 1200mm dia. Maintenance Hole including Watertight Frame Cover	1	ea	\$15,000	\$15,000
15	Supply & Placement of 1500mm dia. Maintenance Hole including 300mm dia. Drop pipe and Watertight Frame Cover	1	ea	\$25,000	\$25,000
15	Supply & Placement of Vegetated Buttress				
	Roundstone as specified	50	tonne	\$200	\$10,000
	Topsoil to enhance vegetation	10	m ³	\$50	\$500
	Stock Plantings (2 gal potted @ 0.5 spacing)				
	i) Red-osier Dogwood	5	ea	\$45	\$225
	ii) Slender Willow	5	ea	\$45	\$225
	iii) Nannyberry	5	ea	\$45	\$225
	iv) Narrow-Leaved Meadowsweet	5	ea	\$45	\$225
16	Supply & Placement of Erosion Control Blanket - Coir Mat	125	m ²	\$8	\$1,000
17	Supply & Placement of Topsoil for Restoration (300mm for terraseed area & 150mm for Sod)	55	m ³	\$50	\$2,750
18	Supply & Application of Terraseed Mixture	125	m ²	\$8	\$1,000
19	Supply & Application of Sod	55	m ²	\$10	\$550
20	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	ii) Red Maple	6	ea	\$250	\$1,500
	ii) Bur Oak	6	ea	\$250	\$1,500
	iii) Eastern White Cedar	6	ea	\$250	\$1,500
	iv) Basswood	6	ea	\$250	\$1,500

21	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Round Leaved Dogwood	18	ea	\$45	\$810
	ii) Chokecherry	16	ea	\$45	\$720
	iii) Alternate Leaved Dogwood	18	ea	\$45	\$810
	iv) Downy juneberry	18	ea	\$45	\$810
	v) Northern Fly Honeysuckle	18	ea	\$45	\$810
	vi) Wild Red Raspberry	16	ea	\$45	\$720
	vii) Red-berried Elder	16	ea	\$45	\$720
Subtotal Section B (Excl of HST)					\$251,350
Section "C" – Provisional					
22	Replace/ Repair Asphalt Road	1	LS	\$15,000	\$15,000
23	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
24	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$25,000
Section "D" – Contingency					
25	Contingency (20%)	1	LS	\$76,705	\$76,705
Subtotal Section D (Excl of HST)					\$76,705
Section "A" – Site Preparation & Removals					\$107,175
Section "B" – Sewer Works, Channel Works and Restoration					\$251,350
Section "C" – Provisional					\$25,000
Section "D" – Contingency					\$76,705
Sub Total (Exc of taxes)					\$460,230
HST @ 13%					\$59,830
Total Bid Price (Incl of taxes)					\$520,060
Outlet # 42 Engineering Estimate (Inc. Contingency, Exc. HST)					\$460,230

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

Dave Maunder – Project Manager
 Robert Amos – Water Resources Lead
 Golmar Golmohammadi – Water Resources Engineer
 Gabriel Dubé – Water Resources Specialist
 Yun Xia – Water Resources Specialist
 Palka Sharma – CAD Technician
 Julie Scott – Terrestrial Ecologist



April 1st, 2022

Jakub Ripley – GIS Specialist
Darcy LaFramboise – Certified Arborist
Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.

A handwritten signature in blue ink that reads 'Dave Maunder'.

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 45

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 45 as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall 45 are shown in **Figure 1-1**. The storm sewer has a diameter of 200 mm and extends off of the corner joining McGee Street East to Doran Street, outletting into the Indian River. Outfall 45 was identified to be in need of rehabilitation and was ranked as the 6th highest priority site, of the total 17 sites that were assessed.




Figure 1-1: Location of Study Area for Storm Sewer Outfall 45

2 EXISTING CONDITIONS

2.1 Overview

Outfall 45 consists of a 200 mm concrete sewer pipe that has failed at the downstream-most pipe joint, creating a 30 cm gap between the detached pipe segment and the upstream pipe (**Figure 2-1** and **Figure 2-2**). The concrete pipe upstream of the failed joint remains in good condition (**Figure 2-3**), though it is recessed into the channel bank, with scouring noted near the outlet (**Figure 2-4**). There is also evidence of bank erosion near the outfall (**Figure 2-1** and **Figure 2-2**), which has steeped the bank in this area and created a near-vertical slope.



Figure 2-1: Detached Concrete Pipe Segment



Figure 2-2: Close-up Photo of the Detached Concrete Pipe Segment



Figure 2-3: Close-up Photo of the Recessed Concrete Pipe Outlet



Figure 2-4: Scouring at Recessed Concrete Pipe Outlet

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface above the storm sewer pipe, extending into the Indian River to capture streambed tie-in elevations;
- Any visible storm sewer infrastructure near the outlet (invert and obvert, exposed pipe, etc.);
- Upstream maintenance hole lid and pipe invert; and
- Top and bottom of bank elevations approximately 5-10 m upstream and downstream of the storm sewer outfall.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on February 15th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-07 was advanced to a depth of 4.6 m below grade using portable drilling equipment.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

Fill material was encountered at the surface of the borehole, extending to 1.0 m below surface grade. The fill was composed of dark brown to brown sand with some silt and trace gravel. The fill material was underlain by native deposits of silty sand with trace gravel (2.7 m thick) and silty clay (extending to the termination depth of the borehole). Based on soil sample appearance, the groundwater level was estimated to be at approximately 2.3 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 45 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 14 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 5 in the detailed design drawings shows the locations of the surveyed trees within the Outfall 45 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
809	Manitoba Maple	<i>Acer negundo</i>	Good
810	Hybrid Crack Willow	<i>Salix x rubens</i>	Poor
811	Manitoba Maple	<i>Acer negundo</i>	Good
812	White Elm	<i>Ulmus americana</i>	Good
813	White Elm	<i>Ulmus americana</i>	Good
814	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
815	White Ash	<i>Fraxinus americana</i>	Good
816	Manitoba Maple	<i>Acer negundo</i>	Good
817	Manitoba Maple	<i>Acer negundo</i>	Good
818	White Ash	<i>Fraxinus americana</i>	Good
819	Manitoba Maple	<i>Acer negundo</i>	Fair
820	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
821	Manitoba Maple	<i>Acer negundo</i>	Fair
NT1	Manitoba Maple	<i>Acer negundo</i>	Fair-Good

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 45 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Channel Bank Stabilization – Toe erosion and slope failures should be restored by regrading to attain a natural long-term stable slope, followed by the application of channel bank and toe erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel banks are not compromised.

Outlet Protection – The design should consider appropriate protection to prevent erosion and scouring damage to the pipe and associated channel works.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 45 are provided under a separate cover. The proposed design consists removing a 3 m section of the existing 200 mm concrete pipe and replacing it with a 2 m concrete pipe segment of the same diameter. The new 2 m pipe segment is to be incorporated into a vegetated buttress having a total length of 14.5 m, which is intended to provide bank protection near the outfall and to prevent exposure of the remaining sewer pipe. This includes cutting back the existing near-vertical bank to accommodate a lower grade of 2H:1V for the proposed vegetated buttress.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Indian River provides habitat to both spring and fall spawning species. As a major watercourse, the Indian River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study

area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 6 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site’s location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Upland Mix (Application Rate: 25 kg/ha)		
<i>Asclepias syriaca</i>	Common Milkweed	5%
<i>Clematis virginiana</i>	Virgin’s Bower	2%
<i>Fragaria virginiana</i>	Wild Strawberry	3%
<i>Monarda fistulosa</i>	Wild Bergamot	5%
<i>Panicum acuminatum</i> (<i>P. implicatum</i> ; <i>P. lanuginosum</i>)	Hairy Panic Grass	30%
<i>Rudbeckia hirta</i>	Black-eye Susan	15%
<i>Solidago canadensis</i>	Canada Goldenrod	8%
<i>Sporobolus cryptandrus</i>	Sand Dropseed	30%
<i>Symphyotrichum cordifolium</i>	Heart-leaved Aster	1%
<i>Symphyotrichum novae-angliae</i>	New England Aster	1%
Riparian Mix (Application Rate: 25 kg/ha)		

<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphyotrichum novae-angliae</i>	New England Aster	1%
<i>Symphyotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Acer saccharum</i>	Sugar Maple	6	5 gal. potted
<i>Picea glauca</i>	White Spruce	5	5 gal. potted
<i>Thuja occidentalis</i>	Eastern White Cedar	5	5 gal. potted
<i>Tilia americana</i>	Basswood	5	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
Restoration Plantings			
<i>Amelanchier arborea</i>	Downy Juneberry	21	2 gal. potted
<i>Cornus alternifolia</i>	Alternate-leaved Dogwood	21	2 gal. potted
<i>Lonicera canadensis</i>	Northern Fly Honeysuckle	21	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	21	2 gal. potted
<i>Ribes hirtellum</i>	Smooth Gooseberry	21	2 gal. potted
Vegetated Buttress Plantings			
<i>Cornus sericea</i>	Red-osier Dogwood	12	2 gal. potted
<i>Cornus rugosa</i>	Round-leaved Dogwood	12	2 gal. potted
<i>Salix petiolaris</i>	Slender Willow	12	2 gal. potted
<i>Spirea alba</i>	Narrow-leaved Meadowsweet	12	2 gal. potted
<i>Viburnum lentago</i>	Nannyberry	12	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 14 live trees identified during the assessment (detailed previously in **Table 2-1**), 7 have been identified for removal. Trees identified for removal are listed in **Table 4-4** below and are shown on Sheet 5 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of filter fence specified on Sheet 4 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Trees Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition	
809	Manitoba Maple	<i>Acer negundo</i>	Good	Remove
810	Hybrid Crack Willow	<i>Salix x rubens</i>	Poor	Remove
813	White Elm	<i>Ulmus americana</i>	Good	Remove
814	Manitoba Maple	<i>Acer negundo</i>	Fair-Good	Remove
815	White Ash	<i>Fraxinus americana</i>	Good	Remove
816	Manitoba Maple	<i>Acer negundo</i>	Good	Remove
NT1	Manitoba Maple	<i>Acer negundo</i>	Fair-Good	Remove

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. In all cases, an OLS should be retained to confirm property parcels and associated limits. In some cases, it may be necessary to require temporary or permanent easements.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing

the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Indian River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access for construction is proposed from McGee Street. The access routes are shown on Sheet 5 of the drawing set. A staging and storage area has also been shown. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$151,506 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 45

PEMBROKE OUTLETS - OUTLET # 45					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS	\$6,000	\$6,000
2	Field Office	1	LS	\$3,000	\$3,000
3	Construction Layout, Utility & Locates	1	LS	\$8,000	\$8,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat, Steel Plates & Staging Areas	1	LS	\$12,000	\$12,000
6	Clearing, Grubbing, and Vegetation Removal	1	LS	\$10,000	\$10,000
7	Supply, Install & Remove Temporary Erosion & Sediment Control Fence	35	m	\$20	\$700
8	Supply, Install & Remove Temporary Construction Fence	90	m	\$15	\$1,350
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$10,000	\$10,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
11	Removal & Disposal of Excess Pipe	1	LS	\$3,000	\$3,000
Subtotal Section A (Excl of HST)					\$69,050
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials (~70 m ³)	1	LS	\$6,000	\$6,000
15	Supply & Placement of Vegetated Buttress				
	Roundstone as specified	90	tonne	\$200	\$18,000
	Topsoil to enhance vegetation	20	m ³	\$50	\$1,000
	Stock Plantings (2 gal potted @ 0.5 spacing)				
	i) Red-osier Dogwood	12	ea	\$45	\$540
	ii) Slender Willow	12	ea	\$45	\$540
	iii) Nannyberry	12	ea	\$45	\$540
	iv) Narrow-Leaved Meadowsweet	12	ea	\$45	\$540
	v) Round Leaved Dogwood	12	ea	\$45	\$540
16	Supply & Placement of Erosion Control Blanket - Coir Mat	180	m ²	\$8	\$1,440
17	Supply & Placement of Topsoil for Restoration (300mm for terraseed area & 150mm for Sod)	75	m ³	\$50	\$3,750
21	Supply & Application of Terraseed Mixture (Upland)	80	m ²	\$8	\$640
22	Supply & Application of Terraseed Mixture(Riparian)	100	m ²	\$8	\$800
19	Supply & Application of Sod	145	m ²	\$20	\$2,900
20	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	ii) Sugar Maple	6	ea	\$250	\$1,500
	ii) White Spruce	5	ea	\$250	\$1,250
	iii) Eastern White Cedar	5	ea	\$250	\$1,250
	iv) Basswood	5	ea	\$250	\$1,250

21	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Alternate Leaved Dogwood	21	ea	\$45	\$945
	ii) Chokecherry	21	ea	\$45	\$945
	iii) Smooth Gooseberry	21	ea	\$45	\$945
	iv) Downy juneberry	21	ea	\$45	\$945
	v) Northern Fly Honeysuckle	21	ea	\$45	\$945
Subtotal Section B (Excl of HST)					\$47,205
Section "C" – Provisional					
23	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
24	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$10,000
Section "D" – Contingency					
25	Contingency (20%)	1	LS	\$25,251	\$25,251
Subtotal Section D (Excl of HST)					\$25,251
Section "A" – Site Preparation & Removals					\$69,050
Section "B" – Sewer Works, Channel Works and Restoration					\$47,205
Section "C" – Provisional					\$10,000
Section "D" – Contingency					\$25,251
Sub Total (Exc of taxes)					\$151,506
HST @ 13%					\$19,696
Total Bid Price (Incl of taxes)					\$171,202
Outlet # 45 Engineering Estimate (Inc. Contingency, Exc. HST)					\$151,506

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

- Dave Maunder – Project Manager
- Robert Amos – Water Resources Lead
- Golmar Golmohammadi – Water Resources Engineer
- Gabriel Dubé – Water Resources Specialist
- Yun Xia – Water Resources Specialist
- Palka Sharma – CAD Technician
- Julie Scott – Terrestrial Ecologist



April 1st, 2022

Jakub Ripley – GIS Specialist
Darcy LaFramboise – Certified Arborist
Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.

A handwritten signature in blue ink that reads 'Dave Maunder'.

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 46

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 46 as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall 46 are shown in **Figure 1-1**. The storm sewer has a diameter of 250 mm and extends off of Murray Street, outletting into Indian River approximately 105 m downstream of Eganville Road. Outfall 46 was identified to be in need of rehabilitation and was ranked as the 8th highest priority site, of the total 17 sites that were assessed.




Figure 1-1: Location of Study Area for Storm Sewer Outfall 46

2 EXISTING CONDITIONS

2.1 Overview

Outfall 46 consists of a 250 mm pipe that was originally connected to a 250 mm cast iron pipe, though a 2 cm gap has since developed at the joint of the two pipe segments (**Figure 2-1**). The cast iron pipe extends well past the channel bank into the Indian River, with the outlet completely submerged and partially filled with a 2.5 cm deep deposit of fine sand (**Figures 2-2, 2-3 and 2-4**). It is unclear whether the cast iron pipe was intended to extend into the Indian River or whether it became exposed due to recession of the channel bank.



Figure 2-1: Gap Between the Cast Iron and Clay Pipe Segments



Figure 2-2: Cast Iron Pipe Extending into the Indian River (Looking Upstream)



Figure 2-3: Close-up View of the Cast Iron Pipe



Figure 2-4: Submerged End of the Cast Iron Pipe

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface along, extending into the Indian River to capture the submerged end of the cast iron pipe and streambed tie-in elevations;
- Any visible storm sewer infrastructure near the outlet (invert and obvert, exposed pipe, etc.);
- Upstream maintenance hole lid and pipe invert; and
- Top and bottom of bank elevations approximately 5-10 m upstream and downstream of the storm sewer outfall.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on February 14th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-06 was advanced to a depth of 4.6 m below grade using portable drilling equipment.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

A 50 mm layer of asphaltic concrete was encountered at the surface, followed by a 160 mm thick road base layer and an 800 mm subbase layer. The road base layer consisted of brown crushed sand with gravel and some silt, and the subbase layer was composed of brown sand with some gravel and some silt. The subbase material was underlain by native deposits of silty sand (2.2 m thick) and silty clay (extending to the termination depth of the borehole). Based on soil sample appearance, the groundwater level was estimated to be at approximately 3.2 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 46 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 10 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 5 in the detailed design drawings shows the locations of the surveyed trees within the Outfall 46 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
NT1	Manitoba Maple	<i>Acer negundo</i>	Fair
801	White Elm	<i>Ulmus americana</i>	Good
802	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
803	White Ash	<i>Fraxinus americana</i>	Fair-Good
804	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
805	White Elm	<i>Ulmus americana</i>	Fair-Good
Bn1	Butternut	<i>Juglans cinerea</i>	Good
806	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
807	White Ash	<i>Fraxinus americana</i>	Good
808	White Ash	<i>Fraxinus americana</i>	Good

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 46 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Channel Bank Stabilization – Toe erosion and slope failures should be restored by regrading to attain a natural long-term stable slope, followed by the application of channel bank and toe erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel banks are not compromised.

Outlet Protection – The design should consider appropriate protection to prevent erosion and scouring damage to the pipe and associated channel works.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 46 are provided under a separate cover. The proposed design consists of constructing an armourstone retaining wall, with the intention of stabilizing the channel bank and providing protection against erosion. This selected as the preferred alternative for stabilizing and protecting the river bank, rather than a sloped vegetated buttress, due to limited space between Murray Street and the river bank.

Specifics of the design include removing the exposed 250 mm cast iron pipe and incorporating the remaining 250 mm clay pipe within the armourstone retaining wall. Angular stone is specified at the base of the armourstone wall, so as to provide protection against scouring from stormwater exiting the pipe.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Indian River provides habitat to both spring and fall spawning species. As a major watercourse, the Indian River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 6 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site's location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphyotrichum novae-angliae</i>	New England Aster	1%
<i>Symphyotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Acer rubrum</i>	Red Maple	1	5 gal. potted
<i>Acer saccharum</i>	Sugar Maple	1	5 gal. potted
<i>Picea glauca</i>	White Spruce	1	5 gal. potted
<i>Tilia americana</i>	Basswood	1	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
<i>Amelanchier arborea</i>	Downy Juneberry	4	2 gal. potted
<i>Cornus rugosa</i>	Round-leaved Dogwood	4	2 gal. potted
<i>Lonicera canadensis</i>	Northern Fly Honeysuckle	4	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	4	2 gal. potted
<i>Spiraea alba</i>	Narrow-leaved Meadowsweet	4	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 10 live trees identified during the assessment (detailed previously in **Table 2-1**), 4 have been identified for removal. Trees identified for removal are listed in **Table 4-4** below and are shown on Sheet 5 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of hoarding fence specified on Sheet 4 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Trees Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition
801	White Elm	<i>Ulmus americana</i>	Good
802	Manitoba Maple	<i>Acer negundo</i>	Fair-Good
803	White Ash	<i>Fraxinus americana</i>	Fair-Good
804	Manitoba Maple	<i>Acer negundo</i>	Fair-Good

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. In all cases, an OLS should be retained to confirm property parcels and associated limits. In some cases, it may be necessary to require temporary or permanent easements.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on

requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Indian River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access for construction is proposed from Murray Street. The access routes are shown on Sheet 6 of the drawing set. A staging and storage area has also been shown. The existing guard rail and sign post are to be removed prior construction to facilitate site access, and are to be replaced upon completion of construction. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$169,104 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 46

PEMBROKE OUTLETS - OUTLET # 46					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS		\$0
2	Field Office	1	LS		\$0
3	Construction Layout, Utility & Locates	1	LS	\$8,000	\$8,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$12,000	\$10,000
6	Clearing, Grubbing, and Vegetation Removal Including Removal and Reinstalling Guard Rail	1	LS	\$10,000	\$10,000
7	Supply, Install & Remove Temporary Tree Hoarding Fence	18	m	\$20	\$360
8	Supply, Install & Remove Temporary Construction Fence	30	m	\$15	\$450
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$12,000	\$12,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
11	Removal & Disposal of Excess Sewer Pipe	1	LS	\$10,000	\$10,000
Subtotal Section A (Excl of HST)					\$65,810
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$8,000	\$8,000
17	Supply & Placement of Angular Channel Substrate	50	tonne	\$200	\$10,000
17	Supply & Placement of Armoustone Retaining Wall	140	tonne	\$235	\$32,900
19	Supply & Placement of Erosion Control Blanket - Coir Mat	35	m ²	\$8	\$280
20	Supply & Placement of Topsoil for Restoration (300mm)	10	m ³	\$50	\$500
21	Supply & Application of Terraseed Mixture	35	m ²	\$8	\$280
23	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	i) Sugar Maple	1	ea	\$250	\$250
	ii) White Spruce	1	ea	\$250	\$250
	iii) Red Maple	1	ea	\$250	\$250
	v) Basswood	1	ea	\$250	\$250
23	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Round Leaved Dogwood	4	ea	\$45	\$180
	ii) Chokecherry	4	ea	\$45	\$180
	iii) Narrow leaved Meadowsweet	4	ea	\$45	\$180
	iv) Downy juneberry	4	ea	\$45	\$180
	v) Northern Fly Honeysuckle	4	ea	\$45	\$180
Subtotal Section B (Excl of HST)					\$53,860

Section "C" – Provisional					
24	Asphalt Road Repair (Removal, Granular Placement, New Asphalt, Buffer Restoration)	45	m ²	\$250	\$11,250
25	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
26	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$21,250
Section "D" – Contingency					
27	Contingency (20%)	1	LS	\$28,184	\$28,184
Subtotal Section D (Excl of HST)					\$28,184
Section "A" – Site Preparation & Removals					\$65,810
Section "B" – Sewer Works, Channel Works and Restoration					\$53,860
Section "C" – Provisional					\$21,250
Section "D" – Contingency					\$28,184
Sub Total (Exc of taxes)					\$169,104
HST @ 13%					\$21,984
Total Bid Price (Incl of taxes)					\$191,088
Outlet # 46 Engineering Estimate (Inc. Contingency, Exc. HST)					\$169,104

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

- Dave Maunder – Project Manager
- Robert Amos – Water Resources Lead
- Golmar Golmohammadi – Water Resources Engineer
- Gabriel Dubé – Water Resources Specialist
- Yun Xia – Water Resources Specialist
- Palka Sharma – CAD Technician
- Julie Scott – Terrestrial Ecologist
- Jakub Ripley – GIS Specialist
- Darcy LaFramboise – Certified Arborist
- Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.



MEMORANDUM

April 1st, 2022

Dave Maunder

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

Technical Memo for Design and Reconstruction of Storm Sewer Outfall 56

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall 56 as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall 56 are shown in **Figure 1-1**. The sewer pipe has a diameter of 300 mm and conveys water under Noman Street, outletting into an outside bend of the Indian River, approximately 440 m upstream of the confluence with the Muskrat River. Outfall 56 was identified to be in need of rehabilitation and was ranked as the 9th highest priority site, of the total 17 sites that were assessed.




Figure 1-1: Location of Study Area for Storm Sewer Outfall 56

2 EXISTING CONDITIONS

2.1 Overview

Outfall 56 consists of a 300 mm CSP sewer pipe that passes under Norman Street and was intended to collect water from an upstream box culvert, which has collapsed (**Figure 2-1**). However, a local resident informed Aquafor that very little water flows through the collapsed box culvert during storm event under existing conditions. The collapsed culvert passes under private property belonging to 444 Norman Street and is connected to the inlet of the CSP via a small ditch (**Figure 2-2**).

Approximately 30% of the CSP rise is filled with sediment (**Figure 2-3**). The outlet is recessed into the slope and is slightly crushed (**Figure 2-4**), with concrete rubble located near the outlet that appears to belong to a failed headwall. The outlet is located approximately 8 m away from the edge of the river, such that water existing the CSP flows down the channel slope. This has caused erosion scarring downstream of the outlet, particularly due to the high slope, which is approximately 1H:1V.

As shown in the detailed design drawings, much of the study area – including Norman Street – is located on private property belonging to 442 Norman Street.



Figure 2-1: Upstream Collapsed Box Culvert



Figure 2-2: CSP Inlet



Figure 2-3: Sediment Deposits Inside the CSP



Figure 2-4: Crushed and Recessed CSP Outlet, Surrounded by Concrete Rubble

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface overtop the CSP, extending down the slope and into the Indian River to capture streambed tie-in elevations;
- Any visible storm culvert/pipe infrastructure near the outlet (e.g., invert and obvert);
- Top and bottom of bank elevations approximately 5-10 m upstream and downstream of the storm sewer outfall; and
- Ground shots at the edge of erosion scars and within the eroded areas.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on March 14th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-05 was advanced to a depth of 8.2 m below grade using a truck-mounted drill.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. In situ

vane shear testing was carried out in the borehole to measure the undrained shear strength of the silty clay deposits. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

A 50 mm layer of asphaltic concrete was encountered at the surface, followed by a 150 mm thick road base layer and a 300 mm subbase layer. The road base layer consisted of brown crushed sand with gravel and some silt, and the subbase layer was composed of brown gravelly sand with trace silt. Beneath the road base, a 1.0 m thick layer of fill was encountered, consisting of brown sand and silt with trace gravel. The fill material was underlain by native deposits of silty sand (0.9 m thick), silty clay (3.4 m thick), and glacial till composed of clayey sand and gravel (extending to the termination depth of the borehole). Based on soil sample appearance, the groundwater level was estimated to be at approximately 7.2 m below surface grade at the time of the investigation.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall 56 study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 3 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet 4 in the detailed design drawings shows the locations of the surveyed trees within the Outfall 56 study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
NT1	Manitoba Maple	<i>Acer negundo</i>	Fair
NT2	Hybrid Crack Willow	<i>Salix x rubens</i>	Fair-Poor
NT3	Manitoba Maple	<i>Acer negundo</i>	Poor

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall 56 were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Slope Stabilization – Slope erosion and failures should be restored by regrading to attain a natural long-term stable slope, followed by application of erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope is not compromised.

CSP Protection – The design should consider appropriate protection to prevent damage to the ends of the CSP and sediment buildup within the pipe.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall 56 are provided under a separate cover. The proposed design consists of placing galvanized end sections on each end of the existing CSP running under Norman Street and removing existing sediment deposits within the pipe. The galvanized sections are intended to protect the ends of the CSP, as well as to reduce the sediment load passing through the pipe. Rip rap is proposed both upstream and downstream of the CSP to protect against erosion. Due to the high slope (roughly 1H:1V) downstream of the CSP, a boulder weir is specified at the toe of the rip rap to prevent displacement of the substrate.

Rehabilitation of the collapsed upstream box culvert is beyond the scope of this project. However, Aquafor recommends undertaking future design and construction works to ensure proper conveyance of stormwater to the inlet of the CSP.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Indian River provides habitat to both spring and fall spawning species. As a major watercourse, the Indian River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year

to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 5 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site's location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphyotrichum novae-angliae</i>	New England Aster	1%
<i>Symphyotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Acer rubrum</i>	Red Maple	1	5 gal. potted
<i>Thuja occidentalis</i>	Eastern White Cedar	1	5 gal. potted
<i>Tilia americana</i>	Basswood	1	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
<i>Amelanchier arborea</i>	Downy Juneberry	3	2 gal. potted
<i>Cornus alternifolia</i>	Alternate-leaved Dogwood	3	2 gal. potted
<i>Lonicera canadensis</i>	Northern Fly Honeysuckle	3	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	2	2 gal. potted
<i>Rubus ideaus</i>	Wild Red Raspberry	2	2 gal. potted
<i>Sambucus racemosa</i>	Red-berried Elder	2	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 3 live trees identified during the assessment (detailed previously in **Table 2-1**), 1 has been identified for removal. The tree identified for removal is shown in **Table 4-4** below and on Sheet 4 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of page wire hoarding specified on Sheet 3 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Tree Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition
NT3	Manitoba Maple	<i>Acer negundo</i>	Poor

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. As shown on Sheet 4 of the detailed design drawings, access routes and construction activities are proposed within private property at 442 Norman Street, for which an easement would be required. In all cases, an OLS should be retained to confirm property parcels and associated limits.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Indian River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access for construction is proposed from Norman Street, which will require temporary single-lane closure. The access routes are shown on Sheet 4 of the drawing set. Any changes to the access routes must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$99,204 which includes a 20% contingency but is exclusive of



April 1st, 2022

HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall 56

PEMBROKE OUTLETS - OUTLET # 56					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS	\$8,000	\$8,000
2	Field Office	1	LS	\$3,000	\$3,000
3	Construction Layout, Utility & Locates	1	LS	\$8,000	\$8,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$8,000	\$10,000
6	Clearing, Grubbing, and Vegetation Removal	1	LS	\$5,000	\$5,000
8	Supply, Install & Remove Temporary Construction Fence	25	m	\$15	\$375
9	Supply, Install & Remove Silt Socks	35	m	\$20	\$700
10	Removal & Disposal of Sediment	1	LS	\$3,000	\$3,000
Subtotal Section A (Excl of HST)					\$48,075
Section "B" – Sewer Works, Channel Works and Restoration					
11	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$2,000	\$2,000
12	Supply & Placement of Angular Channel Substrate	35	tonne	\$200	\$7,000
13	Supply & Placement of Galvanised End Section fro 12" CSP	2	ea	\$600	\$1,200
14	Supply & Placement of Boulders	3	ea	\$500	\$1,500
15	Supply & Placement of Erosion Control Blanket - Coir Mat	45	m ²	\$8	\$360
16	Supply & Placement of Topsoil for Restoration (300mm for terraseed area & 150mm for Sod)	15	m ³	\$50	\$750
17	Supply & Application of Terraseed Mixture	45	m ²	\$8	\$360
18	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	ii) Red Maple	1	ea	\$250	\$250
	ii) Eastern White Cedar	1	ea	\$250	\$250
	iii) Basswood	1	ea	\$250	\$250
19	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Alternate Leaved Dogwood	3	ea	\$45	\$135
	ii) Chokecherry	2	ea	\$45	\$90
	iii) Downy juneberry	3	ea	\$45	\$135
	iv) Northern Fly Honeysuckle	3	ea	\$45	\$135
	v) Wild Red Raspberry	2	ea	\$45	\$90
	vi) Red-berried Elder	2	ea	\$45	\$90
Subtotal Section B (Excl of HST)					\$14,595
Section "C" – Provisional					
20	Replace/ Repair Asphalt Road	1	LS	\$10,000	\$10,000
21	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
22	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$20,000
Section "D" – Contingency					
23	Contingency (20%)	1	LS	\$16,534	\$16,534
Subtotal Section D (Excl of HST)					\$16,534

Section "A" – Site Preparation & Removals				\$48,075
Section "B" – Sewer Works, Channel Works and Restoration				\$14,595
Section "C" – Provisional				\$20,000
Section "D" – Contingency				\$16,534
Sub Total (Exc of taxes)				\$99,204
HST @ 13%				\$12,897
Total Bid Price (Incl of taxes)				\$112,101
Outlet # 56 Engineering Estimate (Inc. Contingency, Exc. HST)				\$99,204

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

- Dave Maunder – Project Manager
- Robert Amos – Water Resources Lead
- Golmar Golmohammadi – Water Resources Engineer
- Gabriel Dubé – Water Resources Specialist
- Yun Xia – Water Resources Specialist
- Palka Sharma – CAD Technician
- Julie Scott – Terrestrial Ecologist
- Jakub Ripley – GIS Specialist
- Darcy LaFramboise – Certified Arborist
- Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.



Dave Maunder, M.Sc., P.Eng
 Project Manager
 Aquafor Beech Limited

Technical Memo for Design and Reconstruction of Storm Sewer Outfall # Unknown

1 INTRODUCTION

As part of the City-Wide Flood Risk Assessment and Storm Outlet Review, the City of Pembroke has requested an assessment of the condition on 17 of the City’s storm sewer outfalls, complete with an inventory of the findings. After conducting the outfall assessment, Aquafor Beech reported a total of 9 outfalls in poor condition and in need of repair. The following Technical Memo provides an overview of the existing conditions of Outfall # Unknown as well as the Detailed Design of the proposed outfall reconstruction.

The study area and location of Outfall # Unknown are shown in **Figure 1-1**. The outfall pipe has a diameter of 300 mm and extends off of Paul Martin Drive, outletting atop a steep road embankment that connects to an outfall channel, which ultimately discharges into the Muskrat River immediately downstream of the Paul Martin Drive bridge crossing. Outfall # Unknown was identified to be in need of rehabilitation and was ranked as the 4th highest priority site, of the total 17 sites that were assessed.




Figure 1-1: Location of Study Area for Storm Sewer Outfall # Unknown

2 EXISTING CONDITIONS

2.1 Overview

Outfall # Unknown consists 300 mm CSP sewer pipe that outlets atop the embankment of Paul Martin Drive (**Figure 2-1**). Holes have developed at the bottom of the CSP due to rust corrosion. Water exiting the pipe flows down the steep embankment slope (exceeding 1.35H:1V), over which a geotextile erosion blanket has been placed to mitigate erosion (**Figure 2-2**).

An outfall channel (**Figure 2-3**) collects water from both from Outfall # Unknown and from a culvert passing under International Drive. The total length of the channel is roughly 110 m, though the length of channel extending from Outfall # Unknown to the Muskrat River is only ~23 m. Despite erosion control consisting of roundstone placed overtop geotextile, severe erosion was noted along the downstream extents of the outfall channel, affecting a continuous channel length of 34 m. This included bank erosion as well as scouring of roundstone, which exposed the underlying geotextile erosion protection. Much the displaced roundstone settled as an outwash fan at the confluence with the Muskrat River (**Figure 2-4**).



Figure 2-1: Outlet and Eroded Bank



Figure 2-2: Eroded Bank at Outlet



Figure 2-3: Bank Erosion and Exposed Geotextile



Figure 2-4: Washed Out Swale

2.2 Topographic Survey

A detailed topographic survey was completed from November 8th to November 19th in 2021 to record existing site conditions. Sufficient detail was captured to support the detailed design of the outfall reconstruction. Key parameters captured during the survey include:

- Longitudinal profile of the ground surface above the storm sewer pipe;
- Survey points to characterize the outfall channel (cross-sections, thalweg, top-of-bank, etc.), extending into the Muskrat River to capture streambed tie-in elevations;
- Any visible storm sewer infrastructure near the outlet (invert and obvert, exposed pipe, etc.);
- Top and bottom of bank elevations along the Muskrat River, extending approximately 5-10 m upstream and downstream of the confluence with the outfall channel; and
- Additional ground shots within the outfall channel to capture erosion.

The survey was completed using a high-precision GPS instrument that was referenced to the NAD83 UTM Zone 18N horizontal coordinate system and the CGVD2013 vertical datum. A DEM derived from LiDAR data collected between 2019-2020 by Natural Resources Canada was used to complement the topographic survey data, allowing for elevations to be determined beyond the extents of the survey.

2.3 Geotechnical Investigation

A detailed geotechnical investigation was undertaken by GEMTEC within the study area on February 15th, 2022. The assessment was intended to define and characterize the subsurface soil conditions, inform the design of the proposed outfall reconstruction, and make recommendations regarding slope stabilization measures. One (1) borehole designated as 22-03 was advanced to a depth of 6.1 m below grade using portable drilling equipment.

Soil samples were obtained at regular intervals in the overburden soils with a 51 mm diameter Standard Penetration Test split-spoon sample. This was done in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing. Dynamic cone penetration testing (DCPT) was also carried out in this borehole. The results of the geotechnical investigation, along with a borehole location plan, are included in **Appendix I**.

Fill material was encountered at the surface of the borehole, extending to 1.7 m below surface grade. The fill consisted of brown sand and gravel with some silt. The fill material was underlain by native deposits of sandy clay, extending to the sampling termination point of 4.3 m. The borehole was further advanced by means of a DCPT to the termination depth of 6.1 m. Blow counts recorded during the DCPT ranged from 30 to 52 blows per 300 mm. No groundwater was observed within the open borehole.

2.4 Tree Inventory

A comprehensive tree inventory was undertaken in the Outfall # Unknown study area in February, 2022 to identify trees that may potentially be removed or damaged to accommodate construction activities. A total of 10 trees were inventoried in the study area, including at any potentially suitable access and staging areas. Sheet

5 in the detailed design drawings shows the locations of the surveyed trees within the Outfall # Unknown study area. **Table 2-1** provides a summary of the tree inventory results by species.

Table 2-1: Tree Inventory Summary by Species

Tag #	Species Common Name	Species Botanical Name	Condition
822	Bur Oak	<i>Quercus macrocarpa</i>	Good
823	Manitoba Maple	<i>Acer negundo</i>	Fair
824	Eastern White Cedar	<i>Thuja occidentalis</i>	Good
825	Eastern White Cedar	<i>Thuja occidentalis</i>	Good
826	Eastern White Cedar	<i>Thuja occidentalis</i>	Good
827	Eastern White Cedar	<i>Thuja occidentalis</i>	Good
828	Eastern White Cedar	<i>Thuja occidentalis</i>	Good
829	Eastern White Cedar	<i>Thuja occidentalis</i>	Good
830	Eastern White Cedar	<i>Thuja occidentalis</i>	Good
NT1	Eastern White Cedar	<i>Thuja occidentalis</i>	Good

3 DESIGN FACTORS

At the outset of the design process, all opportunities, constraints, and considerations for the reconstruction of Outfall # Unknown were identified. This ensured that they were adequately considered during development of the detailed design. Constraints and considerations identified within the study area were as follows:

Disturbance to Terrestrial Vegetation – Some of the trees and other vegetation located within the study area may be harmed or removed during construction. However, space allowing, any mature trees that are required for removal to facilitate construction will be compensated with trees plantings at a 3:1 ratio, along with 5 shrubs planted for every 1 tree planted. If there is insufficient space near the study area to meet this replanting target, trees will be planted at a minimum 1:1 ratio, with 5 shrubs planted for every 1 tree planted. Tree species selection will be based on their nativity within the City of Pembroke, and seed mix composition will reflect typical vegetation found within Plant Hardiness Zone 4b (Natural Resources Canada, 2021).

Utilities – In addition to the storm sewer infrastructure identified during the background review of base mapping provided by the City, Aquafor has also completed an Ontario One Call utility locate request for the entire site identify all other utilities and any potential design conflicts.

Channel Bank Stabilization – Toe erosion and slope failures should be restored by regrading to attain a natural long-term stable slope, followed by the application of channel bank and toe erosion protection.

Upstream and Downstream Tie-In Points – Care must be taken to ensure that there is a smooth transition into, and out of, the proposed outfall design, such that the stability of the slope and channel banks are not compromised.

4 DETAILED DESIGN

4.1 Principal Design Components

Detailed design drawings for Outfall # Unknown are provided under a separate cover. The proposed design consists of rehabilitating the downstream extents of the outfall channel by placing angular stone fill, which is intended to resist scouring. The reconstructed channel is to be 3 m wide and is to have a uniform gradient of 16%, before entering the Muskrat River at a 3H:1V slope. Banks are to be graded to 3H:1V and vegetated with native riparian seed mix, shrubs, and trees, in order to provide additional slope stability and resist erosion during high flow periods. The slope connecting the Outfall # Unknown to the outfall channel, which currently exceeds 1.35H:1V, is to be filled with angular stone and regraded to 3H:1V.

4.2 Wildlife Mitigation Measures

4.2.1 Breeding Birds

Tree removals should occur outside of the bird nesting window (generally April 1st to August 31st) to ensure that active nests of protected species are not harmed or destroyed and that the project is compliant with the *Migratory Birds Convention Act*. Individual trees or areas of low-complexity habitat could potentially be removed during the nesting window following an inspection to confirm the absence of active nesting in the area. However, this method is not recommended for complex habitats (e.g., mature woodland) due to the low detectability of nests in such areas, and is further not permitted if a restriction is placed on tree removal due to SAR bat habitat.

4.2.2 Bat Maternity Roosts

The active window for Ontario's SAR bats extends from April 1st to September 30th. The study area is inclusive of potential SAR bat habitat, and as such, tree removal is prohibited during this period.

4.2.3 In-Water Works Timing Windows and Fisheries Act

Discussions with MNRF (personal communication, March 15, 2022) confirmed that the Indian River provides habitat to both spring and fall spawning species. As a major watercourse, the Indian River contains fish at any time during any given year. Thus, no in-water works may occur between October 1 to July 15 of any given year to avoid works within the spring and fall spawning windows for the MNR Southern Region (March 15 - July 15 and October 1 - May 21, respectively).

4.2.4 DFO Self-assessment

The federal *Fisheries Act* requires that projects avoid causing the death of fish and the harmful alteration, disruption or destruction of fish habitat unless authorized by the Minister of Fisheries and Oceans Canada (DFO). This applies to work being conducted in or near waterbodies that support fish at any time during any given year or are connected to waterbodies that support fish at any time during any given year. As noted above, the study area does contain fish at any time during any given year. Therefore, the *Fisheries Act* applies to works conducted in or near water at the site.

April 1st, 2022

As the proposed works include minor regrading and rock placement within the high-water mark of the channel, Aquafor will undertake a request for regulatory review under the federal *Fisheries Act*.

4.3 Vegetation Removals and Restoration

A detailed restoration plan is shown on Sheet 6 of the design drawings. As soon as possible following construction, all disturbed areas should be revegetated through application of an annual cover crop and native herbaceous seed mix in areas of disturbance. Native seed mix should include wildflowers (preferably including milkweed species) to promote wildlife habitat. Terraseeding is the preferred application to hydroseeding. The recommended annual cover crop consists of Canada Wild Rye (*Elymus canadensis*) (40%) and Annual Oats (*Avena sativa*) (60%) applied at a rate of 33 kg/ha. after the risk of frost (i.e., after March 31 and before October 31); if applied during the time of frost risk, the cover crop should be 100% Annual Oats at a rate of 33kg/ha.

In addition, interplanting with native trees and shrubs is recommended within the coastal floodplain where appropriate. Restoration within disturbed areas should be in keeping with existing communities, and interplanting should utilize vegetation appropriate to the target community. Such interplanting will aid in stabilizing the banks and will also enhance habitat for wildlife and aquatic species.

All species selected should be native, suitable to the site conditions, and reflect the diversity of species commonly found in local natural areas. Based on native species within Pembroke and the site's location within Plant Hardiness Zone 4b, suggested species and sizes are listed in **Table 4-1**, **Table 4-2**, and **Table 4-3**.

Table 4-1: Native Seed Mixes

Scientific Name	Common Name	% by Weight
Nurse Crop Mix (Application Rate: 33 kg/ha)		
<i>Elymus canadensis</i>	Canada Wild Rye	40%
<i>Avena sativa</i>	Annual Oats	60%
Riparian Mix (Application Rate: 25 kg/ha)		
<i>Anemonastrum canadensis</i>	Canada Anemone	1%
<i>Apocynum cannabinum</i>	Indian-hemp Dogbane	5%
<i>Asclepias incarnata ssp. incarnata</i>	Swamp Milkweed	5%
<i>Bidens cernua</i>	Nodding Beggarticks	2%
<i>Bidens frondose</i>	Devil's Beggarticks	2%
<i>Carex granularis</i>	Meadow/Open Field Sedge	20%
<i>Clematis virginiana</i>	Virgin's Bower	4%
<i>Elymus virginicus var. virginicus</i>	Virginia Wild Rye	10%
<i>Euthamia graminifolia</i>	Grass-leaved Goldenrod	5%
<i>Juncus dudleyi</i>	Dudley's Rush	10%
<i>Poa palustris</i>	Fowl Bluegrass	25%
<i>Solidago canadensis</i>	Canada Goldenrod	4%
<i>Symphyotrichum novae-angliae</i>	New England Aster	1%
<i>Symphyotrichum puniceum</i>	Purple Stemmed Aster	1%
<i>Verbena hastata</i>	Blue Vervain	5%

Table 4-2: Native Tree Plantings

Scientific Name	Common Name	Amount	Size
<i>Picea glauca</i>	White Spruce	1	5 gal. potted
<i>Quercus macrocarpa</i>	Bur Oak	1	5 gal. potted
<i>Thuja occidentalis</i>	Eastern White Cedar	1	5 gal. potted

Table 4-3: Native Shrub Plantings

Scientific Name	Common Name	Amount	Size
<i>Amelanchier arborea</i>	Downy Juneberry	3	2 gal. potted
<i>Cornus racemosa</i>	Grey dogwood	3	2 gal. potted
<i>Cornus stolonifera</i>	Red osier dogwood	3	2 gal. potted
<i>Prunus virginiana</i>	Chokecherry	2	2 gal. potted
<i>Salix lucida</i>	Shining Willow	2	2 gal. potted
<i>Salix petiolaris</i>	Slender Willow	2	2 gal. potted

4.3.1 Removal Timing Window and Protection Measures

It will be necessary to remove some trees and other vegetation to facilitate the proposed works. Of the 10 live trees identified during the assessment (detailed previously in **Table 2-1**), 1 has been identified for removal. The tree identified for removal is shown in **Table 4-4** below and on Sheet 5 of the detailed design drawings. Tree removals on the site should take place outside of the typical bird nesting and bat maternity roost season (collectively April 1 to September 30).

Construction activities can have adverse effects on nearby trees that are to remain in place and should not be disturbed by the proposed works. Tree protections measures, consisting of page wire hoarding specified on Sheet 4 of the detailed design drawings, should be followed in order to mitigate against potential damages.

Table 4-4: Tree Identified for Removal

Tag #	Species Common Name	Species Botanical Name	Condition
824	Eastern White Cedar	<i>Thuja occidentalis</i>	Good

5 EASEMENT REQUIREMENTS

Aquafor was provided the property fabric by the City of Pembroke on March 7, 2022. In all cases, an OLS should be retained to confirm property parcels and associated limits. In some cases, it may be necessary to require temporary or permanent easements.

6 PERMITS AND APPROVALS

6.1 MNRF Fish Collection Permit

As de-watering will be required to accommodate construction, a fish rescue must be conducted. It will therefore be necessary to obtain a fish collection permit from the MNRF prior to construction. In addition, the dewatering and fish rescue must be conducted in accordance with MNRF timing windows to reduce harm to aquatic species, with no in-water works occurring between October 1 to July 15 (as discussed in **Section 4.2.3**). In the event that the work area becomes inundated following a significant rainfall event, fish rescues will be required prior to continuing instream works.

6.2 Provincial Species at Risk – MECP 17(2) (b/c) Species at Risk Permit

Prior to implementation, the study area should be subject to a Species at Risk (SAR) screening to identify any potential conflicts and ensure compliance with applicable legislation. Screening should be completed by consulting background information and agencies (MECP) to identify potential species associations, and assessing the potential for those species to occur in the study area based on their habitat requirements as compared to the habitat present on site. Mitigation measures to prevent or minimize impacts to species should be developed. If endangered or threatened species will potentially be impacted by the project, an Information Gathering Form (IGF) should be prepared and submitted to the MECP so that they may review the project and advise on requirements under the *Endangered Species Act*. Such requirements may include: implementation of additional mitigation measures as specified by MECP; registering the project via a Notice of Activity under a regulatory exemption; or preparation of an Overall Benefit Permit (OBP) package to address impacts to protected species

or habitat. Please note that the review period for an OBP, if such is required, is currently estimated at nine months to one year.

6.3 Department of Fisheries and Oceans Request for Review

As noted in **Section 4.2.4**, the detailed design will be submitted to DFO for review under the federal *Fisheries Act*.

7 CONSTRUCTION REQUIREMENTS

Construction Supervision – To ensure that the objectives of the outfall rehabilitation design are realized, it is important that someone with experience in channel design and restoration be part of the construction supervision (i.e., a qualified professional or representative of Aquafor Beech Ltd.). The supervision will enable construction issues to be addressed quickly and appropriately and ensure that important design details such as those listed below are implemented:

- Implementation of functional erosion and sediment control measures, including dewatering and pumping procedures;
- Removal of existing vegetation within, and protection of vegetation in close proximity to, the works area and access route;
- Confirmation of stone size gradation;
- Construction of an appropriate transition at the upstream and downstream tie-in points; and
- Restoration planting of native shrubs and trees, and Terraseeding of native seed mix.

Erosion and Sediment Control Measures – Erosion protection shall be used on regraded banks to provide erosion protection prior to the establishment of a vegetative cover.

Inspection of ESC measures should be completed regularly during the construction process to ensure that erosion and sediment control measures are functioning as intended and to address any immediate concerns. Similarly, monitoring of erosion control works should be completed following any flooding event to ensure that erosion control blankets and plantings are not compromised as a result of the event. The inspection and monitoring should be completed by an engineer, environmental inspector, or representative of Aquafor Beech Ltd.

Timing – Construction timing is restricted for fisheries protection. The Indian River provides habitat to both spring and fall spawning species. As such, no in-water works may occur between October 1 to July 15 of any given year to respect spring and fall spawning species for the MNR Southern Region. All tree removals on the site must take place outside of the period from April 1 to September 30, which is inclusive of the typical bird nesting season (April 1 to August 31) and the typical maternity roost season (April 1 - September 30).

Fish Removal – An initial fish rescue will be required once the in-water work area has been isolated; the fish rescue will be completed prior to dewatering the work area. Subsequent fish rescues will be required if the coffer dam isolating the work area is overtopped by high flows in the river. The contractor will be responsible for coordinating with the qualified aquatic biologist for fish rescues.

Construction Methodology – The channel bank and bed works must be undertaken in the dry. Dry working conditions will be created by blocking the perimeter of the work zone with coffer dams and routing the water

around the work zone (dam and flume techniques). Additional precautions and procedures, specified in the detailed drawings, include:

- All practical measures will be implemented to maintain the work zone in good condition;
- Utilities will be located and protected;
- Equipment refuelling will take place in the designated staging area, a minimum of 30 m from the watercourse; and
- All erosion and sediment control measures will be maintained in good working order.

Site Access – Access routes are shown on Sheet 6 of the drawing set, along with a staging and storage area. Access for construction is proposed from Paul Martin Drive, which will require temporary lane closure. The existing 5 m long guard rail is to be removed prior construction to facilitate site access, and is to be replaced upon completion of construction. Any changes to the access routes or staging area locations must be approved by the City and the field engineer.

Vegetation – To minimize the rate of erosion, it is desirable to establish vegetation quickly where it has been specified. Potted shrubs, potted trees, and a native seed mix (to be applied by Terraseeding) will be used to restore the site. Onsite consideration should be given to the season and prevailing light conditions for planting. If construction occurs after October, plantings should be completed as soon as possible in the following spring season.

8 CONSTRUCTION COST ESTIMATION

Preliminary construction costs have been estimated based on a schedule of quantities from the detailed design presented here. The construction cost estimate is \$341,940 which includes a 20% contingency but is exclusive of HST. The detailed schedule of quantities showing the breakdown of costs is provided on the following page in **Table 8-1**.

Table 8-1: Construction Cost Estimate for Reconstruction of Outfall # Unknown

PEMBROKE OUTLETS - OUTLET # UNKNOWN					
City of Pembroke					
Item	Description	Qty	Unit	Unit Price	Extended Price (Excl. HST)
Section "A" – Site Preparation & Removals					
1	Bonds and Insurance	1	LS	\$10,000	\$10,000
2	Field Office	1	LS	\$3,000	\$3,000
3	Construction Layout, Utility & Locates	1	LS	\$8,000	\$8,000
4	Mobilization & Demobilization	1	LS	\$10,000	\$10,000
5	Access Route, Mud Mat & Staging Areas	1	LS	\$12,000	\$10,000
6	Clearing, Grubbing, and Vegetation Removal Including Removal and Reinstalling Guard Rail	1	LS	\$10,000	\$10,000
7	Supply, Install & Remove Temporary Tree Hoarding/Construction Fence	15	m	\$15	\$225
8	Supply, Install & Remove Temporary Erosion and Sediment Control Fence	80	m	\$20	\$1,600
9	Stream Control, Bypass Pumping & Dewatering	1	LS	\$12,000	\$12,000
10	MNRF Fish Collection Permit and Fish Rescues	1	LS	\$5,000	\$5,000
Subtotal Section A (Excl of HST)					\$69,825
Section "B" – Sewer Works, Channel Works and Restoration					
12	Excavate, Earthwork, Grading & Disposal of Materials	1	LS	\$8,000	\$8,000
17	Supply & Placement of Angular Channel Substrate	780	tonne	\$200	\$156,000
19	Supply & Placement of Erosion Control Blanket - Coir Mat	315	m ²	\$8	\$2,520
20	Supply & Placement of Topsoil for Restoration (300mm)	95	m ³	\$50	\$4,750
21	Supply & Application of Terraseed Mixture	315	m ²	\$8	\$2,520
23	Supply & Planting of Trees (5 gal potted @ min 2.5m spacing)				
	i) Bur Oak	1	ea	\$250	\$250
	ii) White Spruce	1	ea	\$250	\$250
	iii) Eastern White Cedar	1	ea	\$250	\$250
23	Supply & Planting of Shrubs (2 gal potted @ 1m spacing)				
	i) Red Osier Dogwood	3	ea	\$45	\$135
	ii) Chokecherry	2	ea	\$45	\$90
	iii) Grey Dogwood	3	ea	\$45	\$135
	iv) Downy juneberry	3	ea	\$45	\$135
	v) Shining Willow	2	ea	\$45	\$90
	vi) Slender Willow	2	ea	\$45	\$90
Subtotal Section B (Excl of HST)					\$175,125
Section "C" – Provisional					
24	Asphalt Road Repair (Removal, Granular Placement, New Asphalt, Buffer Restoration)	1	LS	\$30,000	\$30,000
25	Migratory Nesting Bird Survey	1	LS	\$5,000	\$5,000
26	Retain Certified Arborist	1	LS	\$5,000	\$5,000
Subtotal Section C (Excl of HST)					\$40,000

Section "D" – Contingency					
27	Contingency (20%)	1	LS	\$56,990	\$56,990
Subtotal Section D (Excl of HST)					\$56,990
Section "A" – Site Preparation & Removals					\$69,825
Section "B" – Sewer Works, Channel Works and Restoration					\$175,125
Section "C" – Provisional					\$40,000
Section "D" – Contingency					\$56,990
Sub Total (Exc of taxes)					\$341,940
HST @ 13%					\$44,452
Total Bid Price (Incl of taxes)					\$386,392
Outlet # UNKNOWN Engineering Estimate (Inc. Contingency, Exc. HST)					\$341,940

9 REFERENCES

Natural Resources Canada (2021). Plant hardiness of Canada. Retrieved from <http://planthardiness.gc.ca/>

Department of Fisheries and Oceans. (2021). Projects near water. Retrieved from Fisheries and Oceans Canada: <http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>

10 SIGNATURES

This project is being completed with input from the following consulting staff:

- Dave Maunder – Project Manager
- Robert Amos – Water Resources Lead
- Golmar Golmohammadi – Water Resources Engineer
- Gabriel Dubé – Water Resources Specialist
- Yun Xia – Water Resources Specialist
- Palka Sharma – CAD Technician
- Julie Scott – Terrestrial Ecologist
- Jakub Ripley – GIS Specialist
- Darcy LaFramboise – Certified Arborist
- Graham Eby – Aquatic Biologist

Upon your review, should you have any questions or comments, please do not hesitate to contact the undersigned.



MEMORANDUM

April 1st, 2022

Dave Maunder

Dave Maunder, M.Sc., P.Eng
Project Manager
Aquafor Beech Limited

APPENDIX I

Draft Geotechnical Investigation Report



GEMTEC

www.gemtec.ca

DRAFT

**Geotechnical Investigation for the
City of Pembroke Flood Risk Assessment
and Storm Outlets
Pembroke, Ontario**



GEMTEC

www.gemtec.ca

Submitted to:

Aquafor Beech Ltd.
55 Regal Road, Unit 3
Guelph, Ontario
N1K 1B6

**Geotechnical Investigation for the
City of Pembroke Flood Risk
Assessment and Storm Outlets**
Pembroke, Ontario

March 25, 2022
Project: 101078.001

GEMTEC Consulting Engineers and Scientists Limited
142 Industrial Avenue
Petawawa ON, Canada
K8H 2W8

March 25, 2022

File: 101078.001

Aquafor Beech Ltd.
55 Regal Road, Unit 3
Guelph, Ontario
N1K 1B6

Attention: Mr. Dave Maunder

**Re: Geotechnical Investigation for the City Wide Flood Risk Assessment
and Storm Outlets, Pembroke, Ontario**

Please find enclosed the GEMTEC Consulting Engineers and Scientists Limited (GEMTEC) Geotechnical Investigation report for the City Wide Flood Risk Assessment and Storm Outlets as described in the City of Pembroke Request For Proposal No. P-21-09 located in Pembroke, Ontario.

A geotechnical investigation was conducted to assess the existing subsurface soil conditions at the requested stormwater outlets in order to present geotechnical recommendations pertaining to the reconstruction and stabilization design of the new outlets.

We trust that this report provides sufficient information for your purposes. Should you have any questions or require additional information concerning this report, please do not hesitate to contact the undersigned.

Sincerely,

GEMTEC Consulting Engineers and Scientists Limited

Brent Wiebe, P.Eng
Vice President of Operations - Ontario

TABLE OF CONTENTS

_Toc99265360

1.0	INTRODUCTION.....	1
1.1	General.....	1
1.2	Background Information.....	1
1.3	Review of Geology Maps.....	2
2.0	METHODOLOGY.....	2
2.1	Geotechnical Field Investigation.....	2
3.0	SUBSURFACE CONDITIONS.....	3
3.1	General.....	3
3.2	Soil Stratigraphy.....	4
3.2.1	Borehole 22-01 (Christie Street – Outlet 41).....	4
3.2.2	Borehole 22-02 (Boundary Road Pathway – Outlet 35).....	4
3.2.3	Borehole 22-03 (Paul Martin Drive – No Outlet Number).....	5
3.2.4	Borehole 22-04 (Everett Street – Outlet 42).....	5
3.2.5	Borehole 22-05 (Norman Street – Outlet 56).....	6
3.2.6	Borehole 22-06 (Murray Street – Outlet 46).....	7
3.2.7	Borehole 22-07 (Doran Street – Outlet 45).....	8
3.2.8	Borehole 22-08 (Moffatt Street – Outlet 31).....	8
3.2.9	Borehole 22-09 (Margaret Street – Outlet 27).....	9
4.0	GEOTECHNICAL RECOMMENDATIONS.....	10
4.1	General.....	10
4.2	Excavations.....	10
4.3	Pipe Bedding, Cover and Trench Backfill.....	11
4.4	Construction Dewatering.....	11
4.5	Erosion Protection.....	12
5.0	SLOPE STABILIZATION ASSESSMENT.....	13
5.1	Overview.....	13
5.1.1	Slope Stabilization Alternatives.....	14
5.1.1.1	Outlet and Riverbank Support.....	14
5.1.2	Slope Erosion Protection.....	15
5.1.3	Slope Stability Assessment.....	16
5.2	Detailed Design.....	17
5.3	Disposal of Excess Soil.....	17
6.0	CLOSURE.....	18

LIST OF TABLES

Table 3.1: Borehole Numbers and Termination Depths.....	3
Table 4.1: Summary of Estimated Groundwater Levels (at Time of Investigation).....	12
Table 5.1: Summary of Slope Assessment at Outlets.....	13

LIST OF APPENDICES

Appendix A	Christie Street – Outlet 41
Appendix B	Boundary Road Pathway - Outlet 35
Appendix C	Paul Martin Drive - No Outlet #
Appendix D	Everett Street - Outlet 42
Appendix E	Norman Street - Outlet 56
Appendix F	Murray Street - Outlet 46
Appendix G	Doran Street - Outlet 45
Appendix H	Moffatt Street - Outlet 31
Appendix I	Margaret Street - Outlet 27

1.0 INTRODUCTION

1.1 General

This report presents the results of a geotechnical investigation for the City of Pembroke's Flood Risk Assessment and Storm Outlet project. The purpose of the investigation was to identify the general subsurface conditions at nine outlet locations by means of a limited number of boreholes and, based on the factual information obtained, to:

- a) Provide engineering guidelines on the geotechnical design aspect of the proposed outlet reconstruction including construction considerations that could influence design decisions, and;
- b) Develop possible slope stabilization alternatives, where applicable.

The storm outlet locations are located along the Muskrat and Indian Rivers within the City of Pembroke. The nine outlet locations investigated are as follows:

Christie Street – Outlet 41	Boundary Road Pathway – Outlet 35
Paul Martin Drive – No Outlet #	Everett Street – Outlet 42
Norman Street – Outlet 56	Murray Street – Outlet 46
Doran Street – Outlet 45	Moffatt Street – Outlet 31
Margaret Street – Outlet 27	

A Site Plan and Cross-Section for each outlet location is provided in the Appendices of this report. It is noted that these plans were provided to GEMTEC by Aquafor Beech Limited. GEMTEC has not carried out surveying of the slope profiles at the outlet locations.

1.2 Background Information

It is noted that GEMTEC has previously carried out an extensive slope stability investigation for Moffatt Street in the City of Pembroke. This work was carried out directly for the City of Pembroke. It is noted that portions of the current investigation are within the boundaries of the scope of work previously carried out by GEMTEC, namely Outlet 31. The recommendations provided herein are in no way intended to supersede global recommendations provided for the Moffatt street slope stability report previously provided by GEMTEC to the City of Pembroke. Discussions regarding implementations of remediation at Outlet 31 in conjunction with any other work carried out by the City of Pembroke as part of wider slope stabilization measures could be provided as required and it is recommended GEMTEC be contacted to ensure that recommendations have been interpreted as intended and align with recommendations provided for the broader Moffatt Street investigation.

1.3 Review of Geology Maps

Based on our review of available geology maps, the subject sites are underlain by alluvial deposits composed of clay, silt, sand, and gravel and fine-textured glaciomarine deposits of silt and clay. The bedrock is mapped as sandstone, shale, limestone, and dolostone of the Rockcliffe formation.

2.0 METHODOLOGY

2.1 Geotechnical Field Investigation

The geotechnical field investigation consisted of advancing nine (9) boreholes designated 22-01 to 22-09 at the locations shown on the Borehole Location Plans, presented as Figure A1 thru I1 in the Appendices. A complete description of the stratigraphy encountered at each borehole location is presented on the Record of Borehole sheets.

The geotechnical investigation was completed between February 11 and 16, 2022 using portable drilling equipment and March 14 to 16, 2022 using a truck-mounted drill operating under the supervision of experienced GEMTEC personnel. Soil samples were obtained at regular intervals in the overburden soils with a 51-millimetre diameter Standard Penetration Test split-spoon sampler. Sampling procedures were performed in accordance with ASTM Standard D-1586, which provides the penetration resistance (N-value) of the soils. In situ vane shear testing was carried out in the boreholes to measure the undrained shear strength of the silty clay deposits. Dynamic cone penetration testing (DCPT) was carried out in boreholes 22-03 and 22-04.

Soil samples were examined in the field for type, texture and colour to classify each soil layer identified. The samples were sealed in air tight plastic bags and transferred to GEMTEC's laboratory for further examination and selection of appropriate samples for laboratory testing.

Groundwater conditions within the boreholes were observed during the course of the field investigation and prior to backfilling.

The borehole locations were determined using a Trimble R10 GPS survey instrument. The elevations are referenced to Geodetic datum.

Table 3.1 summarizes the borehole numbers and final termination depths.

Table 3.1: Borehole Numbers and Termination Depths

Street/ Outlet No.	Borehole No.	Depth Below Ground Surface (m)	Comment
Christie / 41	22-01	4.3	Borehole terminated within silty clay
Boundary / 35	22-02	4.9	Borehole terminated within lean clay
Paul Martin / NA	22-03	6.1	Borehole terminated at termination depth with DCPT
Everett / 42	22-04	10.2	Borehole terminated due to DCPT refusal
Norman / 56	22-05	8.2	Borehole terminated within glacial till
Murray / 46	22-06	4.6	Borehole terminated within silty clay
Doran / 45	22-07	4.6	Borehole terminated within silty clay
Moffatt / 31	22-08	9.8	Borehole terminated within silty clay
Margaret / 27	22-09	18.9	Borehole terminated within glacial till

3.0 SUBSURFACE CONDITIONS

3.1 General

As previously indicated, the soil and groundwater conditions identified in the test holes are given on the Record of Borehole sheets. The logs indicate the subsurface conditions at the specific test locations only. Boundaries between zones on the logs are often not distinct, but rather are transitional and have been interpreted. The precision with which subsurface conditions are indicated depends on the method of exploration, the frequency and recovery of samples, the method of sampling, and the uniformity of the subsurface conditions. Subsurface conditions at other than the test locations may vary from the conditions encountered in the test holes. In addition to soil variability, fill of variable physical and chemical composition can be present over portions of the sites or on adjacent properties.

The groundwater conditions described in this report refer only to those observed at the place and time of observation noted in the report. These conditions may vary seasonally or as a consequence of construction activities in the area.

The soil descriptions in this report are based on commonly accepted methods of classification and identification employed in geotechnical practice. Classification and identification of soil

involves judgement and GEMTEC does not guarantee descriptions as exact, but infers accuracy to the extent that is common in current geotechnical practice.

The following presents an overview of the subsurface conditions encountered in the test holes advanced during the field investigation.

3.2 Soil Stratigraphy

3.2.1 Borehole 22-01 (Christie Street – Outlet 41)

The following provides a summary of the soil stratigraphy encountered at borehole 22-01:

- A 75 millimetre thick topsoil layer was encountered at ground surface. The topsoil is underlain by about one metre of fill material composed of brown sand and silt with trace gravel. The fill was found to be frozen at the time of the investigation.
- Native deposits of brown becoming grey sand with silt were encountered below the fill material at a depth of about 1.1 metres. The sand with silt deposits have a thickness of about 2.1 metres and extend to a depth of about 3.2 metres below existing grade. Standard Penetration Test results (N values) recorded in the sand with silt ranged from 3 to 9 blows per 300 millimetres indicating a very loose to loose relative density. One grain size distribution test was carried out on a sample of the sand and silt (refer to the Soil Grading Chart in Appendix A).
- The sand with silt is underlain by grey silty clay which extends to the termination depth of borehole 22-01 at a depth of 4.3 metres below surface grade. Standard Penetration Test results (N values) recorded in the silty clay were 8 blows per 300 millimetres indicating a stiff to very stiff consistency. One particle size distribution analysis was carried out on a sample of the grey silty clay (refer to the Soil Grading Chart in Appendix A).
- Based on soil sample appearance, the groundwater level was estimated at about 2.1 metres below surface grade at the time of the investigation.

3.2.2 Borehole 22-02 (Boundary Road Pathway – Outlet 35)

The following provides a summary of the soil stratigraphy encountered at borehole 22-02:

- Fill material having a thickness of about 1.4 metres was encountered at ground surface. The fill material consists of about 200 millimetres of gravelly sand over brown silty clay fill with trace sand. The fill was frozen at the time of the investigation.
- Native deposits of dark grey to brown silty clay were encountered below the fill material at a depth of about 1.4 metres. The silty clay deposits were found to extend to the termination depth of borehole 22-02 at about 4.9 metres below surface grade. Standard Penetration Test results (N values) recorded in the silty clay ranged from 9 to 12 blows per 300 millimetres indicating a very stiff consistency. One particle size distribution analysis was

carried out on a sample of the brown silty clay (refer to the Soil Grading Chart in Appendix B)

- Based on soil appearance, the groundwater level was estimated to be at about 3.0 metres below surface grade at the time of the investigation.

3.2.3 Borehole 22-03 (Paul Martin Drive – No Outlet Number)

The following provides a summary of the soil stratigraphy encountered in borehole 22-03:

- Fill material was encountered at ground surface, extending to about 1.7 metres below surface grade. The fill material consists of brown sand and gravel with some silt. The fill was frozen at the time of our investigation. One grain size distribution test was carried out on a sample of fill (refer to the Soil Grading Chart in Appendix C).
- Native deposits of brown sandy clay were encountered below the fill material at a depth of about 1.7 metres. The sandy clay deposits extend to the sampling termination point of borehole 22-03 at a depth of about 4.3 metres below ground surface. Standard Penetration Test results (N values) recorded in the sandy clay ranged from 32 to 48 blows per 300 millimetres indicating a compact relative density. One particle size distribution analysis was carried out on a sample of sandy clay (refer to the Soil Grading Chart in Appendix C).
- Borehole 22-03 was further advanced by means of a dynamic cone penetration test (DCPT) to the termination depth of 6.1 metres. Blow counts recorded during the DCPT test ranged from 30 to 52 blows per 300 millimetres.
- Groundwater infiltration was not observed within the open borehole.

3.2.4 Borehole 22-04 (Everett Street – Outlet 42)

The following provides a summary of the soil stratigraphy encountered in borehole 22-04:

- A 1.2 metre thick fill layer was encountered at ground surface. The fill consists of dark brown sand and silt with some gravel. Large pieces of concrete debris were observed on the surface directly downstream of the outlet.
- Native deposits of dark grey clayey sand were encountered below the fill material at a depth of about 1.2 metres. The clayey sand was found to have a thickness of about 1.8 metres and extends to a depth of about 3.0 metres below existing grade. Standard Penetration Test results (N values) recorded in the clayey sand ranged from 7 to 9 blows per 300 millimetres indicating a loose relative density. One grain size distribution test was carried out on a sample of the clayey sand (refer to the Soil Grading Chart in Appendix D).

- The dark clayey sand is underlain by dark grey clayey silt, which has a thickness of about 1.8 metres and extends to a depth of about 4.9 metres below ground surface. Standard Penetration Test results (N values) recorded in the clayey silt ranged from 12 to 44 blows per 300 millimetres indicating a stiff to very stiff consistency. One particle size distribution test was carried out on a sample of the clayey silt (refer to the Soil Grading Chart in Appendix D).
- The dark grey clayey silt is underlain by a deposit of dark grey silty clay which has a thickness of about 1.5 metres and extends to a depth of about 6.4 metres below surface grade. Standard Penetration Test results (N values) recorded in the silt clay ranged from 7 to 12 blows per 300 millimetres. In-situ shear vane testing was performed in the silty clay deposit. The values of undrained shear strength were recorded as 168 kilopascals which indicates a very stiff consistency. One particle size distribution test was carried out on a sample of the silty clay (refer to the Soil Grading Charts in Appendix D).
- The dark grey silty clay is underlain by a deposit of glacial till primarily composed of grey clayey sand and silt with some gravel. The glacial till was found to extend to the sampling termination depth of the borehole at about 7.0 metres below surface grade. A Standard Penetration Test Result (N value) recorded in the glacial till was 30 blows per 300 millimetres which indicates a compact relative density. One grain size distribution test was carried out on a sample of the glacial till (refer to the Soil Grading Chart in Appendix D).
- Borehole 22-04 was further advanced by means of a dynamic cone penetration test (DCPT) and terminated at a depth of about 10.2 metres due to refusal within the inferred glacial till on cobbles or boulders. Blow counts recorded during the DCPT test ranged from 14 to 58 blows per 300 millimetres.
- Based on soil sample appearance, the groundwater level was estimated to be at about 4.9 metres below surface grade at the time of the investigation.

3.2.5 Borehole 22-05 (Norman Street – Outlet 56)

The following provides a summary of the soil stratigraphy encountered in borehole 22-05:

- From the surface, a 50 millimetre layer of asphaltic concrete was encountered. Underlying the surficial layer of asphaltic concrete, a road base and subbase material was observed. The road base consisted of a brown crushed sand with gravel and some silt and has a thickness of about 150 millimetres. The subbase consists of a brown gravelly sand with trace silt and has a thickness of about 300 millimetres. The road base and subbase was frozen at the time of the investigation.
- Underlying the pavement structure, a fill material consisting of brown sand and silt with trace gravel was encountered. The fill was found to have a thickness of about 1.0 metre and extends to a depth of about 1.5 metres below surface grade. Standard Penetration Test results (N values) recorded in the fill were recorded as 35 blows per 300 millimetres indicating a dense relative density.

- Native deposits of brown silty sand were encountered below the fill material at a depth of about 1.5 metres. The silty sand deposit has a thickness of about 0.9 metres and extends to a depth of about 2.4 metres below surface grade. A Standard Penetration Test (N value) recorded in the silty sand was 6 blows per 300 millimetres, indicating a loose relative density. One grain size distribution test was carried out on a sample of the silt (refer to the Soil Grading Charts in Appendix E).
- The silty sand is underlain by brown to grey silty clay. The silty clay has a thickness of about 3.4 metres and extends to a depth of about 5.8 metres below existing grade. Standard Penetration Test results (N values) recorded in the silty clay ranged from 1 to 9 blows per 300 millimetres. In-situ shear vane testing was performed in the silty clay deposit. The undrained shear strength values ranged from 91 to 104 kilopascals which indicates a stiff to very stiff consistency. One particle size distribution analysis was carried out on a sample of the silty clay (refer to the Soil Grading Chart in Appendix E).
- The silty clay is underlain by glacial till composed of grey clayey sand and gravel. The glacial till was found to extend to the termination depth of borehole 22-05 at about 8.2 metres below surface grade. Standard Penetration Test results (N values) recorded in the glacial till ranged from 11 to 21 blows per 300 millimetres indicating a compact relative density.
- Based on soil sample appearance, the groundwater level was estimated to be at about 7.2 metres below surface grade at the time of the investigation.

3.2.6 Borehole 22-06 (Murray Street – Outlet 46)

The following provides a summary of the soil stratigraphy encountered in borehole 22-06:

- From the surface, a 50 millimetre layer of asphaltic concrete was encountered. Underlying the surficial layer of asphaltic concrete, a road base and subbase material was observed. The road base consisted of a brown crushed sand with gravel and some silt and has a thickness of about 160 millimetres. The subbase consists of a brown sand with some gravel and some silt and has a thickness of about 800 millimetres. The road base and subbase was frozen at the time of the investigation.
- Native deposits of brown silty sand were encountered below the pavement structure at a depth of about 1.0 metre. The silty sand deposit has a thickness of about 2.2 metres and extends to about 3.2 metres below surface grade. Standard Penetration Test results (N values) recorded in the silty sand ranged from 2 to 4 blows per 300 millimetres indicating a very loose relative density. One grain size distribution test was carried out on a sample of the silty sand (refer to the Soil Grading Charts in Appendix F).
- The silty sand is underlain by grey silty clay. The silty clay extends to the termination depth of borehole 22-06 at about 4.6 metres below surface grade. Standard Penetration Test results (N values) recorded in the silty clay ranged from 1 to 5 blows per 300

millimetres indicating a firm consistency. One particle size distribution analysis was carried out on a sample of the silty clay (refer to the Soil Grading Chart in Appendix F).

- Based on soil sample appearance, the groundwater level was estimated to be about 3.2 metres below surface grade at the time of the investigation.

3.2.7 Borehole 22-07 (Doran Street – Outlet 45)

The following provides a summary of the soil stratigraphy encountered in borehole 22-07:

- From the surface, a fill material consisting of dark brown to brown sand with some silt and trace gravel was encountered. The fill has a thickness of about 1.0 metre. The fill was frozen at the time of the investigation.
- Native deposits of brown silty sand with trace gravel were encountered below the fill. The silty sand deposits have a thickness of about 2.7 metres and extend to a depth of about 3.7 metres below surface grade. Standard Penetration Test results (N values) recorded in the silty sand range from 3 to 12 blows per 300 millimetres indicating a very loose to compact relative density. Split spoon sampler refusal was encountered at a depth of about 3.3 metres below surface grade on organic wood material. One grain size distribution test was carried out on a sample of the silty sand (refer to the Soil Grading Chart in Appendix G).
- The silty sand is underlain by grey silty clay. The silty clay extends to the termination depth of borehole 22-07 at about 4.6 metres below surface grade. A Standard Penetration Test (N values) recorded in the silty clay was 7 blows per 300 millimetres indicating a stiff consistency. One particle size distribution analysis was carried out on a sample of the silty clay (refer to the Soil Grading Charts in Appendix G).
- Based on soil sample appearance, the groundwater level was estimated to be at about 2.3 metres below surface grade at the time of the investigation.

3.2.8 Borehole 22-08 (Moffatt Street – Outlet 31)

The following provides a summary of the soil stratigraphy encountered in borehole 22-08:

- From the surface, a 40 millimetre layer of asphaltic concrete was encountered. Underlying the surficial layer of asphaltic concrete, a road base material was observed. The road base consisted of a brown crushed sand with gravel and some silt and has a thickness of about 200 millimetres.
- Underlying the pavement structure, a layer of fill consisting of brown silty sand with trace clay was encountered. The fill has a thickness of about 1.9 metres and extends to about 2.1 metres below surface grade. Standard Penetration Test results (N values) recorded in the fill range from 6 to 20 blows per 300 millimetres indicating a loose to compact relative

density. One grain size distribution test was carried out on a sample of the fill (refer to the Soil Grading Chart in Appendix H).

- A native deposit of brown sand with some silt was encountered below the fill material. The sand deposit has a thickness of about 2.8 metres and extends to a depth of about 5.0 metres below surface grade. Standard Penetration Test results (N values) recorded in the sand range from 4 to 15 blows per 300 millimetres indicating a loose to compact relative density. One grain size distribution test was carried out on a sample of the sand (refer to the Soil Grading Chart in Appendix H).
- The sand is underlain by grey silty clay. The silty clay extends to the termination depth of borehole 22-08 at about 9.8 metres below surface grade. Standard Penetration Test results (N values) recorded in the silty clay range from 2 to 14 blows per 300 millimetres. In-situ shear vane testing was performed in the silty clay deposit. The values of undrained shear strength were greater than 108 kilopascals which indicates a very stiff consistency. One particle size distribution analysis was carried out on a sample of the silty clay (refer to the Soil Grading Chart in Appendix H).
- Based on soil sample appearance, the groundwater level was estimated to be at about 4.3 metres below surface grade at the time of the investigation.

3.2.9 Borehole 22-09 (Margaret Street – Outlet 27)

The following provides a summary of the soil stratigraphy encountered in borehole 22-09:

- Fill material was encountered at surface, extending to about 1.8 metres depth. The fill is variable but can be described as brown sand and gravel to silty sand with trace asphaltic concrete. The upper portion of the fill was frozen at the time of our investigation. Standard Penetration Test results (N values) recorded in the fill range from 4 to 9 blows per 300 millimetres indicating a loose relative density. One grain size distribution test was carried out on a sample of the fill (refer to the Soil Grading Chart in Appendix I).
- A native deposit of brownish grey sandy silt were encountered below the fill material. The sandy silt deposit has a thickness of about 11.0 metres and extends to a depth of about 12.8 metres below surface grade. Standard Penetration Test results (N values) recorded in the sandy silt range from 4 to 15 blows per 300 millimetres indicating a loose to compact relative density. One particle size distribution test was carried out on a sample of the sandy silt (refer to the Soil Grading Charts in Appendix I).
- The sandy silt is underlain by grey silty clay. The silty clay has a thickness of about 5.8 metres and extends to a depth of about 18.6 metres below surface grade. Standard Penetration Test results (N values) recorded in the silty clay indicated 2 blows per 300 millimetres. In-situ shear vane testing was performed in the silty clay deposit. The values of undrained shear strength were recorded as being greater than 108 kilopascals which

indicates a very stiff consistency. One particle size distribution analysis was carried out on a sample of the silty clay (refer to the Soil Grading Chart in Appendix I).

- The silty clay is underlain by glacial till comprised of grey sand and silt with gravel. The glacial till extends to the termination depth of borehole 22-09 at about 18.9 metres below surface grade. A Standard Penetration Test result (N value) recorded in the glacial till was 13 blows per 300 millimetres, indicating a compact relative density.
- Based on soil sample appearance, the groundwater level was estimated to be at about 12.2 metres below surface grade at the time of the investigation.

4.0 GEOTECHNICAL RECOMMENDATIONS

4.1 General

As discussed in Section 1.0, the project may include reconstruction and replacement of the existing storm outlets and pipes.

4.2 Excavations

For the proposed reconstruction of the storm outlets and pipes, it is anticipated that the replacement pipes and outlets will be of similar size and depth below surface grade. The depth of excavation will vary from outlet to outlet based on existing slope of surface grade and the slope of the outlet pipe. The maximum depth of pipe is not anticipated to exceed 4 metres below surface grade at any of the sites.

The sides of the excavations in the overburden should be sloped in accordance with the requirements in Ontario Regulation 213/91 under the Occupational Health and Safety Act. According to the Act, the overburden soils can be classified as Type 3 and, accordingly, allowance should be made for excavation side slopes of 1 horizontal to 1 vertical, or flatter. As an alternative or where space constraints dictate, the service installations could be carried out within a tightly fitting, braced steel trench box, specifically designed for this purpose.

During the excavation process, no excavated material should be piled, nor machinery or equipment placed, closer than 2.0 metres from the edge of the top of slope. No vertical unbraced excavations should be performed in the soil.

An examination of the excavation slopes should be performed by a qualified geotechnical personnel before any worker enters the excavation. The exposed soil should be protected against erosion from water run-off or rain. Excavation side slopes should not be left exposed to inclement weather.

4.3 Pipe Bedding, Cover and Trench Backfill

The bedding for the proposed services should be in accordance with OPSD 802.010 and 802.031 for flexible and rigid pipes in overburden excavations. The pipe bedding material should consist of at least 150 millimetres of well-graded crushed stone meeting OPSS 1010 for Granular A.

In areas where the subsoils are disturbed or where unsuitable material (such as fill material, organic soil or existing trench backfill material) exists below the pipe subgrade level, the disturbed/unsuitable material should be removed and replaced with engineered granular fill such as OPSS Granular A or Granular B Type II or III. To provide adequate support for pipes in the long term in areas where subexcavation of material is required below design subgrade level, the excavations should be sized to allow a 1 horizontal to 2 vertical spread of granular material down and out from the bottom of the pipes. The use of clear crushed stone as bedding or subbedding material should not be permitted.

Cover material, from pipe spring line to at least 300 millimetres above the top of the pipe, should consist of granular material, such as OPSS Granular A.

The granular bedding and cover materials should be compacted in maximum 200-millimetre thick lifts to at least 95 percent of the Standard Proctor Maximum Dry Density (SPMDD) of the material.

In areas where the pipes are below or near hard surfaced areas, consideration should be given to the composition of the trench backfill and the potential for differential frost heaving between the area over the service trench and the adjacent asphalt surface. In these areas, acceptable native materials should be used as backfill between the roadway subgrade level and the depth of seasonal frost protection (ie. 1.8 metres below finished grade). The backfill materials within the zone of frost penetration should match the materials exposed on the trench walls. Backfill below the zone of seasonal frost penetration could consist of either acceptable native material or imported granular material conforming to OPSS Granular B Types I, II or III.

To minimize future settlement of the backfill and achieve an acceptable subgrade for any roadways, curbs, etc., the trench backfill should be compacted in maximum 300-millimetre thick lifts to at least 95 percent of the SPMDD.

4.4 Construction Dewatering

It is anticipated that any groundwater inflow from the overburden or surface water runoff into the excavation should be handled by pumping from within the excavations. Flatter side slopes or tightly fitting trench boxes may be necessary for excavations below the groundwater level due to sloughing of the excavation sidewalls. It is not expected that short term pumping during excavation will have a significant effect on nearby structures and services.

Water levels can be expected to vary on a seasonal basis with the highest levels occurring in the spring. In order to reduce the potential for groundwater pumping during excavation, consideration should be given to conducting construction during drier periods of the year (i.e. June to October).

Table 4.1 below provides the estimated groundwater level at each of the nine outlet locations based on soil sample appearance and observations within the open boreholes during the field investigation.

Table 4.1: Summary of Estimated Groundwater Levels (at Time of Investigation)

Location	Estimated Groundwater Level (mbgs)	Geodetic Elevation
Christie Street - Outlet 41	2.1 mbgs	116.6 m
Boundary St Pathway- Outlet 35	3.0 mbgs	122.3 m
Paul Martin Drive - No Outlet #	No Infiltration Observed	n/a
Everett Street - Outlet 42	4.9 mbgs	117.7 m
Norman Street - Outlet 56	7.2 mbgs	115.2 m
Murray Street - Outlet 46	3.2 mbgs	115.4 m
Doran Street - Outlet 45	2.3 mbgs	116.5 m
Moffatt Street - Outlet 31	4.3 mbgs	119.5 m
Margaret Street - Outlet 27	12.2 mbgs	116.4 m

Notes:

1. As indicated above, the estimated groundwater levels are based on visual and tactile observations at the time of the field investigation. No standpipe piezometers were installed as part of this investigation.

4.5 Erosion Protection

The outlets should be protected from erosion and scour using rip rap (refer to OPSD 810.010). The rip rap should be suitably sized and graded to prevent damage to the rip rap. The sizing and grading should take into consideration the flow velocities, ice buildup, ice damming effects, etc. at each individual outlet.

The rip rap should meet the requirements of OPSS 1004 and should be placed in accordance with OPSS 511. A non-woven geotextile meeting OPSS 1860 Class II requirements should be placed between the subgrade surface and the rip rap. All seams in the geotextile should be sewn or provided with at least 0.5 metres of overlap.

The geotextile and rip rap should be placed on undisturbed, native soil. All disturbed or deleterious material, such as construction debris, organic material, etc., should be removed from below the rip rap. Removal of vegetation may also be required. Excavation at the toe of the slope should be carefully planned and controlled to ensure excavation at the toe does not reduce the stability of the existing slope. For example, excavation and backfilling near the toe of the slope should be carried out in short sections. Excavation below the water level, where required, could be carried out “in the wet”, provided that in water work is permitted and necessary permits have been obtained.

The rip rap should be placed to 0.5 metres above the high water mark and should be compacted by tamping with the bucket of the excavator. The thickness of the rip rap should be at least 1.5 times the maximum particle size.

To prevent undermining (i.e., erosion of the soil below the rock fill), we recommend that the underside of the rock fill extend to the approximate elevation of the creek bed adjacent to the slope.

The rock fill should be placed with a slope not steeper than 1.5 horizontal to 1 vertical and should be underlain by a nonwoven geotextile meeting OPSS 1860 Class II with 0.5 metre overlaps.

Consideration should be given to the carrying out the work at a time of year when the water level in the rivers are expected to be low, such as late summer/early fall.

5.0 SLOPE STABILIZATION ASSESSMENT

5.1 Overview

The nine storm outlets included as part of this investigation all terminate into the Indian and Muskrat Rivers. The banks of the rivers surrounding the outlets vary significantly in slope and height. The nine outlet locations were assessed by GEMTEC personnel using rating charts in Table 4.2 of the Ontario Ministry of Natural Resources Technical Guide – River and Stream Systems; Erosion Hazard Limit (2002). These assessments were used as a preliminary guide, to determine if any of the slopes within the vicinity of the outlets present a potential for slope stability failure and to identify where detailed assessments of the existing factor of safety is required.

Table 5.1 below summarizes the findings of the slope assessment using the MNR rating charts:

Table 5.1: Summary of Slope Assessment at Outlets

Location	Comments	Potential for Slope Failure
Christie Street Outlet 41	No active erosion; minimal slope height; pipe outlets near bottom of river bank	Low

Boundary Street Pathway Outlet 35	Minimal slope inclination; pipe outlet is broken and deteriorated contributing to active surface erosion	Low
Paul Martin Drive No Outlet #	Active surface erosion, pipe outlet is at top of slope; minimal slope inclination	Low
Everett Street Outlet 42	Active surface erosion; minimal slope inclination; pipe outlet is near top of slope	Low
Norman Street Outlet 56	Active surface erosion of river bank; steep slope inclination; pipe outlet is at top of slope	Moderate
Murray Street Outlet 46	No active erosion; minimal slope height; pipe outlets near bottom of river bank	Low
Doran Street Outlet 45	No active erosion; minimal slope height; pipe outlets near bottom of river bank	Low
Moffatt Street Outlet 31	Active surface erosion of river bank, moderate slope inclination, pipe outlet near top of slope	Slight
Margaret Street Outlet 27	Active bank erosion, steep slope inclination; pipe outlets near top of slope	Moderate

Based on the slope assessment for each of the nine outlets, three locations were identified as requiring further slope analysis to determine the existing factor of safety and possible remediation alternatives. They include Norman Street – Outlet 56; Moffatt Street – Outlet 31; and, Margaret Street – Outlet 27.

Furthermore, three locations were also identified as exhibiting active surface erosion from surface water runoff. These locations include Boundary Road Pathway – Outlet 35; Paul Martin Drive – No Outlet #; and, Everett Street – Outlet 42.

5.1.1 Slope Stabilization Alternatives

5.1.1.1 Outlet and Riverbank Support

Christie Street – Outlet 41, Murray Street – Outlet 46 and Doran Street – Outlet 45 were identified as having little to no erosion of the river bank or slope immediately adjacent to the outlet. In all three cases, the pipe outlet is below the water level or near the level of the adjacent river.

As mentioned in Section 4.5, the use of rip-rap should be considered around the outlet and river bank to provide protection from erosion and scour.

5.1.2 Slope Erosion Protection

Erosion from surface water runoff was identified at the Boundary Road Pathway – Outlet 35, Paul Martin Drive – No Outlet # and Everett Street – Outlet 42. In all three cases, the outlets are located near the top of the slope which was also found to have minimal slope inclination at all three locations. Based on the slope assessment, there is also a low potential for future slope failure based on the existing conditions.

To reconstruct the slope and protect it from future erosion the following alternatives are suggested:

Alternative	Strategy	Comments
Slope Re-grading	Re-grading the eroded slope by moving the crest of the slope into the tablelands. The location of the toe could be maintained.	In order to flatten the existing slopes, earth excavation and removal of any remaining vegetation is required. Furthermore, loss of the tableland area is required in order to construct the stabilization alternative.
Blast Rock / Rip-Rap Buttress	The eroded soil downstream of the outlets could be replaced with well graded blast rock or rip-rap inclined at 1.5 horizontal to 1 vertical, or flatter.	The location of the toe could be maintained which would prevent encroachment of the slope into the adjacent river. Some loss of the tableland area and removal of existing vegetation may be required in order to accommodate an inclination of 1.5H:1V while maintain the location of the toe.
Reinforced Soil Slope	A reinforced soil slope could be constructed along the slope. A reinforced slope generally consists of excavating portions of the slope and rebuilding with compacted granular materials reinforced with plastic or steel grid reinforcement. A permanent erosion blanket is generally incorporated into the design to prevent erosion and promote vegetative growth.	In order to construct the reinforced slope, earth excavation and removal of existing vegetation (including trees) is required.

The slope erosion and stabilization alternatives presented above should be implemented and combined with the following erosion control measures:

- Following regrading or where a vegetated slope face is desired, a thin layer of topsoil could be placed along the slope face and seeded. A suitable erosion control blanket (i.e. double net, straw and coconut fibre blanket) should then be installed on the surface and secured using wood stakes. It is important that suitable vegetation be established over the slope. This could include special perennials such as crown vetch which is ideal for steep slopes and is commonly used along roadway embankments.
- Installation of toe erosion protection to prevent erosion of the toe of the slope (e.g. rip rap, riverstone, etc.). The type of toe erosion protection will depend on the anticipated flow velocities of the adjacent river and ice scour effects.

5.1.3 Slope Stability Assessment

Based on the preliminary assessment using Table 4.2 of the Ontario Ministry of Natural Resources Technical Guide – River and Stream Systems; Erosion Hazard Limit (2002) as a guide, three slopes within the vicinity of the outlets were determined to have a low to moderate potential for future slope instability and possible slope failure. These locations include Norman Street – Outlet 56, Moffat Street – Outlet 31 and Margaret Street – Outlet 27.

Active soil and bank erosion was observed at each of the three outlet locations. The slopes or river banks are relatively steep with a slope inclination ranging from about 16 degrees to 34 degrees and height of slope ranging from about 8 metres to 16 metres.

Based on the preliminary assessment, it is recommended that further slope stability analysis be completed using slope stability software to determine such factors as the existing slope factor of safety and the stability of the slope under seismic loading conditions. A more in-depth analysis will allow for the implementation of slope stabilization measures in order to decrease the probability of occurrence for a deeper slope failure. Such measures could include:

- **Avoidance:** This approach is essentially the “do nothing” alternative. For this case, no effort is made to reduce the probability of occurrence for a slope failure. In the higher risk areas, demolition of existing dwellings could be considered to reduce the consequences of a failure.
- **External Toe Berm:** Involves the construction of an external rock berm at the bottom of the slope, while maintaining the geometry and vegetation along the upper portion of the slope. The rock berm will encroach into the river. The berm also protects the toe from erosion.
- **Slope Flattening:** Involves re-grading the slope at a shallower angle that will be stable. Removal of the existing vegetation and loss of horizontal, tableland area is required in

order to accommodate the shallower slope angle. Not feasible in areas where existing structures and dwellings are located in close proximity to the slope. Re-vegetation of the regraded slope is required. Erosion protection measures are required at the toe of the slope.

- **Horizontal Drains:** Involves the installation of 4 metre long horizontal wick drains through the slope face using hand operated equipment in order to reduce the groundwater levels. The drains could be installed on a regularly spaced grid pattern and inclined from the horizontal to promote gravity drainage. Erosion protection measures should be implemented at the toe of the slope.
- **Full Slope Reconstruction:** This method involves excavating the existing slope and rebuilding with rock fill in benches. Similar to construction of an external toe berm; however, for full slope reconstruction, the rock fill extends up to the crest of the slope. Full slope reconstruction also protects the toe from erosion.
- **Structural Elements:** Involves the installation of sheet piling and tie-backs to strengthen and stabilize the slope. The sheet piling could be installed near the upper portion of the slope and driven to refusal. Tie-backs, installed into bedrock, will likely be required to restrain the top of the piles. Erosion protection measures are required at the toe of the slope.

Further comments on the selection of an appropriate remediation alternative could be provided following the detailed slope stability assessment at each location.

5.2 Detailed Design

It is recommended that GEMTEC be consulted during the detailed design stage to confirm that the information in this report has been interpreted as intended. If required, permitting for in-water stabilization works, such as a Fisheries Act authorization from DFO and a permit under the Endangered Species Act, 2007 associated with potential impacts to SAR habitat, should also be finalized during the detailed design stage.

5.3 Disposal of Excess Soil

The presence or implications of possible surface and/or subsurface contamination, including naturally occurring source of contamination, are outside the terms of reference for this report. This report does not constitute a Phase II Environmental Site Assessment (ESA) nor does it constitute a contaminated material management plan.

6.0 CLOSURE

It is noted that the information provided in this report pertain only to the geotechnical aspects of the project. It is recommended that the final design drawings be reviewed by the geotechnical engineer to ensure that the guidelines provided in this report have been interpreted as intended.

We trust this report provides sufficient information for your present purposes. If you have any questions concerning this report, please do not hesitate to contact our office.

Respectfully,

GEMTEC Consulting Engineers and Scientists Limited



Adam Stamplicoski, C.E.T.
Senior Geotechnical Technologist

Brent Wiebe, P.Eng
Vice President of Operations – Ontario
Senior Geotechnical Engineer

DRAFT

APPENDIX A

Christie Street – Outlet 41
Site Plan – Figure A1
Record of Borehole Sheets
Laboratory Test Results



Key Map - NTS

No.	REVISION	By	DATE
1	ISSUED FOR REVIEW	D.M.	2021-11-25


No.	REVISION	By	DATE
1	ISSUED FOR REVIEW	D.M.	2021-11-25

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CE CATHBASIN
- M STORM MANHOLE
- S SANITARY MANHOLE

THE POSITION OF THE POLE LINES, CONDUITS, WATERMANS, SEWERS, AND OTHER UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK
THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE



CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW

CITY OF PEMBROKE, ONTARIO

SHEET TITLE

OUTLET # 41
General Plan & Cross Section

DESIGNED BY:	APPROVED BY:
--------------	--------------



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

DRAFT



APPENDIX B

Boundary Road Pathway – Outlet 35

Site Plan – Figure B1

Record of Borehole Sheets

Laboratory Test Results



Key Map - NTS

No.	REVISION	By	DATE
1	ISSUED FOR REVIEW	D.M.	2021-11-25


LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CB CATHBASIN
- SM STORM MANHOLE
- SM SANITARY MANHOLE

THE POSITION OF THE POLE LINES, CONDUITS, WATERMANS, SEWERS, AND OTHER UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK
THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.

DRAFT



JOB TITLE



CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW

CITY OF PEMBROKE, ONTARIO

SHEET TITLE

OUTLET # 35
General Plan & Cross Section

DESIGNED BY: _____ APPROVED BY: _____



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

RECORD OF BOREHOLE 22-02

CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Boundary Road Pathway - Outlet 35

SHEET: 1 OF 1
 DATUM: CGVD2013
 BORING DATE: Feb 14 2022



DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE			SAMPLES				PENETRATION RESISTANCE (N), BLOWS/0.3m		SHEAR STRENGTH (Cu), kPA		ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION				
		DESCRIPTION	STRATA PLOT	ELEV. / DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m	●	▲	+	⊕						
				WATER CONTENT, %														
									10	20	30	40	50	60	70	80	90	
0		Ground Surface		125.30														
		FILL: brown gravelly sand with some silt, frozen		125.10	1	SS	400	-										
		FILL: brown silty clay with trace sand, frozen		0.20														
1					2	SS	300	-										
		Dark grey to brown SILTY CLAY with trace sand and trace organics (wood)		123.93	3	SS	350	9	●									
2				1.37	4	SS	400	9	●									
					5	SS	400	10	●									
3		Brown LEAN CLAY, stiff, wet		122.25	6	SS	600	11	●									
		- becoming wet at 3.0 metres		3.05	7	SS	600	10	●									
4					8	SS	600	12	●									
5		End of Borehole 22-02 at 4.9 metres within lean clay		120.42														
				4.88														
6																		
7																		
8																		
9																		
10																		

GEO - BOREHOLE LOG - 101078.001 BOREHOLE LOGS DRAFT GP J GEMTEC 2018 GDT - 3/27/22

DRAFT

APPENDIX C

Paul Martin Drive – No Outlet #
Site Plan – Figure C1
Record of Borehole Sheets
Laboratory Test Results




No.	1	ISSUED FOR REVIEW	D.M.	2021-11-25
		REVISION	By	DATE

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CE CATHBASIN
- M STORM MANHOLE
- S SANITARY MANHOLE


BEFORE STARTING WORK
 THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE
CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW
 CITY OF PEMBROKE, ONTARIO

SHEET TITLE
OUTLET # UNKNOWN
 General Plan & Cross Section

DESIGNED BY: _____ APPROVED BY: _____





SCALE: 1:250	REVIEWED BY:	PROJECT No.:
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.:
DATE: 25 NOV, 2021	SHEET NO: 1	

DRAFT

APPENDIX D

Everett Street – Outlet 42
Site Plan – Figure D1
Record of Borehole Sheets
Laboratory Test Results



Key Map - NTS


No.	REVISION	By	DATE
1	ISSUED FOR REVIEW	D.M.	2021-11-25

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CATHBASIN
- STORM MANHOLE
- SANITARY MANHOLE

THE POSITION OF THE POLE LINES, CONDUITS, WATERMANS, SEWERS, AND OTHER UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK
THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE

CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW



CITY OF PEMBROKE, ONTARIO

SHEET TITLE

OUTLET # 42

General Plan & Cross Section

DESIGNED BY: _____ APPROVED BY: _____



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

RECORD OF BOREHOLE 22-04

CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Everett Street - Outlet 42

SHEET: 1 OF 1
 DATUM: CGVD2013
 BORING DATE: Feb 16 2022



DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES				PENETRATION RESISTANCE (N), BLOWS/0.3m		SHEAR STRENGTH (Cu), kPA		ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m	DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m		WATER CONTENT, %			
									10	20	30			40
0		Ground Surface		122.55										
		FILL: Dark brown sand and silt, some gravel, trace concrete debris			1	SS	300	-						
1				121.33	2	SS	150	35						
		Dark grey CLAYEY SAND, loose, moist		1.22	3	SS	0	9						
2					4	SS	200	7						
					5	SS	200	7						
3		Dark Grey CLAYEY SILT, firm, moist		119.50	6	SS	250	12						
				3.05	7	SS	450	52						
4					8	SS	350	44						
		Dark Grey SILTY CLAY, stiff, wet - becoming wet at 4.9 metres		117.67	9	SS	500	12						
				4.88	10	SS	400	7						
5														
		Grey clayey sand and silt with some gravel (GLACIAL TILL), compact, moist		116.15	11	SS	300	30						
				6.40										
6		Dynamic Cone Penetration Test (DCPT)		115.55										
				7.00										
7														
8														
9														
10														
		End of Borehole 22-04 at 10.2 metres due to DCPT refusal		112.31										
				10.24										

GEO - BOREHOLE LOG 101078.001 BOREHOLE LOGS DRAFT GP J GEMTEC 2018 GDT 3/27/22

DRAFT

APPENDIX E

Norman Street – Outlet 56
Site Plan – Figure E1
Record of Borehole Sheets
Laboratory Test Results



Key Map - NTS

1	ISSUED FOR REVIEW	D.M.	2021-11-25
No.	REVISION	By	DATE


1	ISSUED FOR REVIEW	D.M.	2021-11-25
No.	REVISION	By	DATE

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CE CATHBASIN
- M STORM MANHOLE
- M SANITARY MANHOLE

THE POSITION OF THE POLE LINES, CONDUITS, WATERMANS, SEWERS, AND OTHER UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK
THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE


CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW

CITY OF PEMBROKE, ONTARIO

SHEET TITLE

OUTLET # 56
General Plan & Cross Section

DESIGNED BY: _____ APPROVED BY: _____



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

RECORD OF BOREHOLE 22-05

CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Norman Street - Outlet 56

SHEET: 1 OF 1
 DATUM: CGVD2013
 BORING DATE: Mar 14 2022



DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES				PENETRATION RESISTANCE (N), BLOWS/0.3m		SHEAR STRENGTH (Cu), kPA		ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m	▲ DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m	●	WATER CONTENT, % Wp — W — Wl		
0		Ground Surface		122.44									
		ASPHALTIC CONCRETE (50mm)		0.05									
		ROAD BASE: brown crushed sand with gravel and some silt, frozen		0.20									
		ROAD SUBBASE: brown gravelly sand with trace silt, frozen		121.94	1	GS	-						
		FILL: brown sand and silt with trace gravel, compact		0.50									
1				120.94	2	SS	350	35					
		Brown SILTY SAND, loose, moist		1.50									
2				120.00	3	SS	450	6					
		Brown becoming grey SILTY CLAY, stiff to very stiff, moist		2.44									
3					4	SS	450	9					
					5	SS	500	7					
4					6	SS	500	4					
					7	SS	500	1					
5													
6		Grey clayey sand and gravel (GLACIAL TILL), compact, moist		116.64	8	SS	300	21					
				5.80									
7					9	SS	300	15					
		- becoming wet at 7.2 metres											
8				114.24	10	SS	300	11					
				8.20									
9		End of Borehole 22-05 at 8.2 metres within glacial till											
10													

GEO - BOREHOLE LOG 101078.001 BOREHOLE LOGS DRAFT GP J GEMTEC 2018 GDT 3/27/22

DRAFT

APPENDIX F

Murray Street – Outlet 46
Site Plan – Figure F1
Record of Borehole Sheets
Laboratory Test Results




No.	REVISION	By	DATE
1	ISSUED FOR REVIEW	D.M.	2021-11-25

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CATHBASIN
- STORM MANHOLE
- SANITARY MANHOLE



BEFORE STARTING WORK
 THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE
CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW
 CITY OF PEMBROKE, ONTARIO

SHEET TITLE
OUTLET # 46
 General Plan & Cross Section

DESIGNED BY: _____ APPROVED BY: _____



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

RECORD OF BOREHOLE 22-06

CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Murray Street - Outlet 46

SHEET: 1 OF 1
 DATUM: CGVD2013
 BORING DATE: Feb 14 2022

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES				PENETRATION RESISTANCE (N), BLOWS/0.3m		SHEAR STRENGTH (Cu), kPA		ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m	▲ DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m	● PENETRATION RESISTANCE (N), BLOWS/0.3m	+ NATURAL ⊕ REMOULDED		
0		Ground Surface		118.58									
		ASPHALTIC CONCRETE (50mm)		0.05									
		ROAD BASE: brown crushed sand with gravel and some silt, frozen		0.21	1	GS	-						
		ROAD SUBBASE: brown sand with some gravel and some silt, frozen											
1		Brown SILTY SAND, loose, moist		117.56 1.02	2	SS	600 36		●				
2					3	SS	400 4		●				
3					4	SS	400 2		●				
4		Grey SILTY CLAY with sand seams, firm, wet		115.38 3.20	5	SS	400 5		●				
		- becoming wet at 3.2 metres											
5		End of Borehole 22-06 at 4.6 metres within silty clay		114.01 4.57	6	SS	600 1		●				
6													
7													
8													
9													
10													



DRAFT

GEO - BOREHOLE LOG - 101078.001 BOREHOLE LOGS DRAFT GP J GEMTEC 2018 GDT - 3/27/22

DRAFT

APPENDIX G

Doran Street – Outlet 45
Site Plan – Figure G1
Record of Borehole Sheets
Laboratory Test Results




1	ISSUED FOR REVIEW	D.M.	2021-11-25
No.	REVISION	By	DATE

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CB CATHBASIN
- SM STORM MANHOLE
- SM SANITARY MANHOLE

THE POSITION OF THE POLE LINES, CONDUITS, WATERMANS, SEWERS, AND OTHER UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK
THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE

CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW



CITY OF PEMBROKE, ONTARIO

SHEET TITLE

OUTLET # 45

General Plan & Cross Section

DESIGNED BY:	APPROVED BY:
--------------	--------------



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

RECORD OF BOREHOLE 22-07

CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Doran Street - Outlet 45

SHEET: 1 OF 1
 DATUM: CGVD2013
 BORING DATE: Feb 15 2022

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE			SAMPLES				PENETRATION RESISTANCE (N), BLOWS/0.3m		SHEAR STRENGTH (Cu), kPA		ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m	●	▲	+	⊕		
WATER CONTENT, %														
								10 20 30 40 50 60 70 80 90		Wp — W — Wl				
0		Ground Surface		118.78										
		FILL: dark brown to brown sand with some silt and trace gravel, frozen												
1		Brown SILTY SAND with trace gravel, moist		117.82 0.96	1	GS	-							
2					2	SS	400 12		●					
3					3	SS	400 7		●					
4		- becoming wet at 2.3 metres			4	SS	400 3		●					
5		- split-spoon refusal due to organic wood material at about 3.3 metres			5	SS	200 50/25mm							
6		Grey SILTY CLAY, firm, wet		115.12 3.66	6	SS	400 7		●					
7		End of Borehole 22-07 at 4.6 metres within silty clay		114.21 4.57										
8														
9														
10														



DRAFT

GEO - BOREHOLE LOG - 101078.001 BOREHOLE LOGS DRAFT GP J GEMTEC 2018 GDT - 3/27/22

DRAFT

APPENDIX H

Moffatt Street – Outlet 31
Site Plan – Figure H1
Record of Borehole Sheets
Laboratory Test Results




Key Map - NTS

1	ISSUED FOR REVIEW	D.M.	2021-11-25
No.	REVISION	By	DATE

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CB CATHBASIN
- MH STORM MANHOLE
- SM SANITARY MANHOLE



BEFORE STARTING WORK
 THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE
CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW
 CITY OF PEMBROKE, ONTARIO

SHEET TITLE
OUTLET # 31
 General Plan & Cross Section

DESIGNED BY: _____ APPROVED BY: _____



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

RECORD OF BOREHOLE 22-08

CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Moffatt Street - Outlet 31

SHEET: 1 OF 1
 DATUM: CGVD2013
 BORING DATE: Mar 15 2022



DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE			SAMPLES				PENETRATION RESISTANCE (N), BLOWS/0.3m		SHEAR STRENGTH (Cu), kPA		ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m	●	▲	+	⊕		
				WATER CONTENT, %										
				10	20	30	40	50	60	70	80	90		
0		Ground Surface		123.80										
		ASPHALTIC CONCRETE (40mm)		0.04										
		ROAD BASE: brown crushed sand with gravel and some silt, frozen		0.24	1	GS	-							
		FILL: brown silty sand with trace clay, loose, frozen becoming moist												
1					2	SS	450	20						
2					3	SS	600	6						
		Brown SAND with some silt, loose to compact, moist		121.67										
				2.13	4	SS	400	8						
3					5	SS	350	15						
4					6	SS	400	4						
		- becoming wet at 4.3 metres												
5					7	SS	400	15						
		Grey SILTY CLAY, very stiff, wet		118.82										
				4.98	8	SS	200	14						
6					9	SS	600	5						
7					10	SS	600	3						
8					11	SS	600	6						
9														
					12	SS	600	2						
10		End of Borehole 22-08 at 9.8 metres within silty clay		114.04										
				9.76										

GEO - BOREHOLE LOG 101078.001 BOREHOLE LOGS DRAFT GP J GEMTEC 2018 GDT 3/27/22

DRAFT

APPENDIX I

Margaret Street – Outlet 27
Site Plan – Figure I1
Record of Borehole Sheets
Laboratory Test Results



Key Map - NTS

No.	REVISION	By	DATE
1	ISSUED FOR REVIEW	D.M.	2021-11-25


No.	REVISION	By	DATE
1	ISSUED FOR REVIEW	D.M.	2021-11-25

LEGEND

- STORM SEWER
- SANITARY SEWER
- WATERMAIN
- CB CATHBASIN
- SM STORM MANHOLE
- SM SANITARY MANHOLE

THE POSITION OF THE POLE LINES, CONDUITS, WATERMANS, SEWERS, AND OTHER UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.



BEFORE STARTING WORK
THE CONTRACTOR SHALL CONFIRM THE POSITION AND EXACT LOCATION OF ALL SUCH UTILITIES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM MADE DURING THE COURSE OF THE CONTRACT WORK.



JOB TITLE
CITY WIDE FLOOD RISK ASSESSMENT AND STORM OUTLET REVIEW
CITY OF PEMBROKE, ONTARIO

SHEET TITLE
OUTLET # 27
General Plan & Cross Section

DESIGNED BY:	APPROVED BY:
--------------	--------------



SCALE: 1:250	REVIEWED BY:	PROJECT No.
DRAWN BY: P.S.	DESIGNED BY: R.A.	FILE No.
DATE: 25 NOV, 2021	SHEET NO: 1	

RECORD OF BOREHOLE 22-09

CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Margaret Street - Outlet 27

SHEET: 1 OF 2
 DATUM: CGVD2013
 BORING DATE: Mar 16 2022

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES				PENETRATION RESISTANCE (N), BLOWS/0.3m		SHEAR STRENGTH (Cu), kPA		ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m	▲ DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m	●	WATER CONTENT, % W _p — W — W _L		
0		Ground Surface		128.61									
		FILL: brown crushed sand with gravel and some silt, frozen		128.36	1	GS	-						
		FILL: brown sand and gravel with some silt, frozen		128.01									
		FILL: brown silty sand with trace asphalt particles, loose, moist		128.01									
1					2	SS	450 9		●				
2		Brownish grey SANDY SILT, loose to compact, moist		126.78	3	SS	500 4		●				
				1.83									
					4	SS	400 4		●				
					5	SS	500 6		●				
					6	SS	500 9		●				
					7	SS	500 4		●				
					8	SS	400 10		●				
					9	SS	350 10		●				
					10	SS	450 14		●				
					11	SS	400 14		●				

GEO - BOREHOLE LOG 101078.001 BOREHOLE LOGS DRAFT GP J GEMTEC 2018 GDT 3/27/22

RECORD OF BOREHOLE 22-09


CLIENT: Aquafor Beech Ltd.
 PROJECT: Geotechnical Investigation - City of Pemroke Storm Outlet Review
 JOB#: 101078.001
 LOCATION: Margaret Street - Outlet 27

SHEET: 2 OF 2
 DATUM: CGVD2013
 BORING DATE: Mar 16 2022

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE			SAMPLES				● PENETRATION RESISTANCE (N), BLOWS/0.3m ▲ DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m	SHEAR STRENGTH (Cu), kPA + NATURAL ⊕ REMOULDED WATER CONTENT, % W _p — W — W _L	ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	RECOVERY, mm	BLOWS/0.3m				
11					12	SS	450	12	●			
12		- becoming wet at 12.2 metres			13	SS	400	15	●			
13		Grey SILTY CLAY, very stiff, wet		115.81 12.80								
14					14	SS	600	2	●			
15					15	SS	500	2	●			
16												
17					15	SS	500	2	●			
18												
19		Grey sand and silt with gravel (GLACIAL TILL), compact, wet		110.01 18.60 109.71 18.90	16	SS	600	13	●			
19		End of Borehole 22-01 at 18.9 metres within glacial till										
20												
21												

GEO - BOREHOLE LOG - 101078.001 BOREHOLE LOGS DRAFT GP J. GEMTEC 2018.GDT - 3/27/22

experience • knowledge • integrity



DRYEF

civil	civil
geotechnical	géotechnique
environmental	environnementale
field services	surveillance de chantier
materials testing	service de laboratoire des matériaux

expérience • connaissance • intégrité



APPENDIX J

Proposed Solutions of Sewer Pipes and Catchbasins in the PCSWMM Model

This appendix includes the detailed proposed works for each storm sewer system. All the sewer pipes listed below have modifications in pipe size upgrades and/or inlet/outlet invert elevations in order to meet the 100-year level of service. The orange highlights indicate the modifications in sewer pipe sizes or inverts.

All the catchbasins listed in the tables below have changes in the type of catchbasins and/or the number of catchbasins to increase the flow rate of flood water entering the storm sewer system and reduce flooding on streets. More details can be found in the PCSWMM models for each area with Tag “MOD” to show proposed solutions.

Table J.1: Proposed Sewer Pipe Information of Amalgamated Model

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
18_0001	111.033	110.494	0.9	111.033	110.494	1.8
18_0002	111.557	111.033	0.9	111.557	111.033	1.8
18_0003	112.807	111.557	1.2	112.807	111.557	1.65
18_0004	114.074	112.807	1.2	114.074	112.807	1.5
18_005	117.454	114.074	1.2	117.454	114.074	1.35
18_008	118.355	117.966	1.2	118.355	117.966	1.35
18_0114	146.45	146.22	0.75	146.062	145.6	1.05
18_012	119.679	117.671	0.525	119.679	117.671	0.75
18_014	119.907	119.818	0.525	119.907	119.818	0.75
18_016	120.09	119.907	0.525	120.09	119.907	0.75
18_017	120.309	120.066	0.525	120.309	120.066	0.75
18_019	120.574	120.309	0.525	120.574	120.309	0.75
18_026	120.99	120.573	0.45	120.99	120.573	0.675
18_037	121.66	121.052	0.375	121.66	121.052	0.525
18_045	120.021	117.454	1.35	117.989	117.454	1.5
18_046	120.158	120.021	1.35	119.452	117.989	1.65
18_048	120.246	120.226	0.9	119.667	119.452	1.65
18_051	121.321	120.726	0.9	120.971	119.667	1.5
18_054	123.664	121.321	0.9	123.664	120.971	1.5
18_058	124.606	123.684	0.9	124.606	123.684	1.5
18_059	124.636	124.606	0.9	124.636	124.606	1.65
18_060	124.7	124.636	0.9	124.7	124.636	1.65
18_063	124.89	124.7	0.9	124.89	124.7	1.65
18_078	126.377	126.233	0.9	125.321	124.89	1.65
18_079	126.958	126.377	0.9	126.356	125.321	1.5
18_081	127.798	126.958	0.9	127.683	126.356	1.5
18_082	128.16	127.938	0.75	128.16	127.824	1.35
18_084	132.534	128.344	0.75	132.234	128.344	1.05

City-Wide Flood Risk Assessment and Storm Outlet Review
 City of Pembroke

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
18_085	136.153	133.116	0.75	135.75	132.234	1.05
18_086	136.21	136.21	0.75	136.21	135.75	1.05
18_091	139.52	139.09	0.75	139.52	138.8	1.2
18_093	139.75	139.52	0.75	139.75	139.52	1.2
18_095	139.91	139.75	0.75	139.91	139.75	1.2
18_097	142.2	140.06	0.6	142.2	140.06	0.825
18_099	144.7	142.2	0.6	144.7	142.2	0.825
18_101	145.34	145.03	0.75	144.932	144.7	1.2
18_103	145.77	145.34	0.75	145.259	144.932	1.2
18_106	146.15	145.77	0.75	145.55	145.259	1.2
18_109	146.22	146.15	0.75	145.6	145.55	1.2
18_110	146.366	146.28	0.45	145.8	145.6	1.05
18_117	146.9	146.496	0.75	146.528	146.062	1.05
18_119A	147.05	147.018	0.75	146.762	146.7	0.975
18_119B	147.018	146.92	0.75	146.7	146.528	1.05
18_123	147.166	147.05	0.75	146.9	146.762	0.9
18_125	147.45	147.166	0.75	147.137	146.9	0.9
18_129a	147.556	147.503	0.75	147.243	147.2	0.825
18_129b	147.503	147.454	0.75	147.2	147.137	0.825
18_159	147.895	147.57	0.75	147.643	147.243	0.75
18_160	147.919	147.9	0.75	147.674	147.643	0.75
18_163	148.364	147.932	0.75	147.8	147.674	0.75
18_165	149.349	148.63	0.5	148.5	147.8	0.45
18_167	150.117	149.715	0.3	149.087	148.5	0.45
18_169	150.277	150.202	0.3	149.3	149.087	0.375
18_170	150.495	150.362	0.3	149.465	149.3	0.375
18_171	150.693	150.495	0.3	150.1	149.465	0.375
18_180	145.812	145.87	0.525	145.812	145.528	1
18_181	145.863	145.719	0.525	145.528	145.464	1
18_183	140.25	136.617	0.6	139.8	135.75	0.825
18_184	141.345	140.218	0.6	140.7	139.8	0.825
18_187	141.521	141.328	0.675	140.9	140.7	1.05
18_188	141.714	141.56	0.675	141.1	140.9	1.05
18_189	141.822	141.758	0.675	141.293	141.1	1.05
18_190	142.026	141.81	0.675	141.688	141.293	1.05
18_193	142.282	142.109	0.675	142.1	141.688	1.05
18_195	142.591	142.54	0.375	142.591	142.54	0.45
18_196	144.122	142.662	0.3	143.7	142.662	0.375
18_199	143.583	143.018	0.6	142.683	142.1	0.825
18_2	120.578	120.522	0.825	120.578	120.158	0.825
18_201	144.876	143.695	0.6	142.75	142.683	0.9
18_202	145.202	144.876	0.6	142.9	142.75	0.9
18_203	128.011	127.897	0.675	127.751	127.683	1.2
18_204	128.38	128.011	0.675	127.9	127.751	1.05
18_207	128.708	128.46	0.675	128.5	127.9	0.825

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
18_208	130.746	128.818	0.525	130.746	128.5	0.525
18_3	117.782	117.671	1.2	117.782	117.671	1.35
18_4	117.671	117.454	1.2	117.671	117.454	1.35
18_5	139.09	137.52	0.6	138.8	137.52	0.9
18_6	137.52	136.26	0.6	137.52	136.26	0.9
C2	145.628	145.202	1	145.464	144.703	1
C108	121.602	120.903	0.6	121.602	120.903	0.75
C20	118.765	118.355	1.2	118.765	118.355	1.35
C31	121.956	121.625	0.6	121.956	121.625	0.75
C35	122.838	122.556	0.3	122.838	122.556	0.375
C6	122.21	122.012	0.525	122.21	122.012	0.675

Table J.2: Proposed Catchbasin Information of Amalgamated Model

Catchbasin Name	Existing Condition	Proposed Condition
18_CB_235	FB-CB-x2	HCI-CB-x2
18_CB_236	HC-CB-x1	HCI-CB-x2
18_MH_0005	HC-CB-x1	HCI-CB-x1
18_MH_0039	FB-CB-x2	HCI-CB-x2
18_MH_0051	FB-CB-x2	HCI-CB-x2
18_MH_0072	FB-CB-x1	HCI-CB-x1
18_MH_0113	FB-CB-x2	HCI-CB-x3
18_MH_0115	HC-CB-x1	HCI-CB-x2
18_MH_0129	HC-CB-x1	TFB-CB-x1
18_MH_0151	FB-CB-x1	HCI-CB-x1
18_MH_0153	HC-CB-x1	TFB-CB-x2
18_MH_0155	FB-CB-x1	HCI-CB-x3
18_MH_0176	FB-CB-x1	TFB-CB-x1
18_MH_0178	HC-CB-x1	HCI-CB-x1
18_MH_0180	TFB-CB-x1	HCI-CB-x3
18_MH_0194	FB-CB-x1	HCI-CB-x1
18_MH_0196	FB-CB-x1	TFB-CB-x1
18_MH_0197	FB-CB-x2	TFB-CB-x2
18_MH_0207	HC-CB-x1	HCI-CB-x1
18_MH_0208	HC-CB-x1	TFB-CB-x1
J8	HC-CB-x1	TFB-CB-x1
STT-2-Amal-ABL	FB-CB-x5	HCI-CB-x2
VN_25-Amal_ABL	FB-CB-x1	TFB-CB-x2

Table J.3: Proposed Sewer Pipe Information of Darcy Model

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
44_0001	115.897	113.277	0.3	115.6	113.277	0.525
44_0004	116.013	115.897	0.3	115.7	115.6	0.525
44_0005	116.925	116.827	0.2	116.625	116.527	0.3
44_0007	117.09	116.925	0.2	116.79	116.625	0.3
44_0008	116.525	116.339	0.2	115.9	115.723	0.525
44_0013	118.814	116.075	0.2	118.814	116.075	0.3
C40	116.913	116.66	0.2	116.6	116.4	0.375
C41_2	116.91	116.741	0.2	116.51	116.4	0.3
C42	116.336	116.033	0.2	115.723	115.7	0.525
C43	116.693	115.839	0.2	116.4	115.839	0.375

Table J.4: Proposed Catchbasin Information of Darcy Model

Catchbasin Name	Existing Condition	Proposed Condition
44_CB_0005	FB-CB-x2	HCI-CB-x1
44_MH_0003	HC-CB-x1	HCI-CB-x1
VN-1--DD-ABL	FB-CB-x1	TFB-CB-x1

Table J.5: Proposed Sewer Pipe Information of Lake St Model

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
09_0001	110.932	109.279	0.75	110	109.279	1.2
09_0002	111.1	110.969	0.75	111	110	1.05
09_0004	111.402	111.37	0.9	111.052	111	0.9
09_0005	111.467	111.402	0.9	111.155	111.052	0.9
09_0007	111.494	111.467	0.9	111.2	111.155	0.9
09_0008	111.547	111.494	0.9	111.295	111.2	0.9
09_0009	111.69	111.547	0.9	111.551	111.295	0.9
09_0012	111.92	111.758	0.75	111.798	111.551	0.75
09_0014	111.964	111.92	0.75	111.824	111.798	0.75
09_0015	112.123	111.964	0.75	111.866	111.824	0.75
09_0019	112.234	112.123	0.75	111.977	111.866	0.75
09_0021	112.238	112.234	0.75	111.981	111.977	0.75
09_0022	112.501	112.238	0.75	112.201	111.981	0.75
09_0023	112.86	112.501	0.45	112.33	112.201	0.6
09_0036	112.651	112.42	0.3	112.23	112.1	0.45
09_0043	111.237	111.199	0.3	111.237	111.199	0.6
09_0048	112.081	111.84	0.3	112	111.84	0.375
09_0049	112.491	112.081	0.3	112.1	112	0.375
10_0001	110.655	109.936	0.375	110.655	109.936	0.6
10_0002	111.182	110.655	0.375	111.182	110.655	0.6

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
10_0004	111.343	111.182	0.375	111.343	111.182	0.6
10_0006	111.833	111.362	0.375	111.833	111.362	0.525
10_0007	112.32	111.874	0.375	112.32	111.874	0.45
10_0008	112.874	112.32	0.3	112.874	112.32	0.375
C50	113.28	113.11	0.3	113.28	112.71	0.3
C52	113.11	112.9	0.3	112.71	112.29	0.375
C53	112.9	112.623	0.3	112.29	112.23	0.375

Table J.6: Proposed Catchbasin Information of Lake St Model

Catchbasin Name	Existing Condition	Proposed Condition
09_MH_0001	FB-CB-x3	HCI-CB-x3
09_MH_0007	FB-CB-x4	HCI-CB-x3
10_MH_0005	FB-CB-x1	TFB-CB-x2

Table J.7: Proposed Sewer Pipe Information of Trafalgar Model

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
6	125.126	122.873	0.45	125.126	122.873	0.75
06_0001	111.766	109.705	0.9	111.6	109.705	1.35
06_0009_1	113.582	113.28	0.9	113.092	112.796	1.35
06_0009_2	113.28	112.052	0.9	112.796	111.6	1.35
06_0014	114.337	113.575	0.9	113.9	113.092	1.35
06_0018	116.297	114.333	0.9	116.297	113.9	1.2
06_0019	118.016	116.297	0.9	118.016	116.297	1.05
06_0020	119.31	119.18	0.9	118.673	118.5	1.2
06_0022	119.708	119.31	0.9	119.198	118.673	1.2
06_0024	120.096	119.772	0.9	119.639	119.198	1.2
06_0025	120.247	120.126	0.9	119.766	119.639	1.2
06_0028	120.603	120.236	0.9	120.183	119.766	1.2
06_0031	120.868	120.601	0.9	120.57	120.183	1.05
06_0032	121.119	120.839	0.9	120.65	120.57	0.9
06_0033	121.291	121.138	0.9	121.291	120.65	0.9
06_0043	123.61	122.891	0.375	123.61	122.891	0.45
06_0045	124.45	123.635	0.375	124.45	123.635	0.45
06_0048	127.282	125.617	0.375	127.282	125.617	0.45
06_0081	119.885	119.146	0.6	119.002	118.016	0.9
06_0082	120.34	119.995	0.6	119.9	119.002	0.9
06_0083	122.022	120.34	0.6	122.022	119.9	0.825
06_0084	122.438	121.998	0.6	122.438	121.998	0.825
06_0085	122.545	122.492	0.75	122.545	122.492	0.9
06_0086	122.657	122.545	0.75	122.657	122.545	0.9

Name	Existing Condition			Proposed Condition		
	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)	Inlet Elev (m)	Outlet Elev (m)	Diameter (m)
06_0087	122.807	122.715	0.75	122.807	122.715	0.825
06_0089	122.916	122.807	0.75	122.916	122.807	0.825
06_0091	123.201	122.916	0.75	123.201	122.916	0.825
06_0092	123.278	123.201	0.675	123.278	123.201	0.75
06_0093	123.328	123.278	0.675	123.328	123.278	0.75
06_0104	126.013	125.838	0.375	126.013	125.838	0.45
06_0105	126.297	126.013	0.375	126.297	126.013	0.45
06_0106	126.61	126.297	0.2	126.61	126.297	0.375
06_0118	122.245	122.072	0.45	122.245	122.072	0.825
06_0119	122.614	122.235	0.45	122.614	122.235	0.825
06_0122	122.868	122.635	0.45	122.868	122.635	0.825
06_0124	125.922	125.072	0.45	125.922	125.072	0.75
06_0129	125.922	126.55	0.45	126.699	125.922	0.75
06_0131	126.714	126.699	0.375	126.714	126.699	0.675
06_0132	126.782	126.714	0.375	126.782	126.714	0.675
06_0134	130.196	126.86	0.375	130.196	126.86	0.45
06_0135	131.838	130.196	0.375	131.838	130.196	0.45
06_0136	132.466	131.957	0.3	132.2	131.957	0.45
08_0050	126.5	126.31	0.525	126.5	126.052	0.9
08_0051	126.702	126.5	0.45	126.702	126.5	0.9
08_0052	127.24	126.702	0.45	127.24	126.702	0.6
08_0054	127.57	127.24	0.45	127.57	127.24	0.6
08_0056	127.95	127.57	0.45	127.95	127.57	0.525
08_0057	128.06	127.95	0.2	128.06	127.95	0.45
08_0059	132.503	128.58	0.2	132.503	128.58	0.375
08_0060	133.123	132.595	0.2	133.123	132.595	0.3
08_0062	132.762	132.564	0.2	132.762	132.564	0.3
08_0063	132.939	132.762	0.2	132.939	132.762	0.3
08_0067	130.436	127.01	0.3	130.436	127.01	0.375
08_0068	131.741	131.436	0.2	131.741	131.436	0.375
08_0072	132.306	131.759	0.2	132.306	131.759	0.375

Table J.8: Proposed Catchbasin Information of Trafalgar Model

Catchbasin Name	Existing Condition	Proposed Condition
06_MH_0038	FB-CB-x5	TFB-CB-x4
06_MH_0046	FB-CB-x3	HCI-CB-x2
06_MH_0049	HC-CB-x1	HCI-CB-x1
06_MH_0057	FB-CB-x1	HCI-CB-x1
06_MH_0059A	HC-CB-x1	HCI-CB-x1
06_MH_0069	FB-CB-x2	TFB-CB-x2
06_MH_0077	FB-CB-x2	HCI-CB-x2
06_MH_0080	HC-CB-x1	TFB-CB-x1
06_MH_0099	FB-CB-x1	HCI-CB-x2

City-Wide Flood Risk Assessment and Storm Outlet Review
City of Pembroke

Catchbasin Name	Existing Condition	Proposed Condition
06_MH_0101	FB-CB-x2	HCI-CB-x1
08_MH_0044	HC-CB-x1	HCI-CB-x1
08_MH_0046	FB-CB-x1	HCI-CB-x1
08_MH_0048	FB-CB-x1	TFB-CB-x1
J1	HC-CB-x1	HCI-CB-x1
STT-11-ABL	HC-CB-x1	HCI-CB-x1
STT-15-ABL	HC-CB-x1	TFB-CB-x1
VN-10-ABL	HC-CB-x1	HCI-CB-x2